

CRANFIELD UNIVERSITY

DAVID FERNÁNDEZ LÓPEZ-REY

EFFECTIVENESS OF H<sub>2</sub>O<sub>2</sub>/UV AND O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub>/UV FOR  
METALDEHYDE REMOVAL IN DRINKING WATER AND FULL-  
SCALE COSTING ANALYSIS

SCHOOL OF WATER, ENERGY AND ENVIRONMENT

MASTER OF SCIENCE

MSc by Research in Water Science  
Academic Year: 2016 - 2017

Supervisor: Dr Francis Hassard and Prof Bruce Jefferson  
September 2017



CRANFIELD UNIVERSITY

SCHOOL OF WATER, ENERGY AND ENVIRONMENT

MSc by Research in Water Science

Academic Year 2016 - 2017

DAVID FERNÁNDEZ LÓPEZ-REY

EFFECTIVENESS OF H<sub>2</sub>O<sub>2</sub>/UV AND O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub>/UV FOR  
METALDEHYDE REMOVAL IN DRINKING WATER AND FULL-  
SCALE COSTING ANALYSIS

Supervisor: Dr Francis Hassard and Prof Bruce Jefferson  
September 2017

© Cranfield University 2017. All rights reserved. No part of this  
publication may be reproduced without the written permission of the  
copyright owner.



## **DECLARATION**

Chapter 1 comprises a pilot-scale experimental work carried out by Marine Diana and David Fernandez Lopez-Rey as part of two MRes partnership projects between Cranfield University and Severn Trent Water. Despite producing two separate theses, the results reported on that chapter have thus similarities with Diana's research as sample collection and DBPFP laboratory analysis were undertaken by both students. However, data interpretation and analysis, as well as the writing up, were solely done by David Fernandez Lopez-Rey.



## ABSTRACT

Metoldehyde is a widely used pesticide in the UK and has been reported to produce drinking water quality failures across the national water utilities. Advanced Oxidation Processes (AOPs) are effective in the removal of recalcitrant organic constituents but pose (i) high energy and chemical costs and (ii) by-products formation upon disinfection stage. In this context, UV/H<sub>2</sub>O<sub>2</sub> and O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV were tested at pilot-scale concurrently at Draycote water treatment work (WTW) (UK) for metoldehyde degradation and disinfection by products formation potential (DBPFP) at different energy demands (E<sub>D</sub>), H<sub>2</sub>O<sub>2</sub> and O<sub>3</sub> doses; and pesticide concentrations. Whole-life costing analysis (WLCA) was undertaken to assess which AOP was most economic for metoldehyde removal at a Draycote sized WTW. Sensitivity analysis considered potential costs of each AOP. Metoldehyde was removed up to 98% (UV/H<sub>2</sub>O<sub>2</sub>) and 97% (O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV) successfully fulfilling European Directive 98/83/EC below both 1.0 kWh m<sup>-3</sup> and 2.14 µg L<sup>-1</sup> pesticide inlet water level. Net DBPFP contribution ranged -283 µg L<sup>-1</sup> to +255 µg L<sup>-1</sup> for trihalomethanes formation potential (THMFP), which are UK regulated. DBPFP was related to organic background characteristics rather than the operating conditions tested in both AOPs. Cost estimating the AOPs for a 0.72-log metoldehyde removal enabled the total expenditures to be determined indicating that energy consumption accounted for 50% (UV/H<sub>2</sub>O<sub>2</sub>), 49 % (O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV) and 31% (O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub>) of their operating costs. Similar £14.7 million capital costs were appraised for O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> and UV/H<sub>2</sub>O<sub>2</sub>. Overall, O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> sub process outperformed the rest of AOPs when considering both metoldehyde degradation (≤96%) and net DBPFP contribution (≤51 µg L<sup>-1</sup> THMFP) at the most economically operating costs for 5-month yearly treatment (£0.07 m<sup>-3</sup>). Sensitivity analysis showed the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> more efficient process requiring less inputs than UV/H<sub>2</sub>O<sub>2</sub> for the same metoldehyde removal. However, the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> was cost effective at an ideal stoichiometric mass ratio of 0.7 H<sub>2</sub>O<sub>2</sub>:O<sub>3</sub>. Therefore, this would require validation at full-scale. The AOPs were robust for metoldehyde degradation with reasonable costs.

Keywords: Advanced oxidation process, AOP, DBP, THM, HAA, Whole-life costing analysis

## ACKNOWLEDGEMENTS

Firstly, I would like to extend my gratitude and appreciation to Severn Trent Water for financially supporting this research and providing me with the opportunity of personal and professional growth.

Sincere gratitude to my supervisor's Dr Francis Hassard and Prof Bruce Jefferson whose experience, advice and guidance have enriched considerably this thesis. Special acknowledgement goes to Dr Olivier Autin and Prof. Peter Jarvis for accepting me to undertake this challenge one year ago. Thanks all of you for your backup when difficulties arose and your technical input.

I am grateful for having met the Water Science family at Cranfield University. Many thanks to Dr Pablo Campo Moreno, Dr Emma Goslan and lab technicians for your insights and expertise to achieve this outcome within this tight and intense one-year time frame.

I wish to thank my grandparents and friends their help, wisdom or words, love and relief keeping me always strong enough to thrive and never surrender. Thanks for believe in my potential and attain this feat.

Pero... sin duda alguna estoy agradecido y en deuda con mis padres y mi hermano: Juan, Sagrario y Víctor

“...Sólo dos legados duraderos podemos dejar a nuestros hijos: uno, raíces; otro, alas” (Hodding Carter)

Gracias por apoyarnos a volar cada vez más lejos sin ningún miedo. Os quiero mucho, pese a no soler decirlo. Hemos superado, superamos y superaremos todas las dificultades que se nos presenten juntos, aunque físicamente separados por miles de km. Contad siempre conmigo, aunque esté lejos...



# TABLE OF CONTENTS

|                                                                                                                                                                                                                                                                                          |      |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|
| DECLARATION .....                                                                                                                                                                                                                                                                        | i    |
| ABSTRACT .....                                                                                                                                                                                                                                                                           | iii  |
| ACKNOWLEDGEMENTS.....                                                                                                                                                                                                                                                                    | v    |
| LIST OF FIGURES.....                                                                                                                                                                                                                                                                     | ix   |
| LIST OF TABLES .....                                                                                                                                                                                                                                                                     | x    |
| LIST OF EQUATIONS.....                                                                                                                                                                                                                                                                   | xiii |
| LIST OF ABBREVIATIONS .....                                                                                                                                                                                                                                                              | xiv  |
| 1 INTRODUCTION.....                                                                                                                                                                                                                                                                      | 15   |
| 1.1 Background.....                                                                                                                                                                                                                                                                      | 15   |
| 1.2 Aims and objectives .....                                                                                                                                                                                                                                                            | 19   |
| 2 SUCCEEDING METALDEHYDE AND DISINFECTION BY-PRODUCTS<br>COMPLIANCE LEVELS IN SURFACE DRINKING WATER BODIES BY<br>O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> + H <sub>2</sub> O <sub>2</sub> /UV AND UV/H <sub>2</sub> O <sub>2</sub> .....                                           | 20   |
| Abstract.....                                                                                                                                                                                                                                                                            | 20   |
| 2.1 Introduction .....                                                                                                                                                                                                                                                                   | 21   |
| 2.2 Methodology .....                                                                                                                                                                                                                                                                    | 24   |
| 2.2.1 Pilot plant and operating conditions .....                                                                                                                                                                                                                                         | 24   |
| 2.2.2 Chemical reagents .....                                                                                                                                                                                                                                                            | 25   |
| 2.2.3 Experimental procedure .....                                                                                                                                                                                                                                                       | 26   |
| 2.2.4 Analytical methods .....                                                                                                                                                                                                                                                           | 28   |
| 2.2.5 Statistical methods .....                                                                                                                                                                                                                                                          | 29   |
| 2.3 Results and discussion .....                                                                                                                                                                                                                                                         | 31   |
| 2.3.1 Effectiveness of ozone and UV-based AOPs for metaldehyde<br>removal .....                                                                                                                                                                                                          | 31   |
| 2.3.2 Impact of the operating conditions on metaldehyde removal .....                                                                                                                                                                                                                    | 34   |
| 2.3.3 Optimum conditions to achieve the statutory limits for metaldehyde<br>residual at the minimum supply of inputs .....                                                                                                                                                               | 36   |
| 2.3.4 Influence of TCMs on metaldehyde removal by UV/H <sub>2</sub> O <sub>2</sub> .....                                                                                                                                                                                                 | 39   |
| 2.3.5 Disinfection by-product formation potential (DBPFP) by ozone and<br>UV-based advanced oxidation processes .....                                                                                                                                                                    | 42   |
| 2.4 Conclusions .....                                                                                                                                                                                                                                                                    | 46   |
| 2.5 Acknowledgments.....                                                                                                                                                                                                                                                                 | 47   |
| 2.6 References .....                                                                                                                                                                                                                                                                     | 47   |
| 3 ECONOMIC EVALUATION OF UV/H <sub>2</sub> O <sub>2</sub> , O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> , AND O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> +<br>H <sub>2</sub> O <sub>2</sub> /UV PROCESSES THROUGH A WHOLE-LIFE COSTING ANALYSIS<br>FOR FULL-SCALE APPLICATION ..... | 55   |
| Abstract.....                                                                                                                                                                                                                                                                            | 55   |
| 3.1 Introduction .....                                                                                                                                                                                                                                                                   | 56   |
| 3.2 Cost estimation methodology.....                                                                                                                                                                                                                                                     | 58   |
| 3.2.1 Procedure for OPerating Expenses (OPEX) calculation.....                                                                                                                                                                                                                           | 60   |

|                                                                   |    |
|-------------------------------------------------------------------|----|
| 3.2.2 Procedure for CAPital EXpenditures (CAPEX) calculation..... | 64 |
| 3.3 Results and discussion .....                                  | 66 |
| 3.4 Conclusions .....                                             | 73 |
| 3.5 Acknowledgments.....                                          | 75 |
| 3.6 References .....                                              | 75 |
| 4 CONCLUSIONS.....                                                | 81 |
| REFERENCES.....                                                   | 83 |
| APPENDICES .....                                                  | 87 |

## LIST OF FIGURES

|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |    |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|
| Figure 1 Flow diagram of UV/H <sub>2</sub> O <sub>2</sub> and O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> + H <sub>2</sub> O <sub>2</sub> /UV pilots at Draycote WTW. SP: sample point.....                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 25 |
| Figure 2 Net metaldehyde removal (%) contour plot regardless the initial concentration of pesticide and including all the operating conditions tested in the pilot-trial (n) by (a) UV/H <sub>2</sub> O <sub>2</sub> (n = 127), (b) O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> (n = 50) and (c) H <sub>2</sub> O <sub>2</sub> /UV (n = 31). Black points represent sampled data. Contour represents interpolation of data between measured points according to <i>SigmaPlot 11</i> . .....                                                                                                                                                                                 | 32 |
| Figure 3 (a) Minimum O <sub>3</sub> concentration per H <sub>2</sub> O <sub>2</sub> dose (O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> ) and (b) minimum H <sub>2</sub> O <sub>2</sub> dose per UV energy demand (H <sub>2</sub> O <sub>2</sub> /UV) at <0.5 to 2.14 µg L <sup>-1</sup> MICs based on benchmark concentration adopted from 0.1 µg L <sup>-1</sup> PCV for individual pesticides (European Parliament, 1998) through the O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> + H <sub>2</sub> O <sub>2</sub> /UV process. Other conditions also achieved < 0.1 µg L <sup>-1</sup> pesticide degradation, but required more chemical and are therefore excluded..... | 38 |
| Figure 4 Minimum H <sub>2</sub> O <sub>2</sub> dose per UV energy demand at <0.5-2.14 µg L <sup>-1</sup> MICs based on benchmark concentration adopted from 0.1 µg L <sup>-1</sup> PCV for individual pesticides (European Parliament, 1998) through the UV/H <sub>2</sub> O <sub>2</sub> process Other conditions also achieved < 0.1 µg L <sup>-1</sup> pesticide degradation, but required more H <sub>2</sub> O <sub>2</sub> and are therefore excluded.....                                                                                                                                                                                                              | 39 |
| Figure 5 Normalized residual metaldehyde concentration profiles regarding control tests and UV/H <sub>2</sub> O <sub>2</sub> full treatment in (a) kaolin-turbid UP water and (b) HA-turbid UP water at different concentrations of TCMS .....                                                                                                                                                                                                                                                                                                                                                                                                                                | 42 |
| Figure 6 Net contribution of the stand-alone UV/ H <sub>2</sub> O <sub>2</sub> , and the O <sub>3</sub> / H <sub>2</sub> O <sub>2</sub> + H <sub>2</sub> O <sub>2</sub> /UV on (a) THMFP (n = 66) and (b) HAAFP (n = 48) based on the day of pilot-scale work.....                                                                                                                                                                                                                                                                                                                                                                                                            | 45 |
| Figure 7 Net contribution of the O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> and H <sub>2</sub> O <sub>2</sub> /UV sub treatments on DBPFP .....                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | 46 |
| Figure 8 Breakdown of the operating expenses (OPEX) and capital expenses (CAPEX) for a UV/H <sub>2</sub> O <sub>2</sub> ; O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> + H <sub>2</sub> O <sub>2</sub> /UV and O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> 25 MLD DW treatment plant reducing metaldehyde levels <0.1 µg L <sup>-1</sup> .....                                                                                                                                                                                                                                                                                                                             | 71 |
| Figure 9 Influence of prices inflation in terms of (a) energy (b) H <sub>2</sub> O <sub>2</sub> and (c) LOX on the TOTEX of UV/H <sub>2</sub> O <sub>2</sub> ( ) and O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> ( ) to reach the cost neutral point between both treatments .....                                                                                                                                                                                                                                                                                                                                                                                          | 73 |

## LIST OF TABLES

|                                                                                                                                                                                                          |    |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|
| Table 1 Treatability studies on metaldehyde removal .....                                                                                                                                                | 22 |
| Table 2 Operating conditions.....                                                                                                                                                                        | 25 |
| Table 3 Range of kaolin concentrations assessed for metaldehyde removal at 2 $\mu\text{g L}^{-1}$ metaldehyde initial concentration under UV/H <sub>2</sub> O <sub>2</sub> .....                         | 28 |
| Table 4 Range of humic acid concentrations assessed for metaldehyde removal at 2 $\mu\text{g L}^{-1}$ metaldehyde initial concentration under UV/H <sub>2</sub> O <sub>2</sub> .....                     | 28 |
| Table 5 Optimum set of experimental conditions at pilot-scale achieved the best metaldehyde removal (%).....                                                                                             | 34 |
| Table 6 Minimum $E_D$ and their associated minimum oxidant doses tested producing metaldehyde-compliant water at dissimilar ranges of metaldehyde inlet concentrations (MICs) .....                      | 37 |
| Table 7 Summary of operating conditions and results of metaldehyde degradation bench-scale experiments applying UV/H <sub>2</sub> O <sub>2</sub> process .....                                           | 40 |
| Table 8 Net contribution of the AOPs on THMFP and HAAFP using minimum oxidant doses per UV ( $E_D$ ) for metaldehyde-compliant water production at different metaldehyde (M) spiking doses .....         | 45 |
| Table 9 Location Factors of different countries relative to USA Gulf Coast for prices update based on 2003 data (Towler and Sinnott, 2012) .....                                                         | 60 |
| Table 10 Assumptions for OPEX and CAPEX costing analysis from treatability studies and supplier information .....                                                                                        | 63 |
| Table 11 AOP treatment conditions tested in the research achieving <0.1 $\mu\text{g L}^{-1}$ metaldehyde and associated OPEX relating to such conditions.....                                            | 68 |
| Table 12 Estimated capital expenditures for metaldehyde treatment using commercial UV and O <sub>3</sub> -based AOPs .....                                                                               | 72 |
| Table A-1 UV/H <sub>2</sub> O <sub>2</sub> process conditions, flow rate, metaldehyde inlet concentration (MIC) and metaldehyde removal after treatment.....                                             | 87 |
| Table A-2 O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> process conditions, flow rate, metaldehyde inlet concentration (MIC) and metaldehyde removal after treatment .....                               | 93 |
| Table A-3 H <sub>2</sub> O <sub>2</sub> /UV process conditions, metaldehyde inlet concentration (MIC), in this case the residual from the peroxone process, and metaldehyde removal after treatment..... | 95 |
| Table B-1 Individual influence of predictors on metaldehyde removal with $n=125$ residual degrees of freedom according to the DistLM marginal test .....                                                 | 97 |

|                                                                                                                                                            |     |
|------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|
| Table B-2 Sequential DistLM test of the predictors explaining metaldehyde removal.....                                                                     | 98  |
| Table B-3 Individual influence of predictors on metaldehyde removal with $n=62$ residual degrees of freedom according to the DistLM marginal test .....    | 98  |
| Table B-4 Sequential DistLM test of the predictors explaining metaldehyde removal.....                                                                     | 98  |
| Table B-5 Individual influence of predictors on metaldehyde removal with $n=48$ residual degrees of freedom according to the DistLM marginal test .....    | 99  |
| Table B-6 Sequential DistLM test of the predictors explaining metaldehyde removal.....                                                                     | 99  |
| Table B-7 Individual influence of predictors on metaldehyde removal with $n=29$ residual degrees of freedom according to the DistLM marginal test .....    | 100 |
| Table B-8 Sequential DistLM test of the predictors explaining metaldehyde removal.....                                                                     | 100 |
| Table C-1 Individual influence of predictors on net THMFP contribution with $n=25$ residual degrees of freedom according to the DistLM marginal test ..... | 101 |
| Table C-2 Sequential DistLM test of the predictors explaining net THMFP contribution .....                                                                 | 102 |
| Table C-3 Individual influence of predictors on net THMFP contribution with $n=37$ residual degrees of freedom according to the DistLM marginal test ..... | 102 |
| Table C-4 Sequential DistLM test of the predictors explaining net THMFP contribution .....                                                                 | 103 |
| Table C-5 Individual influence of predictors on net THMFP contribution with $n=37$ residual degrees of freedom according to the DistLM marginal test ..... | 103 |
| Table C-6 Sequential DistLM test of the predictors explaining net THMFP contribution .....                                                                 | 104 |
| Table C-7 Individual influence of predictors on net THMFP contribution with $n=18$ residual degrees of freedom according to the DistLM marginal test ..... | 104 |
| Table C-8 Sequential DistLM test of the predictors explaining net THMFP contribution .....                                                                 | 105 |
| Table C-9 Individual influence of predictors on net HAAFP contribution with $n=21$ residual degrees of freedom according to the DistLM marginal test ..... | 105 |
| Table C-10 Sequential DistLM test of the predictors explaining net HAAFP contribution .....                                                                | 106 |
| Table C-11 Individual influence of predictors on net HAAFP contribution with $n=23$ residual degrees of freedom according to the DistLM marginal test..... | 106 |

|                                                                                                                                                       |     |
|-------------------------------------------------------------------------------------------------------------------------------------------------------|-----|
| Table C-12 Sequential DistLM test of the predictors explaining net HAAFP contribution .....                                                           | 107 |
| Table C-13 Individual influence of predictors on net HAAFP contribution with $n=21$ residual degrees of freedom according to the DistLM marginal test | 107 |
| Table C-14 Sequential DistLM test of the predictors explaining net HAAFP contribution .....                                                           | 108 |
| Table C-15 Individual influence of predictors on net HAAFP contribution with $n=11$ residual degrees of freedom according to the DistLM marginal test | 108 |
| Table C-16 Sequential DistLM test of the predictors explaining net HAAFP contribution .....                                                           | 109 |

**LIST OF EQUATIONS**

(3-1).....60

(3-2).....60

(3-3).....62

(3-4).....62

## LIST OF ABBREVIATIONS

|            |                                     |
|------------|-------------------------------------|
| 2,4-D      | 2,4-dichlorophenoxyacetic acid      |
| AOP        | Advanced Oxidation Process          |
| BCAA       | Bromochloroacetic acid              |
| BDCAA      | Bromodichloroacetic acid            |
| CAPEX      | CAPital EXpenditures                |
| CDBAA      | Chlorodibromoacetic acid            |
| DBAA       | Dibromoacetic acid                  |
| DBP        | Disinfection by-product             |
| DBPFP      | DBP formation potential             |
| DCAA       | Dichloroacetic acid                 |
| DistLM     | Distance-based linear model         |
| DOC        | Dissolved Organic Carbon            |
| DrWPA      | Drinking Water Protected Areas      |
| DW         | Drinking water                      |
| DWI        | Drinking Water Inspectorate         |
| $E_D$      | Energy demand                       |
| $EE_o$     | Electrical energy per order         |
| EPA        | USA Environmental Protection Agency |
| EU         | European Union                      |
| FBBR       | Fluidised bed bioreactors           |
| GAC        | Granular activated carbon           |
| $H_2O_2$   | Hydrogen peroxide                   |
| HA         | Humic acid                          |
| HAA        | Haloacetic acid                     |
| HAAFP      | HAA formation potential             |
| LOX        | Liquid oxygen                       |
| LPHO       | Low-pressure high-output            |
| MBAA       | Monobromoacetic acid                |
| MCAA       | Monochloroacetic acid               |
| MIC        | Metaldehyde inlet concentration     |
| $Na_2SO_3$ | Sodium sulphite                     |
| NOM        | Natural Organic Matter              |
| NTU        | Nephelometric Turbidity Units       |
| $O_3$      | Ozone                               |

|          |                               |
|----------|-------------------------------|
| •OH      | Hydroxyl radical              |
| OPEX     | OPerating Expenses            |
| PCV      | Permitted concentration value |
| RGF      | Rapid gravity filter          |
| TCM      | Turbidity causing material    |
| TBAA     | Tribromoacetic acid           |
| TCAA     | Trichloroacetic acid          |
| THM      | Trihalomethane                |
| THMFP    | THM formation potential       |
| TOC      | Total Organic Carbon          |
| TOTEX    | TOfal EXpenditures            |
| UP       | Ultrapure                     |
| UV       | Ultra Violet                  |
| UV254 nm | UV absorbance at 254 nm       |
| WLCA     | Whole-Life Costing Analysis   |
| WTW      | Water treatment work          |



# 1 INTRODUCTION

## 1.1 Background

The wholesome supply of drinking water (DW) is threatened from anthropogenic influences such as the application of pesticides to farmland. These pesticides or their degradation products can result in a public health risk and adverse environmental consequences, even at  $\mu\text{g}$  per litre range concentrations (PMEP, 1993; James, Germain and Judd, 2014). One such example is the pesticide metaldehyde, which is considered a pollutant of concern in the UK water sector (Cooper, 2011). Recent investigations showed that 20% of Drinking Water Protected Areas (DrWPA) in England and Wales were at risk due to metaldehyde (Pesticides Forum, 2015). Water suppliers are responsible for providing potable water meeting the Regulations under Section 68(1)(a) of the Water Industry Act 1991 and the requirement set in regulation 4(2)(c) of The Water Supply (Water Quality) Regulations 2000 (DWI, 2000). However, the majority of failures for DW non-compliance in the UK water sector are linked to metaldehyde concentrations (DWI, 2014). In addition, the compliance with the residual UK/EU statutory permitted concentration value (PCV) of  $0.1 \mu\text{g L}^{-1}$  and  $0.5 \mu\text{g L}^{-1}$  for individual and total pesticides, respectively (European Parliament, 1998) is often not achievable with metaldehyde levels regularly reaching  $>0.1 \mu\text{g L}^{-1}$  in source waters (Kay and Grayson, 2014). These high concentrations are due to the low organic carbon sorption coefficient of metaldehyde, resulting in not only high mobility in the environment, but also reported persistency half-life up to 223 days (Kay and Grayson, 2014). Therefore, metaldehyde peak concentrations are found around the time of their application. In the UK, metaldehyde is typically applied in October-December, extending to September-February (Kay and Grayson, 2014). The magnitude of this seasonal issue is exacerbated since this molluscicide bait, used to control gastropods for a wide variety of crops, is non-readily removed by the current water treatment technologies, such as granular activated carbon (GAC) beds (Autin *et al.*, 2012; Tang *et al.*, 2016) and ozone (Comninellis *et al.*, 2008). GAC is the most common treatment applied for removing other pesticides from raw water (Westerhoff *et al.*, 2005) due to the wide-scale applicability,

effectiveness and relatively low cost (Tang *et al.*, 2016). However, GAC processes are ineffective at removing polar pesticides such as metaldehyde over long time scales (Semitoglou-Tsiapou *et al.*, 2016). Metaldehyde has low adsorption capacity onto GAC (IPCS, 1999; UKWIR, 2011) and was found to bypass GAC systems which limited the removal efficiency to 30-50%, with an estimated bed life of <44 days if the media was not regenerated (Tao and Fletcher, 2016). Therefore, regeneration costs associated to maintain performance for metaldehyde removal using GAC treatment are currently unfeasible (Autin *et al.*, 2012; Castle *et al.*, 2017).

Under this challenging landscape, chemical oxidation processes by means of different technologies, *e.g.* ozonation, UV-based, electrolysis, Fenton-related, solar visible irradiation or ultrasound irradiation (Comninellis *et al.*, 2008), have been studied with the aim of effectively removing recalcitrant pollutants such as metaldehyde from source waters (Roche and Prados, 1995; Özcan *et al.*, 2010; Tizaoui *et al.*, 2011; Despotović *et al.*, 2012; Jefferson *et al.*, 2016; Semitsoglou-Tsiapou *et al.*, 2016; Martinez, Delgado and Jarvis, 2016). Some water companies have alternatively decided to embrace catchment measures to reduce the risk of supply water polluted by pesticides (DWI, 2016). Catchment management is a potential option to address metaldehyde contamination problem. Nevertheless, it is unlikely to provide a stand-alone solution. This is because of the variable efficacy of catchment management operations subjected to uncertainties caused by such factors as rainfall patterns, ineffective understanding of the contaminant pathways from the source to waters, resistance of pests to alternative pesticides and human error (Reichenberger, 2007). Moreover, these practices are beyond water suppliers' control since they often do not have ownership of the land or decision making for that land to which pesticides are applied (Dolan, 2013). Also, regulating metaldehyde application would likely create pollution swapping derived from the alternative active substances (Dolan *et al.*, 2014). Therefore, 'end-of-pipe' treatments for metaldehyde removal are likely to represent the ultimate barrier to prevent consumption of waters laden with metaldehyde concentration  $>0.1 \mu\text{g L}^{-1}$ . However, the implementation of promising advanced oxidation processes (AOPs)

for metaldehyde degradation present two main limitations: the high energy and chemical demand, and the formation of unwanted treatment by-products (Autin *et al.*, 2012; James, Germain and Judd, 2014; Kim and Zoh, 2016; Collins and Bolton, 2016). In this study, a pilot trial was undertaken to investigate UV/H<sub>2</sub>O<sub>2</sub> and O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV performance (collectively AOPs) to reliably advise full-scale implementation costs based on the optimisation of the key performance parameters: UV, H<sub>2</sub>O<sub>2</sub> and O<sub>3</sub>. This allows an overall benchmarking between treatments through AOPs.

This thesis consequently is formatted in two chapters as papers for publication. Chapter 1 focuses on the pilot, lab-scale experimental work and the results for the removal of metaldehyde and disinfection by-products (DBPs) formation potential (DBPFP). Chapter 2 explores the economic viability of AOPs for metaldehyde removal and compares the costs of the treatments assessed in this project (H<sub>2</sub>O<sub>2</sub>/UV, O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> and O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV) which are currently commercially available technologies.



## 1.2 Aims and objectives

This research aimed to determine the effectiveness and cost of  $\text{H}_2\text{O}_2/\text{UV}$  and  $\text{O}_3/\text{H}_2\text{O}_2 + \text{H}_2\text{O}_2/\text{UV}$  AOPs for the removal of the recalcitrant pesticide metaldehyde to levels that are deemed acceptable. Moreover, the economic evaluation considered a trade-off between the optimum operating conditions to remove metaldehyde, to limit DBPFP levels from the inlet and to minimise the whole-life costs using real surface waters. To explore potential matrix effects on treatment performance, a bench scale experiment was intended to investigate the influence of turbidity causing materials (TCMs) such as kaolin and humic acid (HA) on the removal of metaldehyde within the  $\text{H}_2\text{O}_2/\text{UV}$  treatment.

In order to achieve this aim, the objectives were developed:

- To test and evaluate the technologies for metaldehyde removal under different reagents doses and UV fluences, sampling from commercially available  $\text{H}_2\text{O}_2/\text{UV}$  and  $\text{O}_3/\text{H}_2\text{O}_2 + \text{H}_2\text{O}_2/\text{UV}$  pilot-scale reactors
- To assess the influence of TCMs on the removal of metaldehyde
- To compare the metaldehyde removal efficiency of both AOPs according to the cost per  $\text{m}^3$  treated
- To determine the optimum energy demand ( $E_D$ ) ( $\text{kWh m}^{-3}$ ),  $\text{H}_2\text{O}_2$  ( $\text{mg L}^{-1}$ ) and  $\text{O}_3$  ( $\text{mg L}^{-1}$ ) doses for each technology to respectively achieve the statutory limits of metaldehyde in DW and to attain the lowest DBPFP. The cost of these processes is considered with respect to CAPital EXpenditures (CAPEX) and OPerating Expenses (OPEX) using a Whole-Life Costing Analysis (WLCA)

## 2 SUCCEEDING METALDEHYDE AND DISINFECTION BY-PRODUCTS COMPLIANCE LEVELS IN SURFACE DRINKING WATER BODIES BY O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV AND UV/H<sub>2</sub>O<sub>2</sub>

David Fernandez Lopez-Rey<sup>1</sup>, Marine Diana<sup>1</sup>, Bruce Jefferson<sup>1</sup>, Peter Jarvis<sup>1</sup>  
Hassard Francis<sup>1</sup>

<sup>1</sup>*Cranfield Water Science Institute, Cranfield University, Bedford, MK43 0AL.*

### Abstract

The efficacy of UV, H<sub>2</sub>O<sub>2</sub> and O<sub>3</sub> for the removal of metaldehyde and disinfection by products formation potential (DBPFP) was investigated at pilot-scale using UV/H<sub>2</sub>O<sub>2</sub> and O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV advanced oxidation processes (AOPs) concurrently. Both AOPs degraded up to 98% metaldehyde from inlet metaldehyde concentrations of  $\leq 2.14 \mu\text{g L}^{-1}$  and  $< 1.0 \text{ kWh m}^{-3}$  to meet the stringent European Directive 98/83/EC. The highest oxidants and energy demands (E<sub>D</sub>) yielded the greatest metaldehyde removals in both technologies. O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> removed the majority of the metaldehyde in the UV/H<sub>2</sub>O<sub>2</sub> and O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> system, up to 96%, depending on the operating conditions. However, the treated water from the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> was above the  $0.1 \mu\text{g L}^{-1}$  benchmark concentration adopted from the European Directive 98/83/EC for metaldehyde inlet concentration (MIC)  $> 0.14 \mu\text{g L}^{-1}$ . A bench-scale study revealed UV/H<sub>2</sub>O<sub>2</sub> effectiveness for metaldehyde removal was reduced in organic-enriched water matrices which had a turbidity  $> 1.0$  Nephelometric Turbidity Units (NTU). This was due to competition between organic compounds and metaldehyde for hydroxyl radicals ( $\bullet\text{OH}$ ). The AOPs also produced trihalomethanes (THMs) compliant water yielding net THM formation potential (THMFP) between  $-283 \mu\text{g L}^{-1}$  to  $+255 \mu\text{g L}^{-1}$ . Net haloacetic acid (HAA) formation potential (HAAFP) after the AOP varied from  $-164 \mu\text{g L}^{-1}$  to  $+131 \mu\text{g L}^{-1}$ . Natural organic matter (NOM) characteristics were found to be more important for DBPFP than the operating conditions tested in this study and metaldehyde concentrations in the inlet water.

Keywords: advanced oxidation process, DBP, haloacetic acid, pesticide, trihalomethane

## 2.1 Introduction

Advanced oxidation processes (AOPs) are characterised by the generation of highly reactive, non-selective hydroxyl radicals ( $\bullet\text{OH}$ ) able to oxidise and degrade organic compounds treating simultaneously a variety of contaminants (Oturán and Aaron, 2014; Collins and Bolton, 2016) such as antibiotics (Lester *et al.*, 2011) and pesticides, e.g. metaldehyde, clopyralid or mecoprop (Autin *et al.*, 2012; Martínez, Delgado and Jarvis, 2016). Extensive research has also been undertaken to evaluate the performance of AOPs for the reduction of persistent organic constituents from waters, including disinfection by-products (DBPs) precursors, not achievable through conventional technologies such as coagulation (Chin and Bérubé, 2005; Toor and Mohseni, 2007; Sarathy and Mohseni, 2010; Bond *et al.*, 2011). The molluscicide metaldehyde is widely used across the UK-residential and agricultural sector, being recognised one of the major causes for failing to achieve pesticide water-quality standards set in European Directive 98/83/EC (DWI, 2014). A number of pilot-scale and bench-scale experiments have been conducted, at different oxidant doses and/or UV fluences, to assess the effectiveness of AOPs to reduce metaldehyde concentration in water (Table 1). Anglian Water treated filtered water through the  $\text{O}_3/\text{H}_2\text{O}_2$  process using a pilot-scale reactor and achieved a 0.7-log reduction of metaldehyde. In this peroxone trial, an initial concentration of  $10 \text{ mg L}^{-1} \text{ O}_3$  was typically applied (Collins and Bolton, 2016). The variety of combined radiation and oxidant doses suggest the importance of correct chemical and energy dosing to target metaldehyde. Moreover, some authors have stated that an excess of oxidants over the optimal concentration affect the AOP removal performance through hydroxyl scavenging (Lucas, Peres and Li Puma, 2010; Autin *et al.*, 2012). In contrast, deficient UV and/or oxidant doses led to greater production of DBPs (Sarathy *et al.* 2011), which is one of the main limitations of AOP full-scale implementation (Collins and Bolton, 2016). DBPs are formed through the reaction between natural organic matter (NOM), iodide, anthropogenic contaminants, and

bromide with disinfectants, such as chlorine. Among the different DBPs, haloacetic acids (HAAs) are regulated in the USA whilst trihalomethanes (THMs) are regulated in the EU and the USA. In the EU, total THMs should not exceed 100  $\mu\text{g L}^{-1}$  in tap water (European Parliament, 1998; DWI, 2000) and a risk assessment to control DBPs when exceeding 50  $\mu\text{g L}^{-1}$  THMs (Jefferson *et al.*, 2016) was outlined in Regulation 26.1(a) of The Water Supply Regulations 2010 (DWI, 2010). The USA has established more stringent treated water standards of 80  $\mu\text{g L}^{-1}$  for total THMs and 60  $\mu\text{g L}^{-1}$  for HAAs (EPA, 2017).

**Table 1** Treatability studies on metaldehyde removal

| MIC<br>( $\mu\text{g L}^{-1}$ ) | Removal<br>rate | Experimental<br>conditions | UV<br>fluences<br>( $\text{mJ cm}^{-2}$ ) | $\text{H}_2\text{O}_2$<br>( $\text{mg L}^{-1}$ ) | $\text{O}_3$<br>( $\text{mg L}^{-1}$ ) | Reference                                 |
|---------------------------------|-----------------|----------------------------|-------------------------------------------|--------------------------------------------------|----------------------------------------|-------------------------------------------|
| 1000                            | 95%             | Laboratory<br>scale        | 600                                       | 272                                              | N/A                                    | Autin <i>et al.</i> (2012)                |
| 0.2                             | >90%            |                            | >2000                                     | >2                                               |                                        | James, Germain and Judd (2014)            |
| 300                             | 97%             |                            | 1000                                      | 15                                               |                                        | Semitsoglo u-Tsiapou <i>et al.</i> (2016) |
| 0.5                             | 72%<br>90%      | Pilot plant                | N/A<br>1200                               | 16-22<br>16-22                                   | 8<br>8                                 | Tang <i>et al.</i> (2016)                 |

MIC: metaldehyde inlet concentration

The presence of background organic constituents, *e.g.* humic substances, proteins, carboxylic acids, carbonate and bicarbonate ions (Chin and Bérubé, 2005; Kim and Yu, 2005; Baghoth, Sharma and Amy, 2011) in water play a key role not only on the formation of DBPs (Richardson, 2007) but in the pollutant removal success of AOPs (Autin *et al.*, 2013a, Carra *et al.* 2016). NOM interferes with the degradation of metaldehyde using AOPs through  $\bullet\text{OH}$  scavenging (Crittenden *et al.*, 2012; Autin *et al.*, 2013a). Hence, elevated UV fluences are required to attain necessary pesticide removal (Jefferson *et al.* 2016). NOM in conjunction with other suspended particles in water, *e.g.* clay, fine inorganic colloids, influences water quality parameters such as turbidity, an optical property related with light scattering and light absorption (Wang and Hsieh, 2001; Parsons and Jefferson, 2006). Humic acids (HA) represent a significant fraction of the

NOM chemical composition (Croue, Korshin and Benjamin, 2000; Carra *et al.* 2016), up to one-half of the dissolved organic carbon (DOC) (Kim and Yu, 2005), and pollutants are able to bind strongly in such a way that adversely affect their degradation in AOPs (Hollrigl-Rosta *et al.*, 2003). The negative effect of pesticides degradation via photo-Fenton process as a result of the  $\bullet\text{OH}$  quenching process and UV light screening by increasing HA concentration has been reported (Farré *et al.*, 2007; Carra *et al.* 2016). However, it is important to elucidate whether inorganic matter also weighs when degrading a target compound. The influence of kaolin clay on the photocatalytic oxidation of 2,4-dichlorophenoxyacetic acid (2,4-D) has been investigated (Giri *et al.*, 2010). The authors concluded that UV shielding from kaolin concentration did not influence 2,4-D removal. Similarly, photocatalytic degradation efficiency of HA in kaolin-turbid water has been tested (Sen Kavurmaci and Bekbolet, 2014), reporting an insignificant effect of the clay mineral in the process.

The robustness of AOPs to decrease organic compounds in water has been discussed (Chin and Bérubé, 2005; Murray *et al.*, 2007; Toor and Mohseni, 2007; Sarathy and Mohseni, 2010; Lamsal *et al.*, 2011; Jefferson *et al.*, 2016). Therefore, the reduction in the formation of DBPs and the removal of metaldehyde is expected provided that adequate oxidants doses and UV fluences are applied (Sarathy *et al.* 2011). For those DBPs generated after AOPs, granular activated carbon (GAC) can subsequently be applied to adsorb them (Kawamura, 2000).

The objective of this work was to critically assess the effectiveness of  $\text{H}_2\text{O}_2/\text{UV}$  and  $\text{O}_3/\text{H}_2\text{O}_2 + \text{H}_2\text{O}_2/\text{UV}$  for metaldehyde degradation under different reagents doses and UV fluences ( $E_D$ ) in pilot-scale AOP reactors. It also addressed the influence of turbidity causing materials (TCMs) for metaldehyde removal under the  $\text{UV}/\text{H}_2\text{O}_2$  process. Equally, the research evaluated the impact of the treatment conditions on the DBPs formation potential (DBPFP). Finally, the optimization of the AOPs, depending on MIC, was studied to comply the European Directive 98/83/EC in terms of both metaldehyde and DBPs.

## 2.2 Methodology

### 2.2.1 Pilot plant and operating conditions


Two pilot-scale AOP plants (Figure 1) were fed with post Rapid Gravity Filtration water (RGF), originally from Draycote water reservoir, and were installed in independent shipping containers at Draycote water treatment work (WTW) (Warwickshire, UK). The UV/H<sub>2</sub>O<sub>2</sub> process comprised a flow-through UV stainless steel pressurized reactor (TrojanUVPhox™, Model 8AL20 oxidation system) providing nominal treatment to 1-5 m<sup>3</sup> h<sup>-1</sup> of water and equipped with 8 low-pressure high-output (LPHO) amalgam lamps (~12,000 h lifespan) and 3.38m L x 1.32m W x 1.93m H physical dimensions. The O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV process was from WEDECO, Xylem Water Solutions UK Ltd. and comprised an ozone generator (GSO3O) (0.80m L x 0.80m W x 0.3m H) supplied with liquid oxygen (LOX) 100 g h<sup>-1</sup> nominal capacity production and 0.5 bar (g) operating pressure; an injection and reaction system (PRO<sub>3</sub>MIX-MiPRO), and a flow-through UV system (LBX 10). The UV reactor (2.90m L x 0.95m W x 1.38m H) worked in the nominal range 0.5-4 m<sup>3</sup> h<sup>-1</sup> and was equipped with 3 Spektrotherm® LPHO (~12,000 h lifespan). As two pilot UV reactors from different suppliers were used in this research, from now on the UV/H<sub>2</sub>O<sub>2</sub> process refers to the Trojan unit, so does H<sub>2</sub>O<sub>2</sub>/UV process to the Xylem model.

Post RGF water, hereinafter referred to as inlet water, was spiked with metaldehyde from a 100 mg L<sup>-1</sup> stock solution contained in a tank with a motorised agitator. The stock solution was diluted in water to reach the concentration required, as different MICs were required at a number of operating conditions assessed (Table 2). All the operating conditions are displayed in Appendix A. H<sub>2</sub>O<sub>2</sub> was dosed upstream of the UV reactor (UV/H<sub>2</sub>O<sub>2</sub>) and the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> reactor system (O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV), respectively with static mixers. Outlets from both treatments were subsequently filtered by separate GAC contactors. Sodium sulphite (Na<sub>2</sub>SO<sub>3</sub>) was also used to quench the residual H<sub>2</sub>O<sub>2</sub>.

**Table 2** Operating conditions

| Treatment                                                          | Metaldehyde spiking dose ( $\mu\text{g L}^{-1}$ ) | Flow rate ( $\text{m}^3 \text{h}^{-1}$ ) | $[\text{H}_2\text{O}_2]$ ( $\text{mg L}^{-1}$ ) | $[\text{O}_3]$ ( $\text{mg L}^{-1}$ ) | Energy demand ( $E_D$ ) ( $\text{kWh m}^{-3}$ ) |
|--------------------------------------------------------------------|---------------------------------------------------|------------------------------------------|-------------------------------------------------|---------------------------------------|-------------------------------------------------|
| $\text{O}_3/\text{H}_2\text{O}_2 + \text{H}_2\text{O}_2/\text{UV}$ | Raw water, 0.5 and 2                              | 0.6-2.5                                  | 8-30                                            | 2-10                                  | 0-1.10                                          |
| $\text{UV}/\text{H}_2\text{O}_2$                                   |                                                   | 2.0-3.5                                  | 10-45                                           | N/A                                   | 0.35-1.00                                       |

N/A: not applicable

**Figure 1** Flow diagram of  $\text{UV}/\text{H}_2\text{O}_2$  and  $\text{O}_3/\text{H}_2\text{O}_2 + \text{H}_2\text{O}_2/\text{UV}$  pilots at Draycote WTW. SP: sample point

### 2.2.2 Chemical reagents

For pilot studies,  $100 \text{ mg L}^{-1}$  metaldehyde (99 wt. %) stock solution (CAS: 9002-91-9, Sigma-Aldrich, UK) was prepared in ultrapure (UP) water (resistivity  $18.2 \text{ M}\Omega \text{ cm}^{-1}$ , TOC  $<3 \text{ ppb}$ , PURELAB®Ultra, UK) and stored at  $5^\circ\text{C}$  until delivery to the pilot units. The concentration of metaldehyde was assessed by Liquid Chromatography - tandem Mass Spectrometry prior to operating experiments.  $\text{H}_2\text{O}_2$  (35 wt. %) (CAS: 7722-84-1, Fisher Scientific, UK) and sodium sulphite anhydrous (CAS: 7757-83-7, Fisher, UK) were also purchased. For lab-scale

TCM experiments, Kaolin clay – light washed with acid (CAS: 1332-58-7, Fisher, UK) and Humic Acid sodium salt (H16752, Aldrich, UK) were used. For DBPs analysis, sodium hypochlorite (10-15%) active chlorine (CAS: 7681-52-9), sodium sulphate (99%) anhydrous (CAS: 7757-82-6), sodium phosphate dibasic (99%) (CAS: 7558-79-4), ammonium chloride (CAS: 12125-02-9) and potassium phosphate monobasic (99%) (CAS: 7778-77-0) were purchased from Fisher Scientific (UK).

## **2.2.3 Experimental procedure**

### **2.2.3.1 Pilot-scale experiments**

A number of relevant operating conditions were tested to evaluate the AOP pilot units for metaldehyde removal and DBPFP (Table 2, Appendix A). As the normal operating conditions involve steady state, operational parameters were regularly changed, but allowing to the AOPs respond to such adjustments. Therefore, samples were collected from each sample point (Figure 1) in 1-litre HDPE bottles 20 min after a flow rate change, and 10 min after the oxidant doses or UV fluences were changed. This decision was made upon operators' experience enabling a full evaluation of the impact caused by parameter changes. The DBPFP analysis involved chlorination. Therefore,  $\text{Na}_2\text{SO}_3$  at a stoichiometric ratio of 3.7 ( $\text{Na}_2\text{SO}_3$ :  $\text{H}_2\text{O}_2$ ) was added to exactly quench the peroxide residual present in samples after measure on-site by a 7100 Palintest photometer (Palintest Ltd., UK). Samples were placed into a cool box on ice. Inlet water was taken twice per day to verify the correct performance of the metaldehyde spiking pump.

### **2.2.3.2 Bench-scale experiment assessing the impact of TCMs on metaldehyde removal by UV/ $\text{H}_2\text{O}_2$**

Experiments were performed using  $2 \mu\text{g L}^{-1}$  of target pesticide as representative of 'high' metaldehyde concentrations in surface waters, reported up to  $2.7 \mu\text{g L}^{-1}$  (Kay and Grayson, 2014). Different concentrations of HA and kaolin to achieve 0, 0.1, 0.2, 0.4, 1, 2, 5 NTU were used to assess the resultant impact on metaldehyde removal via UV/ $\text{H}_2\text{O}_2$  at  $1800 \text{ mJ cm}^{-2}$  UV fluences and  $30 \text{ mg L}^{-1}$   $\text{H}_2\text{O}_2$ . The TCM concentrations selected are typically found in source and potable waters (Collins and Bolton, 2016),

The metaldehyde stock solution was prepared by adding the pesticide to UP water at a concentration of  $1 \text{ mg L}^{-1}$ . Two solutions at a nephelometric turbidity level (NTU) of 5.70 (5.80 mg) and 5.04 (24 mg) for kaolin and HA, respectively, were prepared in one-litre volumetric flasks of UP water. The rest of TCM solutions were obtained by two-fold dilution in UP water (1 part TCM, 1 part UP water) of the concentrated TCM stock solution. A total of five 2-fold serial dilutions were undertaken to cover the range 0.09-5.70 NTU and 0.09-5.04 NTU for kaolin and HA-TCM, respectively (Table 3, Table 4). The TCMs dilutions were subsequently spiked with the pesticide stock solution to attain a final metaldehyde concentration of  $2 \text{ } \mu\text{g L}^{-1}$ .

Appropriate control experiments were undertaken in addition to the  $\text{H}_2\text{O}_2$ /UV full exposure. All the samples were measured for metaldehyde residual concentration ( $\mu\text{g L}^{-1}$ ), turbidity (NTU), UV absorbance at 254 nm (UV254 nm) and transmittance (%). Control test 1 entailed the analysis of 100 mL TCM solution spiked with metaldehyde, without adding  $\text{H}_2\text{O}_2$  nor exposing it under UV light. Control test 2 involved adding 10  $\mu\text{L}$  of  $\text{H}_2\text{O}_2$  (35 wt. %) to 100 mL sample and, afterwards, analysing for the same parameters as in control 1. In the case of the complete  $\text{H}_2\text{O}_2$ /UV experiment, 10  $\mu\text{L}$  of  $\text{H}_2\text{O}_2$  (35 wt. %) to 100 mL sample was equally added as done in control 2. After that, 70 mL sample was poured into a glass Petri dish (9 mm diameter, 1.8 mm high). The 70 mL samples were subsequently irradiated with UV light (254 nm) at  $1800 \text{ mJ cm}^{-2}$  using a low pressure UV collimated beam device (Wedeco AG Water Technology, Germany). Before transferring the sample into the device, UV intensity was measured by VLX-3W radiometer (Vilber Lourmat, France). The UV intensity was  $3.20\text{-}3.40 \text{ mW cm}^{-2}$  resulting in an irradiation-time window of  $\sim 8'50''$  to  $9'20''$ . Over the irradiating time period, the solutions were mixed by a magnetic bar and stirrer located on the platform reactor. A 250 mm space was left between the UV lamps and the sample surface. Then, the irradiated solution was extracted by pipette. 'Control 2' and samples under  $\text{H}_2\text{O}_2$ /UV were quenched by adding  $3.7 \text{ mg L}^{-1}$   $\text{Na}_2\text{SO}_3$  per  $\text{mg L}^{-1}$  of  $\text{H}_2\text{O}_2$ .

**Table 3** Range of kaolin concentrations assessed for metaldehyde removal at 2  $\mu\text{g L}^{-1}$  metaldehyde initial concentration under UV/H<sub>2</sub>O<sub>2</sub>

| Kaolin<br>(mg L <sup>-1</sup> ) | Metaldehyde<br>( $\mu\text{g L}^{-1}$ ) | H <sub>2</sub> O <sub>2</sub><br>(mg L <sup>-1</sup> ) | UV fluences<br>(mJ cm <sup>-2</sup> ) |
|---------------------------------|-----------------------------------------|--------------------------------------------------------|---------------------------------------|
| 5.80                            | 2                                       | 0<br>and<br>30                                         | 0<br>and<br>1800                      |
| 2.90                            |                                         |                                                        |                                       |
| 1.45                            |                                         |                                                        |                                       |
| 0.58                            |                                         |                                                        |                                       |
| 0.29                            |                                         |                                                        |                                       |
| 0.14                            |                                         |                                                        |                                       |
| 0                               |                                         |                                                        |                                       |

**Table 4** Range of humic acid concentrations assessed for metaldehyde removal at 2  $\mu\text{g L}^{-1}$  metaldehyde initial concentration under UV/H<sub>2</sub>O<sub>2</sub>

| Humic acid<br>(mg L <sup>-1</sup> ) | Metaldehyde<br>( $\mu\text{g L}^{-1}$ ) | H <sub>2</sub> O <sub>2</sub><br>(mg L <sup>-1</sup> ) | UV fluences<br>(mJ cm <sup>-2</sup> ) |
|-------------------------------------|-----------------------------------------|--------------------------------------------------------|---------------------------------------|
| 24                                  | 2                                       | 0<br>and<br>30                                         | 0<br>and<br>1800                      |
| 12                                  |                                         |                                                        |                                       |
| 6                                   |                                         |                                                        |                                       |
| 3                                   |                                         |                                                        |                                       |
| 1.50                                |                                         |                                                        |                                       |
| 0.75                                |                                         |                                                        |                                       |
| 0                                   |                                         |                                                        |                                       |

#### 2.2.4 Analytical methods

Measurements were carried out in duplicate. On filtered samples (Millex-HA filter, 0.45  $\mu\text{m}$ , Aldrich, UK), UV254 nm absorbance was determined by means of a 6715 UV/Vis spectrophotometer (Jenway, UK) following standard method 5910. The non-purgeable organic carbon was measured by 5310 standard method with a TOC-V CSH TOC analyser (Shimadzu, UK). Turbidity was determined following 2130 method through a Hach 2100 turbidimeter (Hach Company, Loveland, CO) and a 4330 conductivity & pH meter was used for pH determinations (Jenway, UK). Metaldehyde residual concentration was analysed by gas chromatography-mass spectrometry using an Agilent Technologies 1260 HPLC with 6490 Triple

Quad LC/MS (Affinity Water, UK). A Poroshell 120 EC-C18 column was used (Capillary 2.7 m x 75 mm x 2.1 mm nominal).

The DBPs analytical method involved the chlorination of samples with total organic carbon (TOC) of  $< 1 \text{ mg L}^{-1}$  from a chlorine stock solution of concentrated sodium hypochlorite diluted in UP water. In this research, each sample had a chlorine dose ( $\text{mg L}^{-1}$ ) five times the TOC of the water. Seven days later, HAAs were quenched with ammonium chloride ( $100 \text{ mg L}^{-1}$ ) and THMs first buffered at pH 5 with a mix of sodium phosphate dibasic (1 g) and potassium phosphate monobasic (99 g) and then quenched with  $\text{Na}_2\text{SO}_3$  ( $100 \text{ mg L}^{-1}$ ). HAAs and THMS were subsequently extracted by EPA Method 552.3 and 551.1, respectively. THM internal standard was 4-bromofluorobenzene ( $1 \text{ } \mu\text{g L}^{-1}$ ) and HAA internal standard was 1, 2, 3 - trichloropropane ( $300 \text{ } \mu\text{g L}^{-1}$ ). HAA<sub>9</sub> (MBAA, TCAA, MCAA, DCAA, bromochloroacetic acid (BCAA), (DBAA), bromodichloroacetic acid (BDCAA), tribromoacetic acid (TBAA) and chlorodibromoacetic acid (CDBAA)) and THM<sub>4</sub> (bromoform, chloroform, bromodichloromethane and dibromochloromethane) were analysed by transferring an autosampler vial to a gas chromatography with electron capture detection (ECD) (Agilent HP 6890, Agilent Technologies, USA).

### **2.2.5 Statistical methods**

Metalddehyde and DBPFP variation was subject to crossed and interrelated factors (treatments and water quality) difficult to untangle: e.g. the response under  $\text{O}_3$  doses differs with  $\text{H}_2\text{O}_2$  concentration, UV fluences, DOC, etc. Therefore, standard normal linear models are limited for a multivariate and hierarchized set of factors, as the magnitude and direction of such interactions affect metalddehyde and DBPFP variation. A non-parametric multivariate multiple regression analysis through distance-based linear model (DistLM) analysis in PRIMER v6 software (Clarke and Gorley, 2006) was carried out to assess the AOP performance. The DistLM analysed and modelled the strength and significance of the relationship between a multivariate dataset (effectors) described by a resemblance matrix in Euclidean distance, and at least one predictor variable (Clarke and Gorley, 2006). The DistLM was used due to (i) it

takes into account possible interactions between the predictor variables (ii) multivariate data did not follow a normal distribution. The DistLM is constrained to find linear combinations of the predictors which best explain the greatest variation in the dataset (effector) response individually (marginal test). It also evaluates the cumulative effect of predictors, starting with such of the highest percentage influence and sequentially followed in ranking order by adding the rest, to improve the predictive power of the DistLM (sequential test). In doing so, the sequential test assesses whether the variation is better explained. The sequential routine is made until no further improvement to the model is attained. By using DistLM, the influence of an array of factors/predictors that can explain the change on the effectors before and after the AOP was achievable. In this study, the predictors were the process variables as well as the laboratory analysis results of turbidity, UV254 nm and DOC before such an AOP unit. Metaldehyde removal, net THM formation potential (THMFP) contribution and net HAA formation potential (HAAFP) contribution were the effectors of the model. All the measures were averaged, from each pair of duplicates, across the various operating conditions tested on the pilots.

Because predictors had different measurement scales, they were first square root transformed to equally distribute their weight. Those values were then standardised using the 'normalise' routine of the software (Clarke and Gorley, 2006). They were subsequently established in a resemblance Euclidean distance matrix, hence quantifying the between-normalised sample similarities. Effectors were excluded of square root transformation as the net DBPFP contribution provided with negative values (reduction of DBPFP after AOP). Stepwise permutation test (McArdle and Anderson, 2001) with the criterion of  $R^2$  and 9999 permutations (Clarke and Gorley, 2006) was employed to obtain  $P$ -values for testing the null hypothesis of no significant differences in each effector change among the predictors tested. The null hypothesis was rejected if the significance level ( $P$ ) was  $<0.05$ . A distance based Pseudo- $F$  was calculated. The Pseudo- $F$  represents the effect size and is analogous of  $F$  for multi-factorial univariate ANOVA models (McArdle and Anderson, 2001).

## 2.3 Results and discussion

### 2.3.1 Effectiveness of ozone and UV-based AOPs for metaldehyde removal

UV/H<sub>2</sub>O<sub>2</sub> and the full O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV treatment reduced metaldehyde in the range of 38-98% and 55%-97%, respectively, which was dependent on the MIC and operating conditions (Figure 2). The virgin GAC system post AOP had an effluent metaldehyde concentration of less than 6% of the inlet. For both treatments, the maximum pesticide degradations were achieved at the highest chemical and energy inputs (Table 5). The O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> in isolation removed the majority of the metaldehyde (38%-96%) from the inlet. The subsequent H<sub>2</sub>O<sub>2</sub>/UV process achieved 79% peak metaldehyde removal of the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> effluent. This more limited removal efficiency could be due to the requirement for greater UV fluences to degrade metaldehyde in the same order of magnitude as O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub>. The peroxone process acted as a pre-treatment for the pesticide of interest and could improve the treatability of the water prior to H<sub>2</sub>O<sub>2</sub>/UV. It is noticeable that the stand-alone UV/H<sub>2</sub>O<sub>2</sub> unit and the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> sub process equally removed 38% metaldehyde for the worst-case scenario. For the stand-alone UV/H<sub>2</sub>O<sub>2</sub>, it was at 0.53 µg L<sup>-1</sup> MIC, 13 mg L<sup>-1</sup> H<sub>2</sub>O<sub>2</sub> and 0.41 kWh m<sup>-3</sup>. In the case of the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> sub process, the lowest metaldehyde removal was found at 0.14 µg L<sup>-1</sup> MIC, 2.1 mg L<sup>-1</sup> O<sub>3</sub> and 11 mg L<sup>-1</sup> H<sub>2</sub>O<sub>2</sub>.




Figure 2 Net metaldehyde removal (%) contour plot regardless the initial concentration of pesticide and including all the operating conditions tested in the pilot-trial (n) by (a) UV/H<sub>2</sub>O<sub>2</sub> (n = 127), (b) O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> (n = 50) and (c) H<sub>2</sub>O<sub>2</sub>/UV (n = 31). Black points represent sampled data. Contour represents interpolation of data between measured points according to *SigmaPlot 11*.

Similar maximum metaldehyde removals on the stand-alone UV/H<sub>2</sub>O<sub>2</sub> process were observed in the literature (James, 2013; Semitsoglou-Tsiapou *et al.* 2016). However, their operating conditions and MICs differed to those herein required (Table 5). James (2013) achieved 98% metaldehyde degradation at 0.2 µg L<sup>-1</sup> MIC, 3 mg L<sup>-1</sup> H<sub>2</sub>O<sub>2</sub> and 0.62 kWh m<sup>-3</sup> E<sub>D</sub>, while Semitsoglou-Tsiapou *et al.* (2016) achieved 97% removal applying 1000 mJ cm<sup>-2</sup> UV fluences and 15 mg L<sup>-1</sup> H<sub>2</sub>O<sub>2</sub> for a 0.3 mg L<sup>-1</sup> MIC. Similar 0.7 kWh m<sup>-3</sup> E<sub>D</sub> was required to degrade 90% metaldehyde as Lekkerkerker-Teunissen *et al.* (2013) found in 90% atrazine degradation of an initial concentration of 10 µg L<sup>-1</sup>. However, they dosed 5 mg L<sup>-1</sup> H<sub>2</sub>O<sub>2</sub> whilst 28 mg L<sup>-1</sup> and 40 mg L<sup>-1</sup> were required in this study for metaldehyde inlets of 0.53 µg L<sup>-1</sup> and 2.14 µg L<sup>-1</sup>, respectively.

In the 'two-stage' AOP process (O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV), Tang *et al.* (2016) attained 90% metaldehyde removal from a MIC of 0.5 µg L<sup>-1</sup> using 8 mg L<sup>-1</sup> O<sub>3</sub> and 16-22 mg L<sup>-1</sup> H<sub>2</sub>O<sub>2</sub>. However, similar doses (7.2 mg L<sup>-1</sup> O<sub>3</sub> and 24 mg L<sup>-1</sup> H<sub>2</sub>O<sub>2</sub>) achieved 97% metaldehyde degradation at 2.11 µg L<sup>-1</sup> of initial pesticide level in this study. This was probably because 1800 mJ cm<sup>-2</sup> UV fluences (1.03 kWh m<sup>-3</sup> E<sub>D</sub>) were used whilst Tang *et al.* (2016) irradiated 1200 mJ cm<sup>-2</sup>.

Despite the higher removal efficiency of the peroxone sub stage than the H<sub>2</sub>O<sub>2</sub>/UV, only for a 0.14 µg L<sup>-1</sup> MIC the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> produced metaldehyde-compliant water according to the European Directive 98/83/EC (Figure 3). Otherwise, the presence of the H<sub>2</sub>O<sub>2</sub>/UV was crucial. This stresses that high removal does not imply achieving <0.1 µg L<sup>-1</sup> metaldehyde permitted concentration value (PCV) as it is MIC dependant. Therefore, even a 90% removal is insufficient to produce metaldehyde-compliant water at 2.0 µg L<sup>-1</sup> MIC, but it requires 95%.

**Table 5** Optimum set of experimental conditions at pilot-scale achieved the best metaldehyde removal (%)

| Treatment                                                                            | Flow rate<br>(m <sup>3</sup> h <sup>-1</sup> ) | [H <sub>2</sub> O <sub>2</sub> ]<br>(mg L <sup>-1</sup> ) | [O <sub>3</sub> ]<br>(mg L <sup>-1</sup> ) | E <sub>D</sub><br>(kWh m <sup>-3</sup> ) | [pesticide] <sub>0</sub><br>(µg L <sup>-1</sup> ) | Removal<br>(%) |
|--------------------------------------------------------------------------------------|------------------------------------------------|-----------------------------------------------------------|--------------------------------------------|------------------------------------------|---------------------------------------------------|----------------|
| O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> +<br>H <sub>2</sub> O <sub>2</sub> /UV | 2.5                                            | 24                                                        | 7.2                                        | 1.03                                     | 2.11                                              | 97             |
| O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> <sup>a</sup>                           | 0.6                                            | 24                                                        | 5.4                                        | N/A                                      | 2.23                                              | 96             |
| H <sub>2</sub> O <sub>2</sub> /UV <sup>a</sup>                                       | 2.5                                            | 18                                                        | 6.0                                        | 1.10                                     | 0.53                                              | 79             |
| UV/H <sub>2</sub> O <sub>2</sub><br>stand-alone                                      | 2.0                                            | 45                                                        | N/A                                        | 0.94                                     | 2.11                                              | 98             |

N/A: not applicable; <sup>a</sup> Sub processes of the two-stage UV-based and peroxone AOPs

### 2.3.2 Impact of the operating conditions on metaldehyde removal

Statistical results over 127 samples indicated that H<sub>2</sub>O<sub>2</sub> explained 13% of the variability in metaldehyde removal ( $P=0.0001$ ) within the stand-alone UV/H<sub>2</sub>O<sub>2</sub> process. Metaldehyde removal was improved when H<sub>2</sub>O<sub>2</sub> dose was raised at equal MIC and E<sub>D</sub>, e.g. at <0.5 µg L<sup>-1</sup> MIC and 0.60 kWh m<sup>-3</sup>, 68% removal dosing 14 mg L<sup>-1</sup> H<sub>2</sub>O<sub>2</sub> in contrast with the 83% removal at 29 mg L<sup>-1</sup> H<sub>2</sub>O<sub>2</sub>. However, the UV/H<sub>2</sub>O<sub>2</sub> process performance was not improved at >0.66 kWh m<sup>-3</sup> E<sub>D</sub> and 40 mg L<sup>-1</sup> H<sub>2</sub>O<sub>2</sub> dose regardless MIC, e.g. at 0.89 kWh m<sup>-3</sup> and <0.5 µg L<sup>-1</sup> MIC 93% removal dosing 30 mg L<sup>-1</sup> H<sub>2</sub>O<sub>2</sub>, whilst 85% dosing 47 mg L<sup>-1</sup> H<sub>2</sub>O<sub>2</sub>; or the same 93% metaldehyde removal for 32 mg L<sup>-1</sup> and 40 mg L<sup>-1</sup> H<sub>2</sub>O<sub>2</sub> at 0.77 kWh m<sup>-3</sup>. Negligible process optimisation was also detected for E<sub>D</sub> above both 0.85 kWh m<sup>-3</sup> and 30 mg L<sup>-1</sup> H<sub>2</sub>O<sub>2</sub> in >2.0 µg L<sup>-1</sup> metaldehyde waters. At 0.5-0.8 µg L<sup>-1</sup> metaldehyde inlet, there was a limited difference of pesticide removal either with 30 mg L<sup>-1</sup> H<sub>2</sub>O<sub>2</sub> and 0.86 kWh m<sup>-3</sup> (91.4%) or 40 mg L<sup>-1</sup> H<sub>2</sub>O<sub>2</sub> and 0.97 kWh m<sup>-3</sup> (96%). The DistLM revealed UV irradiation accounted for 32% of the variability in metaldehyde removal on its own ( $P=0.0001$ ).

Regardless the inlet concentration of metaldehyde (µg L<sup>-1</sup>) (0.14 / 0.53 / 2.2) and H<sub>2</sub>O<sub>2</sub> doses (mg L<sup>-1</sup>) (40 / 40 / 30), poorer metaldehyde removals (%) were observed at 0.66 kWh m<sup>-3</sup> E<sub>D</sub> and 2 m<sup>-3</sup> flow rate (84.5 / 79.5 / 79.7) than that of 0.60 kWh m<sup>-3</sup> E<sub>D</sub> and 2.5 m<sup>-3</sup> flow rate (86.6 / 83.1 / 83.8) which was in contrast to the positive trend previously stated up to 0.85 kWh m<sup>-3</sup>. One possible

explanation was that of the better UV light distribution when irradiated at more turbulent regime of water (Koutchma *et al.*, 2004; Dobrović, Juretić and Ružinski, 2007). The AOP performance could be enhanced a maximum of 10% by increasing the flow rate from  $2.5 \text{ m}^3 \text{ h}^{-1}$  to  $3.5 \text{ m}^3 \text{ h}^{-1}$ . The flow rate individually involved 13% of variability in metaldehyde removal ( $P=0.0001$ ). The DistLM analysis showed that when UV and  $\text{H}_2\text{O}_2$  were considered together, they influenced 43% of the variability in metaldehyde removal ( $P=0.0001$ ). The DistLM over 64 samples indicated that  $\text{H}_2\text{O}_2$  and  $\text{O}_3$  influenced individually 34% and 45% of the variability in metaldehyde removal ( $P=0.0001$ ) within the two-stages  $\text{O}_3/\text{H}_2\text{O}_2 + \text{H}_2\text{O}_2/\text{UV}$  process jointly evaluated. Greater metaldehyde removals (%) were found when adding more oxidants on equal  $\text{H}_2\text{O}_2:\text{O}_3$  ratio, e.g. 47% ( $12 \text{ mg L}^{-1} \text{ H}_2\text{O}_2$  and  $4 \text{ mg L}^{-1} \text{ O}_3$ ) versus 67% ( $24 \text{ mg L}^{-1} \text{ H}_2\text{O}_2$  and  $8 \text{ mg L}^{-1} \text{ O}_3$ ) at  $0.53 \text{ } \mu\text{g L}^{-1}$  MIC. This was possibly explained due to greater  $\bullet\text{OH}$  production by raising oxidants despite maintaining ratios. However, similar metaldehyde removal was attained when  $\text{H}_2\text{O}_2$  was overdosed at the same ozone concentration, e.g. 46% vs 47% at a  $\text{H}_2\text{O}_2:\text{O}_3$  ratio 2:1/3:1, respectively and  $0.53 \text{ } \mu\text{g L}^{-1}$  metaldehyde inlet. A 1:1  $\text{H}_2\text{O}_2:\text{O}_3$  mole ratio, 0.7:1 in terms of mass, has been reported to form  $\bullet\text{OH}$  radicals (Lucas, Peres and Li Puma, 2010). Yet the specific ratio is also a function of the water quality parameters and pollutant concentration (Melin, 2000). Thus, it can be hypothesised that  $\text{O}_3$  was the limiting factor for  $\bullet\text{OH}$  production as  $\text{H}_2\text{O}_2$  was of a dose two or three-fold higher than the  $\text{O}_3$  concentration in the pilot-scale experiments. However, such  $\text{H}_2\text{O}_2$  surplus was required to have  $\text{H}_2\text{O}_2$  residual within the subsequent  $\text{H}_2\text{O}_2/\text{UV}$  process for  $\bullet\text{OH}$  production. It can be inferred, therefore, that  $\text{O}_3$  established the amount of  $\bullet\text{OH}$  generated within the  $\text{O}_3/\text{H}_2\text{O}_2$  stage and determined the  $\text{H}_2\text{O}_2$  availability for  $\bullet\text{OH}$  formation within the following UV-based AOP stage. UV fluences individually accounted 54% of the variability in metaldehyde removal ( $P=0.0001$ ), improving the AOP performance with increased fluences. In the  $\text{O}_3/\text{H}_2\text{O}_2 + \text{H}_2\text{O}_2/\text{UV}$  process the UV power was fixed to 0.34 kW and the  $E_D$  ( $\text{kWh m}^{-3}$ ) adjusted by flow rate variation ( $\text{m}^3 \text{ h}^{-1}$ ). Through DistLM the UV and  $\text{O}_3$  when considered together, accounted for 78% of the variability in metaldehyde removal ( $P=0.0001$ ).

A separate assessment for each of the two sub processes revealed that for the  $O_3/H_2O_2$ , the inlet DOC influenced 35% of the variability in metaldehyde degradation ( $P=0.0001$ ), whilst the absorbance accounted for 26% ( $P=0.0004$ ),  $H_2O_2$  12% ( $P=0.0128$ ) and  $O_3$  10% ( $P=0.0255$ ). When considering the cumulative effect of the predictors, the DistLM indicated that 51% of the variation in metaldehyde removal was attributed to DOC and  $O_3$ . This was because (i)  $O_3$  drove the production of  $\bullet OH$  and (ii) DOC is a  $\bullet OH$  scavenger and thus an influential water quality parameter in determining metaldehyde removal (James, 2013). In the  $H_2O_2/UV$  sub process, all process variables were significant ( $P>0.05$ ) for metaldehyde removal. A summary of the statistical data analysis is presented in Appendix B.

### **2.3.3 Optimum conditions to achieve the statutory limits for metaldehyde residual at the minimum supply of inputs**

An optimal set of parameters that successfully achieved metaldehyde PCV in water with the minimum  $H_2O_2$  concentration per energy supplied was identified (Figure 3b and Figure 4a). These operating conditions were dissimilar among MICs. As stated previously, the  $O_3/H_2O_2$  exclusively complied with the legislation at metaldehyde inlets below  $0.5 \mu g L^{-1}$  ( $0.14 \mu g L^{-1}$ ) with a minimum  $0.55 kWh m^{-3} E_D$  (Figure 3a). Unsurprisingly, the greater the metaldehyde inlet concentration, the greater the both UV and  $H_2O_2$  doses which were required (Figure 3b). A ratio  $H_2O_2:O_3$  of 3 was required for the minimum  $E_D$  ( $0.53 kWh m^{-3}$ ) between  $0.5-0.8 \mu g L^{-1}$  metaldehyde inlets. Equal oxidant ratio was demanded for the minimum  $E_D$  ( $0.79 kWh m^{-3}$ ) between  $2.0-2.14 \mu g L^{-1}$  metaldehyde inlets. The  $O_3/H_2O_2 + H_2O_2/UV$  process did not provide with metaldehyde-compliant water at  $>2.14 \mu g L^{-1}$  MICs. The costing analysis (Chapter 2) was used to understand the relative importance of capital and operational expenditures in the total expenditures for the economic viability of these AOPs. Electricity consumption was a paramount factor over the operational costs associated with chemicals for driving the decision-making of real-scale implementation towards  $O_3/H_2O_2$  rather than  $O_3/H_2O_2 + H_2O_2/UV$  or  $UV/H_2O_2$ . Therefore, it is recommended that to fulfil the European Directive 98/83/EC, WTW operators should consider the lower  $E_D$  despite greater oxidants required when upscaling AOP pilot-trials (Table 6).

A set of optimal operating conditions were equally found for the stand-alone UV/H<sub>2</sub>O<sub>2</sub> treatment (Figure 4). The lower limit of 15-20 mg L<sup>-1</sup> H<sub>2</sub>O<sub>2</sub> effectively attained metaldehyde residual UK/EU levels regardless the E<sub>D</sub> (minimum 0.36 kWh m<sup>-3</sup>) at <0.5 µg L<sup>-1</sup> MIC. Between 0.5-0.8 µg L<sup>-1</sup>, the compliance of European Directive 98/83/EC was achievable either by raising E<sub>D</sub> and lowering H<sub>2</sub>O<sub>2</sub> doses (0.67 kWh m<sup>-3</sup> and 28 mg L<sup>-1</sup>) or by lowering E<sub>D</sub> and increasing H<sub>2</sub>O<sub>2</sub> doses (0.55 kWh m<sup>-3</sup> and 37 mg L<sup>-1</sup>). Minimum 0.75 kWh m<sup>-3</sup> E<sub>D</sub> with 42 mg L<sup>-1</sup> H<sub>2</sub>O<sub>2</sub> were required to reduce metaldehyde <0.1 µg L<sup>-1</sup> between 2.0-2.14 µg L<sup>-1</sup> metaldehyde inlets. Similar findings to that of the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV process were identified for metaldehyde inlets >2.14 µg L<sup>-1</sup>. The virgin GAC contactor provided with metaldehyde-compliant water in all the samples analysed according to the benchmark concentration adopted from the European Directive 98/83/EC. However, it is unlikely these high metaldehyde removals would be achieved at full-scale with time due to loss adsorption capacity as the GAC in this pilot study was virgin media.

**Table 6** Minimum E<sub>D</sub> and their associated minimum oxidant doses tested producing metaldehyde-compliant water at dissimilar ranges of metaldehyde inlet concentrations (MICs)

| Treatment                                                                            | [metaldehyde] <sub>0</sub><br>(µg L <sup>-1</sup> ) | [H <sub>2</sub> O <sub>2</sub> ] (mg L <sup>-1</sup> ) | [O <sub>3</sub> ]<br>(mg L <sup>-1</sup> ) | E <sub>D</sub> (kWh m <sup>-3</sup> ) |
|--------------------------------------------------------------------------------------|-----------------------------------------------------|--------------------------------------------------------|--------------------------------------------|---------------------------------------|
| O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> +<br>H <sub>2</sub> O <sub>2</sub> /UV | <0.5                                                | 8                                                      | 2                                          | 0.55                                  |
|                                                                                      | 0.5-0.8                                             | 17                                                     | 6                                          | 0.53                                  |
|                                                                                      | 2.0-2.14                                            | 22                                                     | 7                                          | 0.79                                  |
| UV/H <sub>2</sub> O <sub>2</sub>                                                     | <0.5                                                | 14                                                     | N/A                                        | 0.36                                  |
|                                                                                      | 0.5-0.8                                             | 37                                                     |                                            | 0.55                                  |
|                                                                                      | 2.0-2.14                                            | 42                                                     |                                            | 0.75                                  |

N/A: not applicable




**Figure 3** (a) Minimum  $O_3$  concentration per  $H_2O_2$  dose ( $O_3/H_2O_2$ ) and (b) minimum  $H_2O_2$  dose per UV energy demand ( $H_2O_2/UV$ ) at  $<0.5$  to  $2.14\ \mu g\ L^{-1}$  MICs based on benchmark concentration adopted from  $0.1\ \mu g\ L^{-1}$  PCV for individual pesticides (European Parliament, 1998) through the  $O_3/H_2O_2$  +  $H_2O_2/UV$  process. Other conditions also achieved  $< 0.1\ \mu g\ L^{-1}$  pesticide degradation, but required more chemical and are therefore excluded




**Figure 4** Minimum H<sub>2</sub>O<sub>2</sub> dose per UV energy demand at <0.5-2.14 µg L<sup>-1</sup> MICs based on benchmark concentration adopted from 0.1 µg L<sup>-1</sup> PCV for individual pesticides (European Parliament, 1998) through the UV/H<sub>2</sub>O<sub>2</sub> process. Other conditions also achieved < 0.1 µg L<sup>-1</sup> pesticide degradation, but required more H<sub>2</sub>O<sub>2</sub> and are therefore excluded.

#### 2.3.4 Influence of TCMs on metaldehyde removal by UV/H<sub>2</sub>O<sub>2</sub>

The DistLM showed that turbidity contributed ~2% of the variability in metaldehyde removal within the stand-alone UV/H<sub>2</sub>O<sub>2</sub> process ( $P=0.0186$ ) when other parameters were already considered in the model (Appendix B). The lower influence, however, can be explained because turbidity was <0.2 NTU in all samples. Nevertheless, the transmittance of light including the penetration of UV photons into the water is reduced in turbid matrices (Melin, 2000; Yonar *et al.*, 2006) negatively affecting UV system efficiency for the removal of compounds (Dotson *et al.*, 2010; Carra *et al.* 2016). Therefore, the bench-scale experiments assessed the impact of TCMs on metaldehyde removal by UV/H<sub>2</sub>O<sub>2</sub>. Kaolin clay and HA materials are typically found in surface water matrices (Wang and Hsieh, 2001; Templeton *et al.*, 2007; Yang *et al.*, 2016) and hence represent suitable test TCMs for experimentation. A strong inverse correlation ( $R^2=0.79$ ) was identified between the turbidity caused by HA and metaldehyde removed by UV/H<sub>2</sub>O<sub>2</sub> (Table 7).

**Table 7** Summary of operating conditions and results of metaldehyde degradation bench-scale experiments applying UV/H<sub>2</sub>O<sub>2</sub> process

| TCM        | Experimental conditions <sup>a</sup>                                      | <i>k</i> value (NTU) | R <sup>2</sup> |
|------------|---------------------------------------------------------------------------|----------------------|----------------|
| Humic acid | No treatment <sup>b</sup>                                                 | 0.020                | 0.10           |
|            | 10 µL H <sub>2</sub> O <sub>2</sub> <sup>b</sup>                          | -0.045               | 0.04           |
|            | 10 µL H <sub>2</sub> O <sub>2</sub> , 1800 mJ cm <sup>-2</sup> UV fluence | 0.103                | 0.79           |
| Kaolin     | No treatment <sup>b</sup>                                                 | 0.009                | 0.11           |
|            | 10 µL H <sub>2</sub> O <sub>2</sub> <sup>b</sup>                          | -0.010               | 0.01           |
|            | 10 µL H <sub>2</sub> O <sub>2</sub> , 1800 mJ cm <sup>-2</sup> UV fluence | -0.018               | 0.17           |

<sup>a</sup> Initial metaldehyde concentration 2.03 µg L<sup>-1</sup>; <sup>b</sup> Reaction volume 100 mL; The *k* value was calculated by division of the ratio C/C<sub>0</sub> (residual metaldehyde concentration divided by initial concentration) and the NTU values obtained for each sample. The coefficient of determination (R<sup>2</sup>) was obtained by linear regression

Metaldehyde degradation kinetic by UV/H<sub>2</sub>O<sub>2</sub> was significantly affected by the presence of HA (Figure 5) in line with other studies assessing the influence of organic matter on pollutant removals (Hollrigl-Rosta *et al.*, 2003; Carra *et al.* 2016). The greater HA concentration in the solution, hence the greater turbidity, the lower metaldehyde removal post AOP (Figure 5b). This was evidenced through analysis of the initial (2.03 µg L<sup>-1</sup>) and residual metaldehyde concentrations, e.g. 41% and 89% metaldehyde removals at 4.71 and 0.68 NTU, respectively. Similarly, these outcomes suggested that greater UV irradiations would have been required to achieve similar >86% metaldehyde removals to those of <1 NTU (Figure 5b).

By contrast, the concentration of inorganic material did not interfere with metaldehyde removal. There was a poor correlation (R<sup>2</sup> = 0.17) between the amount of kaolin in water and the removal rate achieved which was 92% on average. Kaolin concentration did not interfere with the photolysis of metaldehyde (*k* = -0.018) with similar removals across the range of turbidity tested, e.g. equal

97% pesticide removals at 2.74 and 1.28 NTU. Therefore, a minimal effect of inorganic materials on UV-based AOP performance for metaldehyde removal can be inferred. The outcome of this experiment showed that kaolin does not have UV shielding effect as confirmed by others (Giri *et al.* 2010; Sen Kavurmaci and Bekbolet, 2014). Control 2 demonstrated the H<sub>2</sub>O<sub>2</sub> negligible effect on metaldehyde removal ( $R^2=0.04$  and  $R^2=0.01$ ; Table 7). It can be equally assumed that H<sub>2</sub>O<sub>2</sub> adsorbed a small fraction of the UV light irradiated, even using three-fold higher H<sub>2</sub>O<sub>2</sub> concentration than the 0.29 mM H<sub>2</sub>O<sub>2</sub> (~10 mg L<sup>-1</sup>) dosed in some previous studies (*e.g.* Rosenfeldt *et al.*, 2006). The standard deviation of the metaldehyde residual ( $C/C_0$ ) from the untreated samples revealed a 5% and 10% metaldehyde experimental error for kaolin and HA experiments, likely a pipetting error. Therefore, the greater metaldehyde concentration than the stock solution (2.03 µg L<sup>-1</sup>, 0.09 NTU) found in some control samples, thus concentration ratios >1 theoretical top-end limit, could be explained (Figure 5). These findings, therefore, stressed the importance of (i) the type of TCM for the AOP performance and also (ii) the processes that remove DOC before a UV-based AOP treatment in organic-turbid waters, *e.g.* coagulation or activated carbon.

After assessing the efficiency of AOPs on the removal of metaldehyde, the generation of DBPFP was also evaluated. DBPs are considered to be a major limitation preventing the wide-scale application of AOPs. Therefore, this is discussed below.




**Figure 5** Normalized residual metaldehyde concentration profiles regarding control tests and UV/H<sub>2</sub>O<sub>2</sub> full treatment in (a) kaolin-turbid UP water and (b) HA-turbid UP water at different concentrations of TCMs

### 2.3.5 Disinfection by-product formation potential (DBPFP) by ozone and UV-based advanced oxidation processes

Results of DBPFP after AOPs showed either production or reduction with respect to the DBPFP from the inlet water. Henceforth the difference between DBPs production/reduction after AOP and the DBPFP from the inlet is referred as net contribution. Inlet DBPFP results ranged 234-610  $\mu\text{g L}^{-1}$  THMFP and 174-321

$\mu\text{g L}^{-1}$  HAAFP. These results would theoretically be 47-121  $\mu\text{g L}^{-1}$  THM<sub>4</sub> and 35-64  $\mu\text{g L}^{-1}$  HAA<sub>9</sub> using a 0.199 conversion factor DBP:DBPFP (Hutton 1994 in Jefferson *et al.*, 2016). Interestingly, the maximum inlet THMFP and HAAFP were found at one of the greatest metaldehyde spiking doses (2.14  $\mu\text{g L}^{-1}$ ), yet the lowest THMFP was at 2.04  $\mu\text{g L}^{-1}$  metaldehyde inlet and similarly for the HAAFP at 2.11  $\mu\text{g L}^{-1}$ . This suggested that metaldehyde concentration did not influence the formation of DBPs, but the water quality of samples, in terms of NOM, of the pilot-trial day (Figure 6). The DistLM also revealed the absence of UV fluences and reagent doses impacting on DBPFP (Appendix C). In the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV, the H<sub>2</sub>O<sub>2</sub> accounted for 14% ( $P=0.018$ ) of the variability in net THMFP contribution, whilst for the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> sub process, 11% ( $P=0.0375$ ). The DistLM showed that H<sub>2</sub>O<sub>2</sub> was not statistically significant ( $P>0.05$ ) to explain the variability in net THMFP contribution under the UV/H<sub>2</sub>O<sub>2</sub> treatment. Neither UV fluences nor O<sub>3</sub> influenced the variability in net THMFP contribution ( $P>0.05$ ). Regarding HAAFP, the H<sub>2</sub>O<sub>2</sub>:O<sub>3</sub> ratio accounted for 37% ( $P=0.0018$ ) of the variability in net HAAFP contribution through the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV process whilst the UV explained 39% of the net HAAFP variability ( $P=0.0223$ ) in the H<sub>2</sub>O<sub>2</sub>/UV sub process. Moreover, analogous operating conditions were applied and only metaldehyde spiking solution and water quality were dissimilar throughout the experimental plan. The water quality influence on DBPFP can also be seen in Table 8 and Appendix C. Under similar operating conditions (H<sub>2</sub>O<sub>2</sub> and E<sub>D</sub>), the UV/H<sub>2</sub>O<sub>2</sub> achieved a net DBPFP reduction on day 2, whilst increased DBPFP on day 4. The results of this study suggested that such DBPFP can be ameliorated by removing DBPs precursors upstream an advanced oxidation process. A limitation of this study is the low number of inlet samples collected, 10 in total. Therefore, DistLM results need to be interpreted with caution.

O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> sub process contributed the lowest to the DBPFP after an AOP treatment with maximum 549  $\mu\text{g L}^{-1}$  THMFP and 245  $\mu\text{g L}^{-1}$  HAAFP. Either the stand-alone UV/H<sub>2</sub>O<sub>2</sub>, the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV and the H<sub>2</sub>O<sub>2</sub>/UV sub process overcame 600  $\mu\text{g L}^{-1}$  THMFP top end (638  $\mu\text{g L}^{-1}$ ; 616  $\mu\text{g L}^{-1}$ , 616  $\mu\text{g L}^{-1}$ , respectively) and 300  $\mu\text{g L}^{-1}$  HAAFP top end (305  $\mu\text{g L}^{-1}$ ; 316  $\mu\text{g L}^{-1}$ , 316  $\mu\text{g L}^{-1}$  respectively). However, the net contribution of UV/H<sub>2</sub>O<sub>2</sub> and O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV

varied in the range  $-283 \mu\text{g L}^{-1}$ , hence reducing the production, to  $+255 \mu\text{g L}^{-1}$  THMFP and  $-164 \mu\text{g L}^{-1}$  to  $+131 \mu\text{g L}^{-1}$  HAAFP. It was found a similar HAAFP maximum net reduction in all the AOPs and sub processes ( $\sim -160 \mu\text{g L}^{-1}$ ), but the lowest maximum net production was given by  $\text{O}_3/\text{H}_2\text{O}_2$  sub process ( $+22 \mu\text{g L}^{-1}$ ). The peroxone sub stage also achieved the THMFP maximum net reduction ( $-283 \mu\text{g L}^{-1}$ ), yet attained the maximum net production ( $+269 \mu\text{g L}^{-1}$ ). Nevertheless, these THMFP boundaries were obtained in a pilot-trial day (day 3) in which an ozone gas leak was reported. Therefore, the results should be approached with some caution due to power outages during clean-up (Figure 6). Over 39 total THMFP samples analysed within this sub process, the maximum net both THMFP reduction and production were  $-101 \mu\text{g L}^{-1}$  and  $+51 \mu\text{g L}^{-1}$ , respectively, if these extreme values are excluded. Surprisingly, the HAAFP data behaved in the same way as did it on other days of testing (Figure 6b). Even with the offset exclusions, the  $\text{O}_3/\text{H}_2\text{O}_2$  sub-process typically formed less THMs than both UV-based pilots. This was confirmed when the net contribution of the UV and peroxone sub processes on DBPFP was assessed (Figure 7). Whilst  $\text{O}_3/\text{H}_2\text{O}_2$  mostly attained a net DBPFP reduction,  $\text{H}_2\text{O}_2/\text{UV}$  enhanced the production. A likely reason can rely on Dotson's *et al.* (2010) conclusions highlighting the strong correlation between THMFP and  $\bullet\text{OH}$  exposure. It was before discussed that the  $\text{O}_3/\text{H}_2\text{O}_2$  removed the majority of the metaldehyde and  $\bullet\text{OH}$  production was limited to  $\text{O}_3$  dose (up to  $10 \text{ mg L}^{-1}$ ), therefore hydroxyl radical scavenging by NOM could be constrained. However, the lower metaldehyde to remove on the subsequent  $\text{H}_2\text{O}_2/\text{UV}$  sub treatment might enable greater  $\bullet\text{OH}$  to interact with NOM, thus increasing DBPFP.

In both global treatments, a positive correlation between THMFP and HAAFP was also found: the greater production of THM or HAA involved greater production of the other and conversely. Some of the DBPFP results showed clear differences between duplicates under the same treatment. If there was variability of greater than 15% between duplicates, then, the DBPFP analysis was repeated on them. The persistence of the difference involved the exclusion of the data (Figure 6b and Table 8).




**Figure 6** Net contribution of the stand-alone UV/ H<sub>2</sub>O<sub>2</sub>, and the O<sub>3</sub>/ H<sub>2</sub>O<sub>2</sub>+ H<sub>2</sub>O<sub>2</sub>/UV on (a) THMFP ( $n = 66$ ) and (b) HAAFP ( $n = 48$ ) based on the day of pilot-scale work

Under optimum oxidant doses and  $E_D$  operating conditions for metaldehyde-compliant water production, a wide range of net DBPFP results were found (Table 8). However, potential THMs formed by an AOP would be  $<100 \mu\text{g L}^{-1}$  regulatory limit (European Parliament, 1998; DWI, 2000) when applied the Hutton's (1994) theoretical conversion factor to THMFP. Therefore, the effectiveness of both AOPs to comply the legislation in terms of metaldehyde as well as on THMs was demonstrated. The GAC contactor limited to a maximum  $246 \mu\text{g L}^{-1}$  THMFP ( $49 \mu\text{g L}^{-1}$  THM) and  $78 \mu\text{g L}^{-1}$  HAAFP ( $16 \mu\text{g L}^{-1}$  HAA).

**Table 8** Net contribution of the AOPs on THMFP and HAAFP using minimum oxidant doses per UV ( $E_D$ ) for metaldehyde-compliant water production at different metaldehyde (M) spiking doses

| Treatment                                     | Day | [M] <sub>0</sub> <sup>1</sup> | [H <sub>2</sub> O <sub>2</sub> ] <sup>2</sup> | [O <sub>3</sub> ] <sup>2</sup> | $E_D$ <sup>3</sup> | THMFP <sup>1</sup> | HAAFP <sup>1</sup> |
|-----------------------------------------------|-----|-------------------------------|-----------------------------------------------|--------------------------------|--------------------|--------------------|--------------------|
| O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> | 2   | 0.5-0.8                       | 16                                            | 10.8                           | 0.79               | 98                 | 88                 |
| +<br>H <sub>2</sub> O <sub>2</sub> /UV        | 3   | 2.0-2.14                      | 22                                            | 7.2                            | 0.79               | -37                | 2                  |
| UV/H <sub>2</sub> O <sub>2</sub>              | 1   | <0.5                          | 20                                            | N/A                            | 0.52               | 45                 | N/D                |
|                                               |     |                               | 19                                            |                                | 0.76               | 12                 | N/D                |
|                                               | 2   | 0.5-0.8                       | 28                                            |                                | 0.75               | -200               | -164               |
|                                               | 4   |                               | 30                                            |                                | 0.74               | 133                | 38                 |
|                                               | 3   | 2.0-2.14                      | 42                                            |                                | 0.75               | -234               | 14                 |

N/A: not applicable; N/D: no data; <sup>1</sup>( $\mu\text{g L}^{-1}$ ); <sup>2</sup>( $\text{mg L}^{-1}$ ); <sup>3</sup>( $\text{kWh m}^{-3}$ )




**Figure 7** Net contribution of the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> and H<sub>2</sub>O<sub>2</sub>/UV sub treatments on DBPFP

## 2.4 Conclusions

This study evaluated the removal of metaldehyde attributed to UV/H<sub>2</sub>O<sub>2</sub>, and O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV fed with the same post RGF water quality to comply the European Directive 98/83/EC for individual pesticides. Also, it addressed the changes in DBPFP due to both AOPs. UV/H<sub>2</sub>O<sub>2</sub> degraded 38-98% pesticide whilst O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV 55%-97%. Within the two-stage process, the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> removed 38%-96% compared to the 79% highest metaldehyde removal of H<sub>2</sub>O<sub>2</sub>/UV. The stand-alone UV-based AOP unit showed more significant removal by increasing flow rate, H<sub>2</sub>O<sub>2</sub> dose and E<sub>D</sub> up to 3.5 m<sup>3</sup> h, 30 mg L<sup>-1</sup> and 0.85 kWh m<sup>-3</sup>, respectively. UV/H<sub>2</sub>O<sub>2</sub> process was also found to be negatively affected by HA-turbid waters over 1.0 NTU. O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV metaldehyde removal effectiveness was enhanced by (i) dosing more O<sub>3</sub> and H<sub>2</sub>O<sub>2</sub>, but maintaining the same ratio and by (ii) raising UV fluences. Ozone was a limiting factor on the success of O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV as it defined the H<sub>2</sub>O<sub>2</sub> available for •OH production on the H<sub>2</sub>O<sub>2</sub>/UV sub treatment. The minimum E<sub>D</sub> to fulfil metaldehyde PCV was <0.6 kWh m<sup>-3</sup> for <0.8 µg L<sup>-1</sup> metaldehyde inlets and close to 0.8 kWh m<sup>-3</sup> for inlets between 2.0 and 2.14 µg L<sup>-1</sup>. None of the operating conditions tested achieved <0.1 µg L<sup>-1</sup> metaldehyde residual at 2.2 µg L<sup>-1</sup> metaldehyde spiking dose. Similarly, the peroxone sub process provided with metaldehyde-compliant water only at MIC of 0.14 µg L<sup>-1</sup>. The net contribution of the advanced oxidation

technologies on DBPFP was likely related to the NOM characteristics in the inlet water on each the day of the pilot-trial. The peroxone sub process contributed the lowest to the DBPFP in absolute terms. Equally, in net terms,  $O_3/H_2O_2$  slightly increased by  $22 \mu g L^{-1}$  HAAFP and  $51 \mu g L^{-1}$  THMFP at most, significantly below to that of the rest of the processes. There was a positive trend between THMFP and HAAFP either decreasing or increasing commensurately. Among the optimum operating conditions that successfully achieved the  $0.1 \mu g L^{-1}$  metaldehyde target, THMs were in all cases below  $100 \mu g L^{-1}$  PCV. The virgin GAC contactor additionally assisted the AOPs limiting both metaldehyde residual and DBPFP. It is likely however that an acclimated GAC would not be as effective as the virgin media used in this study All these results evidenced the efficacy of AOPs to assist water companies on recalcitrant pollutant degradation in drinking water.

Once evaluated  $UV/H_2O_2$ , and  $O_3/H_2O_2 + H_2O_2/UV$  efficiency on the removal of metaldehyde and control of DBPs, a cost evaluation was undertaken for decision making on the most appropriate AOP to implement using a full-scale case study with scenario analysis to project future costs.

## 2.5 Acknowledgments

Severn Trent Water is gratefully acknowledged for the financial support. The authors also thank WatStech Ltd. operators for their support on the sampling surveys, running pilots and technical advice.

## 2.6 References

- Autin O., Hart J., Jarvis P., MacAdam J., Parsons S.A and Jefferson B. (2012) "Comparison of  $UV/H_2O_2$  and  $UV/TiO_2$  for the degradation of metaldehyde: Kinetics and the impact of background organics". *Water Research*, 46 p. 5655-5662
- Autin O., Hart J., Jarvis P., MacAdam J., Parsons S.A and Jefferson B. (2013a) "The impact of background organic matter and alkalinity on the degradation of the pesticide metaldehyde by two advanced oxidation processes:  $UV/H_2O_2$  and  $UV/TiO_2$ ". *Water Research*, 47(6) p. 2041-2049

- Baghoth S.A., Sharma S.K. and Amy G.L. (2011) "Tracking natural organic matter (NOM) in a drinking water treatment plant using fluorescence excitation–emission matrices and PARAFAC". *Water Research*, 45(2) p. 797-809
- Bond T., Huang J., Templeton M.R. and Graham N. (2011) "Occurrence and control of nitrogenous disinfection by-products in drinking water - a review". *Water Research*, 45(15) p. 4341-4354
- Carra I., Sánchez Pérez J.A., Malato S., Autin O., Jefferson B. and Jarvis, P. (2016) "Performance of different advanced oxidation processes for tertiary wastewater treatment to remove the pesticide acetamiprid". *Journal of Chemical Technology and Biotechnology*, 91(1) p. 72-81.
- Collins J. and Bolton J.R. (2016) *Advanced Oxidation Handbook* Denver: American water Works Association
- Chin A. and Bérubé P.R. (2005) "Removal of disinfection by-product precursors with ozone-UV advanced oxidation process". *Water Research*, 39(10) p. 2136–2144
- Clarke K.R. and Gorley R.N. (2006) *PRIMER v6: User Manual/Tutorial*. PRIMER-E, Plymouth, 192 pp
- Crittenden J.C., Trussell R.R., Hand D.W., Howe K.J. and Tchobanoglous G. (2012) *Frontmatter, in MWH's Water Treatment: Principles and Design*. 3<sup>rd</sup> Edition. Hoboken: John Wiley & Sons
- Croue J.-P., Korshin G.V. and Benjamin M.M. (2000) *Characterization of Natural Organic Matter in Drinking Water*. Denver: American Water Works Association Research Foundation
- Dobrović S., Juretić H. and Ružinski, N. (2007) "Photodegradation of natural organic matter in water with UV irradiation at 185 and 254 nm: Importance of hydrodynamic conditions on the decomposition rate". *Separation Science and Technology*, 42(7) p. 1421-1432
- Dotson A.D., Keen V., Metz D. and Linden K.G. (2010) "UV/H<sub>2</sub>O<sub>2</sub> treatment of drinking water increases post-chlorination DBP formation". *Water Research*, 44(12) p. 3703-3713

- Drinking Water Inspectorate (DWI) (2000) *The Water Supply (Water Quality) Regulations 2000, Statutory Instruments. No. 3184. Water, England and Wales*. Drinking Water Inspectorate
- Drinking Water Inspectorate (DWI) (2010) *DWI PR14 Guidance – Disinfection By-products*. Available at: <http://dwi.defra.gov.uk/stakeholders/price-review-process/PR14-guidance-dpb.pdf> [Accessed: 04/06/2017]
- Drinking Water Inspectorate (DWI) (2014) *Public water supplies - regional reports*. Available at: <http://dwi.defra.gov.uk/about/annual-report/2014/index.html> [Accessed: 23/11/2016]
- Environmental Protection Agency (EPA) (2017) *Drinking Water Requirements for States and Public Water Systems: Stage 1 and Stage 2 Disinfectants and Disinfection Byproducts Rules*. Available at: <https://www.epa.gov/dwreginfo/stage-1-and-stage-2-disinfectants-and-disinfection-byproducts-rules> [Accessed: 13/01/2017]
- European Parliament. Council of the European Union (1998) *Directive 98/83/EC of 3 November 1998 on the quality of water intended for human consumption*
- Farré M.J., Doménech X. and Peral, J. (2007) “Combined photo-Fenton and biological treatment for Diuron and Linuron removal from water containing humic acid”. *Journal of Hazardous Materials*, 147(1) p. 167-174
- Giri R.R., Ozaki H., Ota S., Taniguchi S. and Takanami R. (2010). “Influence of inorganic solids on photocatalytic oxidation of 2, 4-dichlorophenoxyacetic acid with UV and TiO<sub>2</sub> fiber in aqueous solution”. *Desalination*, 255(1) p. 9-14
- Hollrigl-Rosta A., Vinken R., Lenz M. and Schäffer A. (2003) “Sorption and dialysis experiments to assess the binding of phenolic xenobiotics to dissolved organic matter in soil”. *Environmental Toxicology and Chemistry*, 22(4) p. 743-752
- James C.P. (2013) *Advanced oxidation processes for wastewater reuse - removal of micropollutants*. MSc by Research Thesis. Cranfield University

- James C.P., Germain E. and Judd S. (2014) "Micropollutant removal by advanced oxidation of microfiltered secondary effluent for water reuse". *Separation and Purification Technology*, 127 p. 77-83
- Jefferson B., Jarvis P., Bhagianathan G.K., Smith H., Autin O., Goslan E.H., MacAdam J. and Carra, I. (2016) "Effect of elevated UV dose and alkalinity on metaldehyde removal and THM formation with UV/TiO<sub>2</sub> and UV/H<sub>2</sub>O<sub>2</sub>". *Chemical Engineering Journal*, 288 p. 359-367
- Kawamura S. (2000) *Integrated design and operation of water treatment facilities*. 2<sup>nd</sup> Edition. New York: John Wiley & Sons
- Kay P. and Grayson R. (2014) "Using water industry data to assess the metaldehyde pollution problem". *Water and Environment Journal*, 28(3) p. 410–417
- Kim H.C. and Yu M.J. (2005) "Characterization of natural organic matter in conventional water treatment processes for selection of treatment processes focused on DBPs control". *Water Research*, 39(19) p. 4779-4789
- Koutchma T., Keller S., Chirtel S. and Parisi, B. (2004) "Ultraviolet disinfection of juice products in laminar and turbulent flow reactors". *Innovative Food Science & Emerging Technologies*, 5(2) p. 179-189
- Lamsal R., Walsh M.E. and Gagnon G.A. (2011) "Comparison of advanced oxidation processes for the removal of natural organic matter". *Water Research*, 45(10) p. 3263-3269
- Lekkerkerker-Teunissen K., Knol A.H., Derks J.G., Heringa, M.B., Houtman C.J., Hofman-Caris C.H.M., Beerendonk E.F., Reus A., Verberk J.Q.J.C., van Dijk J.C. (2013) "Pilot plant results with three different types of UV lamps for advanced oxidation". *Ozone Science Engineering* 35 p. 38-48
- Lester Y., Avisar D., Gozlan I. and Mamane H. (2011) "Removal of pharmaceuticals using combination of UV/H<sub>2</sub>O<sub>2</sub>/O<sub>3</sub> advanced oxidation process". *Water Science and Technology*, 64(11) p. 2230-2238
- Lucas M.S., Peres J.A. and Puma G.L. (2010) "Treatment of winery wastewater by ozone-based advanced oxidation processes (O<sub>3</sub>, O<sub>3</sub>/UV and O<sub>3</sub>/UV/

- H<sub>2</sub>O<sub>2</sub>) in a pilot-scale bubble column reactor and process economics". *Separation and Purification Technology*, 72(3) p. 235-241
- Martinez S., Delgado M. and Jarvis P (2016) "Removal of Herbicide Mecoprop from Surface Water Using Advanced Oxidation Processes (AOPS)". *International Journal of Environmental Research*, 10(2) p. 291-296
- McArdle B.H. and Anderson M.J. (2001) "Fitting multivariate models to community data: a comment on distance-based redundancy analysis". *Ecology*, 82(1) p. 290-297
- Melin G. (Ed.) (2000) *Treatment Technologies for Removal of Methyl Tertiary Butyl Ether (MTBE) from Drinking Water: Air Stripping, Advanced Oxidation Processes, Granular Activated Carbon and Synthetic Resin Sorbents*. CA: Center for Groundwater Restoration and Protection, National Water Research Institute
- Murray C.A., Goslan E.H., and Parsons S.A. (2007) "TiO<sub>2</sub>/UV: Single stage drinking water treatment for NOM removal?". *Journal of Environmental Engineering and Science*, 6(3) p. 311-317
- Oturan M.A., and Aaron J.J. (2014) "Advanced oxidation processes in water/wastewater treatment: principles and applications. A review". *Critical Reviews in Environmental Science and Technology*, 44(23) p. 2577-2641
- Parsons S.A. and Jefferson B. (2006) *Introduction to potable water treatment processes*. Oxford: Blackwell
- Richardson S.D., Plewa M.J., Wagner E.D, Schoeny R. and DeMarini D.M. (2007) "Occurrence, genotoxicity, and carcinogenicity of regulated and emerging disinfection by-products in drinking water: A review and roadmap for research". *Mutation Research - Reviews in Mutation Research*, 636(1-3) p. 178-242
- Rosenfeldt E.J., Linden K.G., Canonica S. and Von Gunten, U. (2006). "Comparison of the efficiency of OH radical formation during ozonation and the advanced oxidation processes O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> and UV/H<sub>2</sub>O<sub>2</sub>". *Water Research*, 40(20) p. 3695-3704

- Sarathy S. and Mohseni M. (2010) "Effects of UV/H<sub>2</sub>O<sub>2</sub> advanced oxidation on chemical characteristics and chlorine reactivity of surface water natural organic matter", *Water Research*, 44(14) p. 4087-4096
- Sarathy S.R., Stefan M.I., Royce A. and Mohseni M. (2011) "Pilot-scale UV/H<sub>2</sub>O<sub>2</sub> advanced oxidation process for surface water treatment and downstream biological treatment: effects on natural organic matter characteristics and DBP formation potential". *Environmental Technology*, 33 p. 1709–1718
- Semitsoglou-Tsiapou S., Templeton M.R., Graham N.J., Leal L.H., Martijn B.J., Royce A. and Kruithof, J.C. (2016) "Low pressure UV/H<sub>2</sub>O<sub>2</sub> treatment for the degradation of the pesticides metaldehyde, clopyralid and mecoprop—Kinetics and reaction product formation". *Water Research*, 91 p. 285-294
- Sen Kavurmaci S. and Bekbolet M. (2014) "Non-selective oxidation of humic acid in heterogeneous aqueous systems: a comparative investigation on the effect of clay minerals". *Environmental Technology*, 35(18) p. 2389-2400
- Tang L.L., DeNardo M.A., Gayathri C., Gil R.R., Kanda R. and Collins T.J. (2016) "TAML/H<sub>2</sub>O<sub>2</sub> Oxidative Degradation of Metaldehyde: Pursuing Better Water Treatment for the Most Persistent Pollutants". *Environmental Science & Technology*, 50(10) p. 5261-5268
- Templeton M.R., Andrews R.C. and Hofmann R. (2007) "Removal of particle-associated bacteriophages by dual-media filtration at different filter cycle stages and impacts on subsequent UV disinfection". *Water Research*, 41(11) p. 2393-2406
- Toor R. and Mohseni M. (2007) "UV-H<sub>2</sub>O<sub>2</sub> based AOP and its integration with biological activated carbon treatment for DBP reduction in drinking water". *Chemosphere*, 66(11) p. 2087-2095
- Wang G.S. and Hsieh S.T. (2001) "Monitoring natural organic matter in water with scanning spectrophotometer". *Environment International*, 26(4) p. 205-212
- Yang Z., Ren K., Guibal E., Jia S., Shen J., Zhang X. and Yang W. (2016) "Removal of trace nonylphenol from water in the coexistence of suspended inorganic particles and NOMs by using a cellulose-based flocculant". *Chemosphere*, 161 p. 482-490

Yonar T., Kestioglu K. and Azbar N. (2006) "Treatability studies on domestic wastewater using UV/H<sub>2</sub>O<sub>2</sub> process". *Applied Catalysis B: Environmental*, 67(3) p. 223-228



### 3 ECONOMIC EVALUATION OF UV/H<sub>2</sub>O<sub>2</sub>, O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub>, AND O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV PROCESSES THROUGH A WHOLE-LIFE COSTING ANALYSIS FOR FULL-SCALE APPLICATION

David Fernandez Lopez-Rey<sup>1</sup>, Bruce Jefferson<sup>1</sup>, Francis Hassard<sup>1</sup>

<sup>1</sup>*Cranfield Water Science Institute, Cranfield University, Bedford, MK43 0AL.*

#### Abstract

Metolaldehyde is a pesticide which is poorly removed by conventional water treatments. UK water utilities consequently have plans to upscale AOP pilot-scale trials from commercial technologies aiming at metolaldehyde removal due to its demonstrated effectiveness and technical feasibility. However, the high economic cost of real-scale implementation is still a matter of controversy. For decision making, this research presents a site-specific Whole-Life Costing Analysis (WLCA), comparing three AOP systems: O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV, O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> and UV/H<sub>2</sub>O<sub>2</sub> to estimate their T<sub>OTEX</sub> for 5 months annually treatment within 25-year operational life. In doing so, it was possible to determine which technology was most viable for implementation. The costs were calculated for 25 MLD capacity treatment plant based upon the results of 0.72-log metolaldehyde degradation from a treatability pilot-scale research. The AOP asset costs in terms of capital (CAPEX) and operation (OPEX) were covered while achieving the performance necessities, <0.1 µg L<sup>-1</sup> metolaldehyde residual. A sensitivity analysis to reflect variability in T<sub>OTEX</sub> from the price inflation and deflation of energy, hydrogen peroxide and liquid oxygen was also conducted. The cost assessment showed that the benchmark commercial O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> unit outperformed H<sub>2</sub>O<sub>2</sub>/UV owing to the operating costs related to energy demand (E<sub>D</sub>), 84% cheaper. The O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> offered a unit cost of £0.07 m<sup>-3</sup> water treated compared to £0.1 m<sup>-3</sup> and £0.13 m<sup>-3</sup> of UV/H<sub>2</sub>O<sub>2</sub> and O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV, respectively. The O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> process was the most cost-effective treatment for metolaldehyde removal and was the lowest sensitive to reagent and energy price changes.

Keywords: advanced oxidation process, metaldehyde, peroxone, pesticide

### 3.1 Introduction

Metaldehyde often reaches ten times greater concentrations than the European Directive 98/83/EC regulatory levels ( $0.1 \mu\text{L}^{-1}$ ) (Marshall, 2013; Castle *et al.* 2017) evidencing poor removal efficiency of the existing methods, *e.g.* granular activated carbon (GAC) (Autin *et al.*, 2012; Tang *et al.*, 2016). The water industry, therefore, has resorted to different approaches to fulfil drinking water (DW) standards for metaldehyde. A popular initiative followed by a number of UK water suppliers, *e.g.* Severn Trent, Southern Water, Anglian Water, Affinity Water and Thames Water, involves stakeholder engagement in the upstream catchment areas of their rivers. Within this action plan, Southern Water provides with financial incentives ( $\text{£1 kg}^{-1}$ ) for metaldehyde substitution aiming to widespread the use of ferric phosphate (Castle *et al.* 2017). However, the complex nature of catchment dynamics, the variable and limited removal efficiency, up to 60% (Castle *et al.* 2017) and the challenges associated to community commitment to undertake these practices, outside the remit of the water companies, lead to further invest in water treatment processes. Affinity Water, for instance, applied Powdered Activated Carbon (PAC) to diminish metaldehyde levels below the maximum allowable limit (Nabeerasool *et al.*, 2015) Yet a major limitation of PAC is disposal costs. Another proposed option is that of the advanced oxidation processes (AOPs) (Autin *et al.*, 2012; James, Germain and Judd, 2014; Jefferson *et al.*, 2016). This modern 'end-of-pipe' technology achieved up to 97% metaldehyde removal (Semitoglou-Tsiapou *et al.*, 2016). However, AOPs present high capital and operational costs, due to consumables and  $E_D$  impacting decision making on a wider implementation (Autin *et al.*, 2012). Anglian Water reported a  $\text{£17 million year}^{-1}$  estimate to operate UV/H<sub>2</sub>O<sub>2</sub>+GAC system across their 27,500 km<sup>2</sup> supply region (Castle *et al.* 2017).

UV and ozone-based AOPs are the most frequently technologies used at full-scale due to their lower energy consumption than other AOPs (Collins and Bolton, 2016). This finding was previously highlighted after comparing the  $E_D$  required for organic constituents' removal in non-alkaline water using UV/H<sub>2</sub>O<sub>2</sub> ( $5.45 \text{ kWh m}^{-3}$

<sup>3</sup>) and UV/TiO<sub>2</sub> (6.4 kWh m<sup>-3</sup>) (Autin *et al.*, 2013b). Between the commonly used UV and ozone-based AOP alternatives at industrial scale, the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> process was generally less energy intensive to form hydroxyl radicals (•OH) than UV/H<sub>2</sub>O<sub>2</sub> in several water bodies (Rosenfeldt *et al.*, 2006). Tang *et al.* (2016) also reported 33% lower energy demanded by O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> than UV/H<sub>2</sub>O<sub>2</sub> to degrade metaldehyde by 72%. By contrast, 0.54:1.05 kWh ratio (UV/H<sub>2</sub>O<sub>2</sub>:O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub>) was required to generate a mole of •OH under optimum conditions (Bolton and Cater, 1994). Nevertheless, the authors stated the UV process more energy consumptive than the O<sub>3</sub> process in waters with high UV absorbance. Other researchers also agreed with the greater electrical energy efficiency of O<sub>3</sub>-based processes than the UV-based processes for organics mineralization (Crittenden *et al.*, 2012; Gassie and Englehardt, 2017).

The total costs\* for degrading any pollutant from water relies on its particular physical and chemical characteristics (Nabeerasool *et al.*, 2015). The UV/H<sub>2</sub>O<sub>2</sub> treatment cost for different contaminant concentrations were: £0.12-0.58 m<sup>-3</sup> (0.1 mg L<sup>-1</sup>) £0.40-0.89 m<sup>-3</sup> (1 mg L<sup>-1</sup>) and £0.44-1.33 m<sup>-3</sup> (10 mg L<sup>-1</sup>) (Chemviron, 1997). Similarly, total costs were estimated at £1.78 m<sup>-3</sup> for the treatment of 0.2 mg L<sup>-1</sup> trichloroethylene-contaminated groundwater using UV/H<sub>2</sub>O<sub>2</sub> (Hirvonen *et al.*, 1998). Recently, the UV/H<sub>2</sub>O<sub>2</sub> process costed £0.24 m<sup>-3</sup> using synthetic water with 50 mg L<sup>-1</sup> of H<sub>2</sub>O<sub>2</sub> and a spiked solution of five different micropollutants at 0.1 mg L<sup>-1</sup> each (Miralles-Cuevas *et al.*, 2017). UV/H<sub>2</sub>O<sub>2</sub>/O<sub>3</sub> was found the cheapest option per gram of degraded phenol (£0.79 g<sup>-1</sup>), in model wastewater, against £2.42 g<sup>-1</sup> of the UV/H<sub>2</sub>O<sub>2</sub> process (Kusic, Koprivanac and Bozic, 2006). Three-fold greater costs were also found in the UV/H<sub>2</sub>O<sub>2</sub> treatment than that of O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub>, £2.58 m<sup>-3</sup> and £0.90 m<sup>-3</sup> respectively, treating MTBE-contaminated groundwater from 100 mg L<sup>-1</sup> initial concentration and achieving 0.01 mg L<sup>-1</sup> final concentration (Safarzadeh-Amiri, 2001). However, very few publications have appraised the costs incurred on UV-based AOPs for metaldehyde removal (Autin *et al.*, 2013c; James, Germain and Judd, 2014; Rolph, 2016). And, besides that,

---

\* Prices herein presented were £ transformed from their original currencies by using location factors (LF). In section 3.2 the LF approach is explained

non-existent research is available on the costing of peroxone-based AOP processes for the same purposes. Therefore, an economic-assessment comparison of different AOPs (UV/H<sub>2</sub>O<sub>2</sub>, O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub>, and O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV) for addressing metaldehyde with the same water quality needs to be conducted to identify the most economically attractive option for real-scale implementation based on reliable data.

The reliability of AOPs to remove metaldehyde could be appealing for water suppliers, despite their reported high capital and annual operation and maintenance costs (James, Germain and Judd, 2014; Collins and Bolton, 2016). The partial treatment of AOPs throughout yearly cycle can also be coupled with other initiatives, *e.g.* catchment management, to reduce costs. Moreover, legal mechanisms are outlined in the Asset Management Plan 6 period to reduce metaldehyde levels in DW in the UK.

The objective of this study was, therefore, to present a practical and viable life cycle cost comparison between conventional AOPs. A detailed analysis on OPEX and CAPEX of each technology is displayed, as well as a sensitivity analysis of the most economically viable alternatives (UV/H<sub>2</sub>O<sub>2</sub>, and O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub>).

### **3.2 Cost estimation methodology**

The methodology developed to arrive at the costs of a full-scale UV/H<sub>2</sub>O<sub>2</sub>, and O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV process mainly relied on the acquisition of a dataset from either operators, suppliers or research. The dataset was then updated using Location Factors (LF) (Table 9). LF relate costs of similar plants in two different places considering the currency exchange and time. It also captures other costs such as local labour, transport, local tariffs or other import duties, local construction and fabrication infrastructure (Gerrard, 2000; Towler and Sinnott, 2012). Table 9 only includes LF from few countries/world regions. Therefore, some assumptions were adopted when updating the prices:

1. The LF is chosen according to the country/area in which the research was primarily undertaken (correspondence address)


2. When such country is not outlined in Table 9, the LF of a listed country with similar economic/cultural situation in 2017 was chosen, e.g. Italy and Spain
3. The year of the research publication is used as baseline to update the LF by dividing the ratio 'local currency in 2003/\$USA2003' and multiplying by the ratio 'GBP2017/\$USA2017' (Towler and Sinnott, 2012)
4. Annual average exchange rates were taken from The Organisation for Economic Co-operation and Development (OECD) (2017)

All the cost-related assumptions are shown in Table 10. AOPs installation depend upon the water matrix being treated (Rosenfeldt *et al.*, 2006). Therefore, a site-specific WLCA for Draycote sized WTW was undertaken. This WTW supplies 25 MLD ( $1,042 \text{ m}^3 \text{ h}^{-1}$ ) and a five-months uninterrupted running was assumed for providing with metaldehyde  $<0.1 \text{ } \mu\text{g L}^{-1}$  regulatory limit (European Parliament, 1998).

Under the array of metaldehyde inlet concentrations applied in the pilot-trial, a worst-case  $0.53 \text{ } \mu\text{g L}^{-1}$  pesticide level was selected for the AOP facility design. Metaldehyde is within the usual  $0.4\text{--}0.6 \text{ } \mu\text{g L}^{-1}$  range in surface waters (Kay and Grayson, 2014; Semitsoglou-Tsiapou *et al.*, 2016). In order to provide with a safety factor to the WLCA, the electrical energy per order ( $E_{EO}$ ) value, the  $\text{H}_2\text{O}_2$  and  $\text{O}_3$  demands corresponded to metaldehyde results  $<0.1 \text{ } \mu\text{g L}^{-1}$  ( $0.075 \text{ } \mu\text{g L}^{-1}$ ) from the pilot-trial data.

The  $\text{O}_3/\text{H}_2\text{O}_2$  sub process is also assessed as stand-alone unit. Because none of the conditions tested for such  $0.53 \text{ } \mu\text{g L}^{-1}$  initial concentration attained the European Union's statutory DW standard in Chapter 1, the  $\text{O}_3$  concentration reported by Anglian Water to achieve 0.7-log reduction of metaldehyde was considered (Collins and Bolton, 2016). However, the authors did not mention  $\text{H}_2\text{O}_2$  concentration, hence a  $\text{H}_2\text{O}_2:\text{O}_3$  ratio of 0.7 was assumed. This decision was based upon the stoichiometric mass ratio for  $\bullet\text{OH}$  production ( $34 \text{ g mol}^{-1} \text{ H}_2\text{O}_2 / 48 \text{ g mol}^{-1} \text{ O}_3$ ) according to (3-1) (Lucas, Peres and Li Puma, 2010). Moreover, a 0.5-1  $\text{H}_2\text{O}_2:\text{O}_3$  optimal range to remove compounds has been stated

(Ijpelaar *et al.*, 2002) and was previously observed on tetrachloroethylene destruction (Glaze *et al.*, 1987).



As suggested by Ofwat (2013), the WLCA was calculated for 25-year asset life and based on (3-2) to minimise the bias towards CAPEX and to drive benefits for customers.

$$\text{TOTEX} = \text{CAPEX} + \text{NPV} \cdot \text{OPEX} \quad (\text{NPV factor} = 14) \quad (3-2)$$

**Table 9** Location Factors of different countries relative to USA Gulf Coast for prices update based on 2003 data (Towler and Sinnott, 2012)

|                |               |      |
|----------------|---------------|------|
| United States  | Gulf Coast    | 1.00 |
|                | East Coast    | 1.04 |
|                | West Coast    | 1.07 |
|                | Midwest       | 1.02 |
| Canada         | Ontario       | 1.00 |
|                | Fort McMurray | 1.60 |
| Mexico         |               | 1.03 |
| Brazil         |               | 1.14 |
| China          | imported      | 1.12 |
|                | indigenous    | 0.61 |
| Japan          |               | 1.26 |
| SE Asia        |               | 1.12 |
| Australia      |               | 1.21 |
| India          |               | 1.02 |
| Middle East    |               | 1.07 |
| France         |               | 1.13 |
| Germany        |               | 1.11 |
| Italy          |               | 1.14 |
| Netherlands    |               | 1.19 |
| Russia         |               | 1.53 |
| United Kingdom |               | 1.02 |

### 3.2.1 Procedure for OPerating Expenses (OPEX) calculation

Estimated oxidant usage ( $\text{H}_2\text{O}_2$ ,  $\text{O}_3$ ) costs, energy and equipment replacement costs, including the GAC media, accounted for the operational cost incurring on an annual basis in this evaluation. Other life-cycle costs, *e.g.* labour, chemical

delivery, analytical costs, DBPFP or site constraints (Collins and Bolton, 2016) were excluded.

### 3.2.1.1 Chemical costs

The two main consumables involved in the AOPs investigated were  $\text{H}_2\text{O}_2$  and  $\text{O}_3$ . All calculations are based on oxidants dose is constant, assuming the reactor reaches steady-state operation. Therefore, the demand is only a function of the flow rate ( $1,042 \text{ m}^3 \text{ h}^{-1}$ ).

$\text{H}_2\text{O}_2$  35 wt. % commercial strength (20-40%) (American Water Works Association, 2005) was considered. The concentrations that successfully performed to achieve  $<0.1 \mu\text{g L}^{-1}$  in this study (Table 11) were multiplied by the flow rate at Draycote, adjusted by the oxidant purity, to estimate the volume.

Ozone production is carried out with on-site generators (American Water Works Association, 2005) owing to its short half-life (Melin, 2000). This fact involves costing the feeding source, liquid oxygen (LOX) herein.  $\text{O}_3$  is a gas, hence the solubility of  $\text{O}_3$  ( $0.34 \text{ mg L}^{-1}$  in  $\text{H}_2\text{O}_2$  per  $1 \text{ mg L}^{-1}$  of gas,  $20^\circ\text{C}$ ) (Stumm, 1958 in Roth and Sullivan, 1981) was used to determine the actual concentration required in the ozone generator. Select LOX over air was built upon a number of reasons. Energy requirements using dried compressed air for  $\text{O}_3$  generation was quantified as  $15 \text{ kWh kg}^{-1} \text{ O}_3$  produced (Katsoyiannis *et al.* 2011) and  $18\text{-}26 \text{ kWh kg}^{-1}$  (Rosenfeldt *et al.*, 2006; Wu and Englehardt; 2015). However, energy needs applying high purity oxygen fed system such as LOX are substantially lower ( $5\text{-}8 \text{ kWh kg}^{-1}$ ) (American Water Works Association, 2005; Smith, 2011). Furthermore, LOX is typically used since 1995 (Rakness, 2011). And besides, the use of an air fed generator requires dehumidification, which may be cost prohibitive in comparison to LOX (Melin, 2000). Finally, processing LOX by modern medium-frequency generators enables 8 to 12% by weight  $\text{O}_3$  concentration production versus 1.5-2% using air (Kawamura, 2000). Therefore,  $7 \text{ kWh kg}^{-1}$  mid-way point for  $\text{O}_3$  production was considered. A commercial ozone generator system producing at  $1 \text{ m}^3 \text{ h}^{-1}$  (10 wt. % ozone in oxygen) (supplier data) was selected. Such percentage weight entailed ten-fold amount of LOX to produce the daily required amount of  $\text{O}_3$ . Moreover,  $\text{O}_3$  production by high-voltage altering current

(6 to 20 kV) (Kawamura, 2000), 5.5 kV in the pilot trial, added to LOX chemical costs 4,118 kW day<sup>-1</sup> (O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV) and 5,147 kW day<sup>-1</sup> (O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub>).

### 3.2.1.2 Electrical efficiency per order of contaminant destruction

For UV systems, a measure of operating cost and accurate scale up system is the E<sub>EO</sub> (Bolton *et al.*, 2001; James, Germain and Judd, 2014). The E<sub>EO</sub> is the energy (kWh) consumed to reduce an initial concentration of contaminant by one order of magnitude in a unit volume. By this way, the comparison of the efficiency between processes can be undertaken on the basis of the electrical use per amount of compound reduction. The E<sub>EO</sub> is defined for flow-through reactors (3-3) (Collins and Bolton, 2016) as:

$$E_{EO} = \frac{P}{\dot{V} \log \left( C_i / C_f \right)} \quad (3-3)$$

Where P is the electrical power (kW),  $\dot{V}$  is the flow rate (m<sup>3</sup> h<sup>-1</sup>), and C<sub>i</sub> and C<sub>f</sub> are the initial and final concentrations of a targeted pollutant. Given the E<sub>EO</sub>, the power requirements were calculated for the processes (Table 11) and, thus the annual energy costs.

### 3.2.1.3 High-cost components replacement

For the three AOP case study, 58,915 kg year<sup>-1</sup> GAC media needed to be regenerated off-site (EPA, 2014) assuming 10% loss of GAC per regeneration (James, Germain and Judd, 2014). With regards UV-based AOPs, lamp replacement was calculated according to (3-4). In the case of the peroxone AOP replacements, 1.5% of the O<sub>3</sub> generator and contactor capital cost was assumed (Melin, 2000; Mahamuni and Adewuyi, 2010).

$$\text{Replacement cost yr}^{-1} = \frac{24 \text{ h} \cdot 30 \text{ d} \cdot 5 \text{ months}}{9000 \text{ h (lifetime)}} \cdot n^{\circ} \text{ lamps} \cdot \text{£}300 \text{ lamp}^{-1} \quad (3-4)$$

**Table 10** Assumptions for OPEX and CAPEX costing analysis from treatability studies and supplier information

| Component                               | Cost                                                                                                                                                                                                                                | Reference                                   | Country  | LF-updated costs            |
|-----------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------|----------|-----------------------------|
| H <sub>2</sub> O <sub>2</sub> prices    | \$0.295 L <sup>-1</sup>                                                                                                                                                                                                             | Ince and Apikyan (2000)                     | Turkey   | £0.3 kg <sup>-1</sup>       |
|                                         | \$0.51 kg <sup>-1</sup>                                                                                                                                                                                                             | Solmaz <i>et al.</i> (2009)                 | Turkey   |                             |
|                                         | €0.39 kg <sup>-1</sup>                                                                                                                                                                                                              | Rueda-Márquez <i>et al.</i> (2010)          | Spain    |                             |
|                                         | €0.24 kg <sup>-1</sup>                                                                                                                                                                                                              | Lucas, Peres and Puma (2010)                | Portugal |                             |
|                                         | €0.55 kg <sup>-1</sup>                                                                                                                                                                                                              | Yalili, Yonar and Kestioğlu (2013)          | Turkey   |                             |
|                                         | £270 m <sup>-3</sup>                                                                                                                                                                                                                | Autin <i>et al.</i> (2013b)                 | UK       |                             |
|                                         | €0.73 L <sup>-1</sup>                                                                                                                                                                                                               | Cédat <i>et al.</i> (2016) from Solvay S.A. | France   |                             |
| Cost H <sub>2</sub> O <sub>2</sub> tank | Large tank cost curve for preliminary estimates                                                                                                                                                                                     | Gerrard (2000)                              | UK       | N/A                         |
| Electricity price                       | £0.1 kWh <sup>-1</sup>                                                                                                                                                                                                              | Energy EU (2017)                            | UK       | £0.1 kWh <sup>-1</sup>      |
| GAC off-site regeneration               | £0.31-0.44 kg <sup>-1</sup> , assuming 5-10% loss of GAC per regeneration                                                                                                                                                           | James, Germain and Judd (2014)              | UK       | £0.51 kg <sup>-1</sup>      |
| UV reactor                              | £900,000 unit <sup>-1</sup>                                                                                                                                                                                                         | Supplier                                    | UK       | £900,000 unit <sup>-1</sup> |
| Number of lamps per UV reactor          | 192 bulbs                                                                                                                                                                                                                           | Supplier                                    | UK       | 192 bulbs                   |
| Power per lamp                          | 1.00 kW                                                                                                                                                                                                                             | Supplier                                    | UK       | 1.00 kW                     |
| Lamp price                              | £223 lamp <sup>-1</sup> (9,000h lifetime) LP-HO                                                                                                                                                                                     | James (2013)                                | UK       | £300 lamp <sup>-1</sup>     |
| LOX price                               | \$0.04 lb <sup>-1</sup>                                                                                                                                                                                                             | Kawamura (2000)                             | USA      | £0.07 kg <sup>-1</sup>      |
| Ozone generation unit (\$)              | 31,015x <sup>0.6475</sup> ; x=O <sub>3</sub> generation capacity (Lb d <sup>-1</sup> , min. 10, max. 3,500). Including: LOX tanks, vaporizer and regulators, piping, valves, flow meters, filters and the O <sub>3</sub> generators | McGivney and Kawamura (2008)                | USA      | N/A                         |
| Ozone contact chamber (per unit) (\$)   | 89.217x <sup>0.6442</sup> ; x= Chamber volume (GAL; min. 1,060, max. 423,000). Including: piping, valves, diffusers and, air handling system, which collects and delivers the residual ozone to the destruct unit                   |                                             |          |                             |

N/A: not applicable

### **3.2.2 Procedure for CAPital EXpenditures (CAPEX) calculation**

The total plant cost was estimated by breaking down the total capital employed into different categories of expenditure. All these clusters are percentage-related to the total delivered cost of the main plant items (MPI) purchased for fluid-processing plants (Gerrard, 2000). However, Gerrard's (2000) percentages were adapted for an AOP facility (Melin, 2000; Mahamuni and Adewuyi, 2010).

Direct costs included controls and instrumentation (18% MPI cost), piping, valves and electrical (30% MPI cost), and buildings, including services, (18% MPI cost). The purchase of land, nor yard improvements were accounted. The sum of these categories provides the total direct plant cost (Gerrard, 2000). Indirect costs comprised engineering and supervision (33% MPI cost), construction expenses (41% MPI cost), the contractor's fee (21% MPI cost), contingency (20% MPI cost) and working capital (86% MPI cost). The total capital employed was obtained by adding the indirect costs to the total direct plant costs.

#### **3.2.2.1 Main plant items cost (MPIC)**

From the manufacturer quotations with regards the number of lamps per UV reactor and their power (Table 10), the number of such standard commercial equipment to cover the electrical power demand was obtained (Table 11). Therefore, the number of lamps required was divided by the number of lamps per UV unit. The cost of the UV equipment and the lamps was then calculated by multiplying the requirements by their LF-updated prices (Table 10). UV commercial unit is equipped with low-pressure high-output (LPHO) lamps. This type of Hg discharge lamps is usual in AOTs (Collins and Bolton, 2016) which better facilitate •OH formation in H<sub>2</sub>O<sub>2</sub> presence and are electrically more efficient than medium pressure lamps (Melin, 2000; Lekkerkerker-Teunissen *et al.*, 2013), which gave the formation of genotoxic activity (Lekkerkerker-Teunissen *et al.*, 2013). However, LPHO lamps produce lower UV output per unit (1 kW) than medium pressure lamps (Melin, 2000; Van der Meer, van Lierop and LIT, 2015).

In the case of the ozone system, the ozone generation equipment and contactor accounted for the MPIC. Both costs were calculated using empirical formulae

(Table 10) (McGivney and Kawamura, 2008). The contact chamber equation requires the volume of ozone required, thus  $2.0 \text{ kg m}^{-3} \text{ O}_3$  density ( $20^\circ\text{C}$ , 1 atm) was utilised (Kawamura, 2000). The international units were subsequently transformed to those indicated by the authors. Two contact units were considered for system maintenance and redundancy (McGivney and Kawamura, 2008) as well as two  $\text{O}_3$  generators operating at 75% of rated capacity (Kawamura, 2000).

When  $\text{O}_3$  is diffused across the water, some gas inevitable reaches the top of the contact tank. Consequently, the  $\text{O}_3/\text{H}_2\text{O}_2$  process requires of  $\text{O}_3$  destructors to avoid the release of the residual gas to the atmosphere. Similarly, large amount of heat is generated when producing  $\text{O}_3$ , so there is the need of a cooling system. The destructor and the cooling system, however, were not scoped in the WLCA due to lack of information, yet they have an energy-cost impact to consider within the  $\text{O}_3/\text{H}_2\text{O}_2$  process.

For the hydrogen peroxide tank cost, a nomographical approach was followed (Gerrard, 2000). On the basis of the oxidant volume monthly required (Maher, personal communication, 2017), 15% headspace was added for gas expansion. A maximum  $25 \text{ m}^3$  (up to  $30 \text{ m}^3$ ) (Cefic, 2001) tank was considered. Therefore, if excess volume resulted in the calculations, this was divided by the minimum number of tanks covering the demand:  $3 \times 25 \text{ m}^3$  ( $65 \text{ m}^3$ ) ( $\text{UV}/\text{H}_2\text{O}_2$ ),  $2 \times 20 \text{ m}^3$  ( $35 \text{ m}^3$ ) ( $\text{O}_3/\text{H}_2\text{O}_2 + \text{H}_2\text{O}_2/\text{UV}$ ) and  $1 \times 15 \text{ m}^3$  ( $\text{O}_3/\text{H}_2\text{O}_2$ ).

GAC capital costs were modelled using EPA (2014) upon the basis on GAC working as secondary filter, as it did in the pilot-trial. Therefore, 14-days interval between backwashes and recycling option for the spent backwashes was assumed (Kaur, personal communication, 2017). The input parameters were the design type (pressure), in parallel operation, 15 minutes theoretical empty bed contact time and regeneration off-site. These assumptions were founded on a similar AOP-based WTW cost exercise (Collins and Bolton, 2016). The design flow was input at MGD (6.604).  $\text{H}_2\text{O}_2$  did not seem to affect GAC quenching performance neither in batch test nor after years of use at full-scale (Li, Zamyadi and Hofmann, 2016). However, Li, Zamyadi and Hofmann (2016) also reported fouling effects of natural organic matter (NOM) on GAC reducing its performance.

Therefore, carbon life span of 2 years was considered. Moreover, this assumption can be supported by the GAC-buffering contribution to minimise DBPs after AOPs, as concluded in Chapter 1. GAC capital cost included the GAC contactors, tanks, valves, pumps and instrumentation (propellers, alarms, pH meters, turbidity meters, temperature meters, carbon steel sampling port and head loss sensors), and initial GAC media charge (52,603 kg) (EPA, 2014). Other components such as the H<sub>2</sub>O<sub>2</sub> injection system, supply and discharge pumps, and mixers were excluded since (i) these assets either make up a small component of the MPIC and/or (ii) the same assumption was made for the three AOPs. However, as in any WLCA, the quality of the cost estimate is the product of the input data quality and the approach taken.

### 3.3 Results and discussion

According to the pilot plant conditions studied, a benchmarking between the CAPEX, OPEX and Total EXpenditures (TOTEX) of each potential AOP treatment plant and the cost per cubic meter annually treated was calculated (Table 11 and Table 12). Over the 25-year project lifetime, the total cost (TOTEX) of the two-stage AOP was £30,406,141; considerably 41.5% (UV/H<sub>2</sub>O<sub>2</sub>) and 49.7% (O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub>) higher than that of the separated sub processes due to both capital and operational expenditures. Nevertheless, UV lamp replacement (£58,849) and ozone equipment replacement (£38,007) were cheaper in the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV treatment. These two OPEX savings were attributed to lower UV power required than for UV/H<sub>2</sub>O<sub>2</sub>, hence fewer lamps to be replaced with time (Table 12), and lower O<sub>3</sub> doses than that of O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> (Table 11). For the UV/H<sub>2</sub>O<sub>2</sub> process, Cédât *et al.* (2016) reported similar 0.155 € m<sup>-3</sup> (£0.12 m<sup>-3</sup> using LF) the total OPEX and 0.059 € m<sup>-3</sup> (£0.047 m<sup>-3</sup> using LF) the electricity costs, removing 80% estrogenic hormones at 30 mg L<sup>-1</sup> H<sub>2</sub>O<sub>2</sub> and 563 mJ cm<sup>-2</sup> UV fluences.

Annual GAC regeneration for the three technologies was equally estimated at £33,051 as the same design flow is treated. The E<sub>EO</sub> for the UV/H<sub>2</sub>O<sub>2</sub> was lower than that of the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV (Table 11). This indicated UV/H<sub>2</sub>O<sub>2</sub> higher energy efficiency as greater levels of pesticide destruction resulted with less energy input. However, the H<sub>2</sub>O<sub>2</sub>/UV sub process only required 0.32-log

reduction to achieve  $<0.1 \mu\text{g L}^{-1}$  (0.72-log reduction for UV/H<sub>2</sub>O<sub>2</sub>). This was because 60% pesticide was previously removed by O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub>. This result explained the greater electrical power, thus  $E_D$  (kWh m<sup>-3</sup>), of the stand-alone UV/H<sub>2</sub>O<sub>2</sub> process (Table 11) than for the H<sub>2</sub>O<sub>2</sub>/UV.

Compared to the UV/H<sub>2</sub>O<sub>2</sub>, the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> had a 40.2% lower OPEX and 0.9% greater CAPEX. Costly O<sub>3</sub> generators daily producing 735 kg O<sub>3</sub> explained the 0.9% difference between their CAPEX. A note of caution is due here since the capital cost of the generation system, as well as the contactors, is likely to be different since McGivney and Kawamura's (2008) empirical method was applied because of the lack of a suitable industrial quote. Equally, the WLCA of the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> relied on a theoretical oxidant mass ratio. Further experimental work needs to examine more closely the optimum H<sub>2</sub>O<sub>2</sub>:O<sub>3</sub> ratio in order to validate these results.

As similar capital costs were found for both AOPs (Table 12), OPEX was the driving factor for suggesting to implement an O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> as the most economically feasible alternative for metaldehyde removal purposes. The use of energy was the principal component of the OPEX cost in all the systems (Figure 8). On average it represented 43% of the total OPEX cost. For the UV/H<sub>2</sub>O<sub>2</sub> case the energy consumption was attributed to 50% of the OPEX, almost twice the cost of H<sub>2</sub>O<sub>2</sub> (£96,429). This outcome is contrary to that of Rosenfeldt *et al.* (2006) where the UV portion of the OPEX accounted for less than 10%. However, James, Germain and Judd (2014) estimated 65% the energy consumption. For the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub>, 31% OPEX costs were attributed to electricity consumption due to ozone production, whilst 39% were for oxidants (LOX + hydrogen peroxide) (£99,706) (Figure 8). Finally, the fact that O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> was 84% more cost-effective energy-saving than the UV/H<sub>2</sub>O<sub>2</sub>, in agreement with previous findings (Rosenfeldt *et al.*, 2006; Crittenden *et al.*, 2012), explained the higher operational costs of the UV-based technology, and thus greater TOTEX. Energy costs subtraction from TOTEX in both treatments rendered around only £400,000 difference between their TOTEX (£17.3 million for UV/H<sub>2</sub>O<sub>2</sub> and £16.9 million for O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub>). Ways of reducing energy costs on-site throughout the development of UV technology, *e.g.*

LED (light-emitting diode) would boost the use of UV/H<sub>2</sub>O<sub>2</sub> over O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub>. The peroxone process needs to be technically improved, in terms of the optimum oxidant ratio for metaldehyde-compliant water production regardless MIC. However, with the current state-of-art, it can thus be concluded that the UV/H<sub>2</sub>O<sub>2</sub> technology is less economically attractive option for a potential full-scale plant installation at the given discount rate and project life.

The £19.96 million TOTEX costs estimated in this research for UV/H<sub>2</sub>O<sub>2</sub> corroborated the £19-40 million whole life costs obtained by Rolph (2016). However, the advantages of this study were (i) the capital costs of the UV system considered the actual number of UV units required for the process, (ii) this approach also considered the number of lamps as well as (iii) the installation of a GAC system for H<sub>2</sub>O<sub>2</sub> residual quenching not already in place and (iv) the H<sub>2</sub>O<sub>2</sub> tank too. Similarly, the percentages of direct and indirect costs as piping, engineering and contingency differed between both research.

**Table 11** AOP treatment conditions tested in the research achieving <0.1 µg L<sup>-1</sup> metaldehyde and associated OPEX relating to such conditions

| Process                                                          | O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> + H <sub>2</sub> O <sub>2</sub> /UV | UV/H <sub>2</sub> O <sub>2</sub> | O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> |
|------------------------------------------------------------------|-----------------------------------------------------------------------------------|----------------------------------|-----------------------------------------------|
| H <sub>2</sub> O <sub>2</sub> (mg L <sup>-1</sup> ) <sup>a</sup> | 16                                                                                | 30                               | 10                                            |
| O <sub>3</sub> (mg L <sup>-1</sup> )                             | 8                                                                                 | N/A                              | 10                                            |
| E <sub>D</sub> (kWh m <sup>-3</sup> )                            | 0.54                                                                              | 0.66                             | N/A                                           |
| E <sub>EO</sub> (kWh m <sup>-3</sup> order <sup>-1</sup> )       | 1.49                                                                              | 0.699                            | N/A                                           |
| UV power (kW)                                                    | 490.41                                                                            | 524.97                           | N/A                                           |
| OPEX (£ m <sup>-3</sup> ) <sup>b</sup>                           |                                                                                   |                                  |                                               |
| Energy                                                           | 0.064                                                                             | 0.050                            | 0.021                                         |
| Chemicals                                                        | 0.030                                                                             | 0.026                            | 0.027                                         |
| GAC                                                              | 0.009                                                                             | 0.009                            | 0.009                                         |
| Lamp replacement                                                 | 0.016                                                                             | 0.017                            | N/A                                           |
| O <sub>3</sub> equipment replacement                             | 0.010                                                                             | N/A                              | 0.012                                         |
| TOTAL                                                            | 0.128                                                                             | 0.102                            | 0.068                                         |

N/A not applicable; <sup>a</sup> 1.135 g mL<sup>-1</sup> density; <sup>b</sup> OPEX: yearly cost of each category divided by (25MLd<sup>-1</sup> · 30 d · 5 months of treatment)

The WLCA of this research was normalised to Rolph's (2016) assumptions to be comparable. Therefore, the UV/H<sub>2</sub>O<sub>2</sub> CAPEX herein calculated would drop to £1.7 million, slightly more costly than the range estimated by the author (£0.9-1.5

million). Nevertheless, this greater capital expenditure is globally balanced in the TOTEX by the likely overestimated OPEX range (£1.3-2.8 million), depending on the water quality, suggested by Rolph (2016). The length of the treatment was not equally mentioned in Rolph's (2016), thus a 12-month run can be inferred. Consequently, as per the author's criterion, the OPEX of this research would increase until £0.9 million. Overall, the UV/H<sub>2</sub>O<sub>2</sub> TOTEX based on Rolph's (2016) assumptions would be £14.5 million, at least £4.5 million cheaper than that of the Rolph's (2016) estimates.

Other options for metaldehyde removal were also appraised. The WLCA of a 20MLD catchment management alternative was estimated at £11,000K (Rolph, 2016). Therefore, a 25 MLD catchment plan for metaldehyde removal would roughly cost £13.75 million, remaining only £0.75 million cheaper than a UV based AOP. Similarly, a biological treatment using fluidised bed bioreactors (FBBR) on a 20MLD WTW was estimated around £15 million TOTEX (Rolph, 2016), thus it is expected to be even more expensive for a 25MLD WTW. Despite of the FBBR lower environmental footprint and chemical costs than AOPs, this technology was 90% electricity dependent (Rolph, 2016). Hence, energy price inflation would increase metaldehyde treatment costs. The final option is to ignore any investment, thus metaldehyde standard could be breached. This unjustifiable decision would only lead to a negative impact on public perception and a number of potential penalties.

A sensitivity analysis was performed to predict the effects of input data variation on the TOTEX outcome (Figure 9). This analysis was restricted to three price inflation scenarios based on those operating costs that exhibited the greatest influence in each treatment (electricity consumption, H<sub>2</sub>O<sub>2</sub> and LOX). The sensitivity of the life-cycle costs to each price was examined by allowing one such price to vary while holding constant the other two. The results showed that UV/H<sub>2</sub>O<sub>2</sub> is more sensitive to changes in the energy price than O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> (Figure 9a). The steeper the slope of the curve, the greater the effect on the total expenditure in such AOP. The peroxone process remained cheaper than UV/H<sub>2</sub>O<sub>2</sub> for a free energy bill by £86,017. However, the impacts of global

warming on energy consumption are estimated to raise the price rather than to cut it down. Similarly, a UV/H<sub>2</sub>O<sub>2</sub> plant was more costly by £615,972 than an O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> full-scale installation even if H<sub>2</sub>O<sub>2</sub> price was deflated to £0 kg<sup>-1</sup> (Figure 9b). Moreover, TOTEX on the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> process would only increase by 0.86% if H<sub>2</sub>O<sub>2</sub> becomes 50% more expensive, whilst 3.38% greater TOTEX was found for the UV/H<sub>2</sub>O<sub>2</sub>.




**Figure 8** Breakdown of the operating expenses (OPEX) and capital expenses (CAPEX) for a UV/H<sub>2</sub>O<sub>2</sub>; O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV and O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> 25 MLD DW treatment plant reducing metaldehyde levels <0.1 µg L<sup>-1</sup>

**Table 12** Estimated capital expenditures for metaldehyde treatment using commercial UV and O<sub>3</sub>-based AOPs

| Parameter                                   | O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> + H <sub>2</sub> O <sub>2</sub> /UV |                   | H <sub>2</sub> O <sub>2</sub> /UV |                   | O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> |                   |
|---------------------------------------------|-----------------------------------------------------------------------------------|-------------------|-----------------------------------|-------------------|-----------------------------------------------|-------------------|
| <b>Direct costs</b>                         |                                                                                   |                   |                                   |                   |                                               |                   |
| UV system                                   |                                                                                   |                   |                                   |                   |                                               |                   |
| UV Reactor                                  |                                                                                   |                   |                                   |                   |                                               |                   |
| Number of UV units                          |                                                                                   | 3                 |                                   | 3                 |                                               |                   |
| Total cost                                  | £                                                                                 | 2,700,000         | £                                 | 2,700,000         |                                               |                   |
| LP-HO amalgam lamps                         |                                                                                   |                   |                                   |                   |                                               |                   |
| Number of bulbs                             |                                                                                   | 490               |                                   | 525               |                                               | N/A               |
| Total cost                                  | £                                                                                 | 147,124           | £                                 | 157,490           |                                               |                   |
| Ozone system                                |                                                                                   |                   |                                   |                   |                                               |                   |
| Ozone generation equipment                  | £                                                                                 | 2,407,606         |                                   | N/A               | £                                             | 2,781,855         |
| Ozone contactor                             | £                                                                                 | 126,174           |                                   |                   | £                                             | 145,669           |
| Peroxide tank                               | £                                                                                 | 28,000            | £                                 | 44,000            | £                                             | 11,500            |
| GAC                                         | £                                                                                 | 1,146,872         | £                                 | 1,146,872         | £                                             | 1,146,872         |
| <b>Main plant items cost</b>                | <b>£</b>                                                                          | <b>6,555,775</b>  | <b>£</b>                          | <b>4,048,426</b>  | <b>£</b>                                      | <b>4,085,896</b>  |
| Instrumentation and control                 | £                                                                                 | 1,180,039         | £                                 | 728,717           | £                                             | 735,461           |
| Piping, valves and electrical               | £                                                                                 | 1,966,732         | £                                 | 1,214,528         | £                                             | 1,225,769         |
| Buildings (including services)              | £                                                                                 | 1,180,039         | £                                 | 728,717           | £                                             | 735,461           |
| <i>Total direct plant cost</i>              | £                                                                                 | 10,882,586        | £                                 | 6,720,388         | £                                             | 6,782,588         |
| <b>Indirect costs</b>                       |                                                                                   |                   |                                   |                   |                                               |                   |
| Engineering and supervision                 | £                                                                                 | 2,163,406         | £                                 | 1,335,981         | £                                             | 1,348,346         |
| Construction expenses                       | £                                                                                 | 2,687,868         | £                                 | 1,659,855         | £                                             | 1,675,217         |
| <i>Total direct and indirect plant cost</i> | £                                                                                 | 15,733,860        | £                                 | 9,716,223         | £                                             | 9,806,151         |
| Contractor's fee                            | £                                                                                 | 983,366           | £                                 | 607,264           | £                                             | 612,884           |
| Contingency                                 | £                                                                                 | 1,311,155         | £                                 | 809,685           | £                                             | 817,179           |
| <i>Total erected cost</i>                   | £                                                                                 | 18,028,381        | £                                 | 11,133,172        | £                                             | 11,236,215        |
| Working capital                             | £                                                                                 | 5,637,966         | £                                 | 3,481,647         | £                                             | 3,513,871         |
| <b>Total capital employed</b>               | <b>£</b>                                                                          | <b>23,666,347</b> | <b>£</b>                          | <b>14,614,819</b> | <b>£</b>                                      | <b>14,750,085</b> |

The O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> would only become less profitable if the LOX price was increased by more than 153% (£0.177 kg<sup>-1</sup>) (Figure 9c) as UV/H<sub>2</sub>O<sub>2</sub> is cost independent of such price. It can be concluded that UV/H<sub>2</sub>O<sub>2</sub> is significantly more susceptible to price inflation than O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub>. All these outcomes are worth of consideration for industry decision makers.




**Figure 9** Influence of prices inflation in terms of (a) energy (b) H<sub>2</sub>O<sub>2</sub> and (c) LOX on the TOTEX of UV/H<sub>2</sub>O<sub>2</sub> (▲) and O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> (●) to reach the cost neutral point between both treatments

### 3.4 Conclusions

DW contamination by metaldehyde in treated waters, exceeding the permitted levels, challenges UK water supplier performance. AOPs have been studied at pilot and lab-scale to address metaldehyde removal not effectively achieved by conventional methods. However, AOPs are considered an expensive alternative with high running and infrastructure costs whose implementation would only be justified for significantly affected niche cases if effluent quality compliance is at risk. Nevertheless, to date, no published studies have indeed assessed the economic viability of two different AOPs fed with the same water quality through a WLCA after demonstrating their efficacy for pesticide removal. A site-specific

WLCA over 25-year period was undertaken from the UV/H<sub>2</sub>O<sub>2</sub>, and O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV results presented in Chapter 1 that achieved <0.1 µg L<sup>-1</sup> metaldehyde residual for a conservative 0.72-log pesticide reduction. O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> became the benchmark for the treatment of metaldehyde at the most affordable total costs. Estimated O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> TOTEX was £18,304,347 saving £1.65 million regarding the UV/H<sub>2</sub>O<sub>2</sub> and £12.1 million with respect to the O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV. The O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> process was 40.2% lower in OPEX (£0.07 m<sup>-3</sup>) and similar in CAPEX than the UV/H<sub>2</sub>O<sub>2</sub> for 5-months annual treatment. The O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> lower operating expenditure mainly resulted from its 84% lower energy costs. Therefore, electricity consumption was pivotal to the economic viability of both AOPs evaluated. However, O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> WLCA was based upon a 0.7 stoichiometric oxidant mass ratio assumption and a pilot-scale experience in the Anglian Water region that similarly achieved up to a 0.7-log pesticide removal. This decision was fundamentally made due to the limited performance of the sub process within the two-stage AOP (O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV) to meet regulatory levels in the pilot-scale study. Therefore, further research should carefully optimize H<sub>2</sub>O<sub>2</sub>:O<sub>3</sub> critical process mass ratio for metaldehyde removal to verify the cost estimates. UV/H<sub>2</sub>O<sub>2</sub> showed greater sensitivity to energy and H<sub>2</sub>O<sub>2</sub> price volatility than O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub>, hence greater risk associated if full-scale implemented. LED-based breakthrough technology would likely incline water utilities to use technically reliable UV/H<sub>2</sub>O<sub>2</sub> over O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub>. Nevertheless, UV/H<sub>2</sub>O<sub>2</sub> remained more affordable than alternative control methods for removing metaldehyde such as biological treatment when this research was normalised at equal assumptions to those of previous studies.

Notwithstanding the cost assumptions and modelling based approach to estimate the expenditures of some assets, this study offers an insight outline for preparing a good AOP cost estimate for a real water treatment plant. This work, therefore, has important implications for DW utilities as it suggests that O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> and UV/H<sub>2</sub>O<sub>2</sub> are robust for metaldehyde removal and an economically viable alternative to source control interventions.

### 3.5 Acknowledgments

Severn Trent Water is gratefully acknowledged for the financial support

### 3.6 References

- American Water Works Association (2005) *Water treatment plant design*. 4<sup>th</sup> Edition. New York: McGraw Hill
- Autin O., Hart J., Jarvis P., MacAdam J., Parsons S.A and Jefferson B. (2012) "Comparison of UV/H<sub>2</sub>O<sub>2</sub> and UV/TiO<sub>2</sub> for the degradation of metaldehyde: Kinetics and the impact of background organics". *Water Research*, 46 p. 5655-5662
- Autin O., Hart J., Jarvis P., MacAdam J., Parsons S.A and Jefferson B. (2013b) "Comparison of UV/H<sub>2</sub>O<sub>2</sub> and UV/TiO<sub>2</sub> processes in an annular photoreactor for removal of micropollutants: Influence of water parameters on metaldehyde removal, quantum yields and energy consumption". *Applied Catalysis B: Environmental*, 138–139 p. 268–275
- Autin O., Romelot C., Rust L., Hart J., Jarvis P., MacAdam J., Parsons S. and Jefferson B. (2013c) "Evaluation of a UV-light emitting diodes unit for the removal of micropollutants in water for low energy advanced oxidation processes". *Chemosphere*, 92(6), p. 745-751
- Bolton J.R. and Cater S.R. (1994) "Homogeneous photodegradation of pollutants in contaminated water: An Introduction" in Helz G., Zepp R. and Crosby D. (ed.) *Surface and aquatic environmental photochemistry*. Boca Raton p. 467-490
- Bolton J.R., Bircher K.G., Tumas W. and Tolman C.A. (2001) "Figures-of-merit for the technical development and application of advanced oxidation technologies for both electric- and solar-driven systems". *Pure and Applied Chemistry*, 73(4) p. 627-637
- Castle G.D., Mills G.A., Gravell A., Jones L., Townsend I., Cameron D.G. and Fones G.R. (2017) "Review of the molluscicide metaldehyde in the environment". *Environmental Science: Water Research & Technology*, 3(3) p. 415-428

- Cédât B., de Brauer C., Métivier H., Dumont N.b and Tutundjian R. (2016) “Are UV photolysis and UV/H<sub>2</sub>O<sub>2</sub> process efficient to treat estrogens in waters? Chemical and biological assessment at pilot scale”. *Water Research*, 100 p. 357-366
- Chemviron Carbon Oxidation Technologies (1997) *AOT Handbook*. Germany
- Collins J. and Bolton J.R. (2016) *Advanced Oxidation Handbook* Denver: American water Works Association
- European Parliament. Council of the European Union (1998) *Directive 98/83/EC of 3 November 1998 on the quality of water intended for human consumption*
- Crittenden J.C., Trussell R.R., Hand D.W., Howe K.J. and Tchobanoglous G. (2012) *Frontmatter, in MWH's Water Treatment: Principles and Design*. 3<sup>rd</sup> Edition Hoboken: John Wiley & Sons
- Energy EU (2017). Available at: <http://www.energy.eu/Website> [accessed 19/08/17]
- Environmental Protection Agency (EPA) (2014) Drinking Water Treatment Technology Unit Cost Models and Overview of Technologies. Available at: <https://www.epa.gov/dwregdev/drinking-water-treatment-technology-unit-cost-models-and-overview-technologies> [Accessed: 03/08/2017]
- European Chemical Industry Council (Cefic) (2001) *Peroxygens: Hydrogen peroxide subgroup. Bulk storage guideline*. Available at [http://www.verbondpk.nl/wp-content/uploads/2017/03/13\\_Bijlage-5-CEFIC-Guidelines-storage-H2O2.pdf](http://www.verbondpk.nl/wp-content/uploads/2017/03/13_Bijlage-5-CEFIC-Guidelines-storage-H2O2.pdf) [Accessed: 10/08/2017]
- Gassie L.W. and Englehardt J.D. (2017) “Advanced oxidation and disinfection processes for onsite net-zero greywater reuse: A review”. *Water Research*, in Press –accepted manuscript
- Gerrard A.M. (Ed.) (2000) *Guide to capital cost estimating*. 4th Edition. Rugby: IChemE
- Glaze W.H., Kang J.W. and Chapin D.H. (1987) “The chemistry of water treatment processes involving ozone, hydrogen peroxide and ultraviolet radiation”. *Ozone Science and Engineering*, 9 p 335-352

- Hirvonen A., Tuhkanen T., Ettala M., Korhonen S. and Kalliokoski P. (1998) "Evaluation of a Field-Scale UV/H<sub>2</sub>O<sub>2</sub>-Oxidation System for the Purification of Groundwater Contaminated with PCE". *Environmental Technology*, 19(8) p. 821-828
- Ijpelaar G.F., Groenendijk M., Hopman R. and Kruithof J.C. (2002) "Advanced oxidation technologies for the degradation of pesticides in ground water and surface water". *Water Science and Technology: Water Supply*, 2(1) p. 129–138
- Ince N. H. and Apikyan, I. G. (2000) "Combination of activated carbon adsorption with light-enhanced chemical oxidation via hydrogen peroxide". *Water Research*, 34(17) p. 4169-4176
- James C.P., Germain E. and Judd S. (2014) "Micropollutant removal by advanced oxidation of microfiltered secondary effluent for water reuse". *Separation and Purification Technology*, 127 p. 77-83
- Jefferson B., Jarvis P., Bhagyanathan G.K., Smith H., Autin O., Goslan E.H., MacAdam J. and Carra, I. (2016) "Effect of elevated UV dose and alkalinity on metaldehyde removal and THM formation with UV/TiO<sub>2</sub> and UV/H<sub>2</sub>O<sub>2</sub>". *Chemical Engineering Journal*, 288 p. 359-367
- Katsoyiannis I.A., Canonica S. and von Gunten U. (2011) "Efficiency and energy requirements for the transformation of organic micropollutants by ozone, O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> and UV/H<sub>2</sub>O<sub>2</sub>". *Water Research*, 45(13) p. 3811-3822
- Kaur, K. (2017) *Design criteria doubts*. Email to: Kally Kaur, 10 August
- Kawamura S. (2000) *Integrated design and operation of water treatment facilities*. 2<sup>nd</sup> Edition. New York: John Wiley & Sons
- Kay P. and Grayson R. (2014) "Using water industry data to assess the metaldehyde pollution problem". *Water and Environment Journal*, 28(3) p. 410–417
- Kusic H., Koprivanac N. and Bozic A.L. (2006). "Minimization of organic pollutant content in aqueous solution by means of AOPs: UV-and ozone-based technologies". *Chemical Engineering Journal*, 123(3) p. 127-137
- Lekkerkerker-Teunissen K., Knol A.H., Derks J.G., Heringa, M.B., Houtman C.J., Hofman-Caris C.H.M., Beerendonk E.F., Reus A., Verberk J.Q.J.C., van

- Dijk J.C. (2013) "Pilot plant results with three different types of UV lamps for advanced oxidation". *Ozone Science Engineering* 35 p. 38-48
- Li J., Zamyadi A. and Hofmann (2016) "Effect of granular activated carbon type and age on quenching  $\text{H}_2\text{O}_2$  residuals after UV/  $\text{H}_2\text{O}_2$  drinking water treatment". *Journal of Water Supply: Research and Technology – AQUA*, 65 p. 28-36
- Lucas M.S., Peres J.A. and Puma G.L. (2010) "Treatment of winery wastewater by ozone-based advanced oxidation processes ( $\text{O}_3$ ,  $\text{O}_3/\text{UV}$  and  $\text{O}_3/\text{UV}/\text{H}_2\text{O}_2$ ) in a pilot-scale bubble column reactor and process economics". *Separation and Purification Technology*, 72(3) p. 235-241
- Mahamuni N.N. and Adewuyi Y.G. (2010) "Advanced oxidation processes (AOPs) involving ultrasound for waste water treatment: a review with emphasis on cost estimation". *Ultrasonics Sonochemistry*, 17(6) p. 990-1003
- Maher, K. (2017) *Data AOP work*. Email to: Keiron Maher 25 August
- Marshall J. (2013) *Water UK Briefing Paper on Metaldehyde*. London: Water UK
- McGivney W.T. and Kawamura S. (2008) *Cost estimating manual for water treatment facilities*. Hoboken: John Wiley & Sons, Inc
- Melin G. (Ed.) (2000) *Treatment Technologies for Removal of Methyl Tertiary Butyl Ether (MTBE) from Drinking Water: Air Stripping, Advanced Oxidation Processes, Granular Activated Carbon and Synthetic Resin Sorbents*. CA: Center for Groundwater Restoration and Protection, National Water Research Institute
- Miralles-Cuevas S., Darowna D., Wanag A., Mozia S., Malato S. and Oller, I. (2017). "Comparison of  $\text{UV}/\text{H}_2\text{O}_2$ ,  $\text{UV}/\text{S}_2\text{O}_8^{2-}$ , solar/ $\text{Fe(II)}/\text{H}_2\text{O}_2$  and solar/ $\text{Fe(II)}/\text{S}_2\text{O}_8^{2-}$  at pilot plant scale for the elimination of micro-contaminants in natural water: An economic assessment". *Chemical Engineering Journal*, 310 p. 514-524
- Nabeerasool M.A., Campen A.K., Polya D.A., Brown N.W. and van Dongen B.E. (2015) "Removal of metaldehyde from water using a novel coupled adsorption and electrochemical destruction technique". *Water*, 7(6) p. 3057-3071

- Ofwat (2013) *Setting price controls for 2015-20 – final methodology and expectations for companies' business plans*. Birmingham: Ofwat
- Organisation for Economic Co-operation and Development (OECD) (2017) *Exchange rates (indicator)*. doi: 10.1787/037ed317-en. [Accessed: 3/08/2017]
- Rakness K.L. (2011) *Ozone in drinking water treatment: process design, operation, and optimization*. Denver: American Water Works Association
- Rolph C. (2016) *21<sup>st</sup> Century Biological Processes for Metaldehyde Removal in Drinking Water Treatment*. EngD Thesis. Cranfield University
- Rosenfeldt E.J., Linden K.G., Canonica S. and Von Gunten, U. (2006). "Comparison of the efficiency of OH radical formation during ozonation and the advanced oxidation processes  $O_3/H_2O_2$  and  $UV/H_2O_2$ ". *Water Research*, 40(20) p. 3695-3704
- Roth A.J and Sullivan D.E. (1981) "Solubility of ozone in water". *Industrial & Engineering Chemistry Fundamentals*, 20 p. 137-140
- Rueda-Márquez J.J., Pintado-Herrera M.G., Martín-Díaz M.L., Acevedo-Merino A. and Manzano, M.A. (2015) "Combined AOPs for potential wastewater reuse or safe discharge based on multi-barrier treatment (microfiltration- $H_2O_2$ /UV-catalytic wet peroxide oxidation)". *Chemical Engineering Journal*, 270 p. 80-90
- Safarzadeh-Amiri A. (2001) " $O_3/H_2O_2$  treatment of methyl-tert-butyl ether (MTBE) in contaminated waters". *Water Research*, 35(15) p. 3706-3714
- Semitsoglou-Tsiapou S., Templeton M.R., Graham N.J., Leal L.H., Martijn B.J., Royce A. and Kruithof, J.C. (2016) "Low pressure  $UV/H_2O_2$  treatment for the degradation of the pesticides metaldehyde, clopyralid and mecoprop– Kinetics and reaction product formation". *Water Research*, 91 p. 285-294
- Smith W. (2011) "Principles of ozone generation". *Watertec Engineering Pty Ltd., Australia*
- Solmaz S.K.A., Üstün G.E., Birgül A. and Yonar, T (2009) "Advanced oxidation of textile dyeing effluents: Comparison of  $Fe^{+2}/H_2O_2$ ,  $Fe^{+3}/H_2O_2$ ,  $O_3$  and chemical coagulation processes". *Fresenius Environmental Bulletin*, 18(8) p. 1424-1433

- Tang L.L., DeNardo M.A., Gayathri C., Gil R.R., Kanda R. and Collins T.J. (2016) "TAML/H<sub>2</sub>O<sub>2</sub> Oxidative Degradation of Metaldehyde: Pursuing Better Water Treatment for the Most Persistent Pollutants". *Environmental Science & Technology*, 50(10) p. 5261-5268
- Towler G. and Sinnott R.K. (2012) *Chemical Engineering Design: Principles, Practice and Economics of Plant and Process Design*. 2<sup>nd</sup> Edition. Massachusetts: Butterworth-Heinemann
- Van der Meer M., van Lierop F. and LIT D.S. (2015) "The analysis of modern low pressure amalgam lamp characteristics". *Deutsche Akademie für Photobiologie und Phototechnologie (DAfP)*
- Wu T. and Englehardt J.D. (2015) "Peroxone mineralization of chemical oxygen demand for direct potable water reuse: Kinetics and process control". *Water Research*, 73 p. 362-372
- Yalili Kiliç M., Yonar T. and Kestioğlu, K (2013) "Pilot-scale treatment of olive oil mill wastewater by physicochemical and advanced oxidation processes". *Environmental Technology*, 34(12) p. 1521-1531

## 4 CONCLUSIONS

An investigation of  $O_3/H_2O_2$  +  $H_2O_2/UV$  and  $UV/H_2O_2$  advanced oxidation technologies for metaldehyde removal and disinfection by-products formation potential throughout a pilot-scale study was carried out. A WLCA was undertaken based on data gathered in the pilot-scale study for industrial application and detailed literature search. From these analyses, a number of conclusions can be drawn:

- The results demonstrated AOPs effectiveness to degrade the pesticide below the legislative limits of  $0.1 \mu\text{g L}^{-1}$  up to  $2.14 \mu\text{g L}^{-1}$  initial levels with  $E_D < 1.0 \text{ kWh m}^{-3}$ . Worst-case 38% minimal removal was logged for  $O_3/H_2O_2$  and the stand-alone  $UV/H_2O_2$ , yet up to 96% and 98% were equally yielded, respectively. The  $H_2O_2/UV$  sub process had conversely a more limited 79% top end removal efficiency. The  $O_3/H_2O_2$  was exclusively successful at fulfilling the European Directive 98/83/EC for metaldehyde feed water concentration  $\leq 0.14 \mu\text{g L}^{-1}$ . A surplus of  $H_2O_2$  required for the  $H_2O_2/UV$  sub process might explain this technical limitation. Further studies should address the optimum  $H_2O_2:O_3$  ratio, which is expected to be between 0.5 and 1, to achieve European Directive 98/83/EC limits for a wider metaldehyde inlet spectrum
- The assessment of metaldehyde degradation has also shown the need of greater oxidative chemical and energy doses to meet the stringent water quality standards when increasing MICs. Inhibitory effect of organic-turbid waters of greater than 1.0 NTU on  $UV/H_2O_2$  metaldehyde performance was reported
- The AOPs had a different net DBPFP contribution for THMFP ( $-283 \mu\text{g L}^{-1}$  to  $+255 \mu\text{g L}^{-1}$ ) to HAAFP ( $-164 \mu\text{g L}^{-1}$  to  $+131 \mu\text{g L}^{-1}$ ). Overall,  $O_3/H_2O_2$  sub process had a lower net production of DBPs than that of the rest of the processes. The impact of feed water quality in terms of NOM was critical for DBPFP, as no correlation was found with the process variables studied across the experimental work

- The practical implications of this work are that OPEX in terms of energy, 43% average, was the main driver for considering  $O_3/H_2O_2$  a cost-efficiency contender for metaldehyde removal. Moreover, this AOP provided with a trade-off between metaldehyde and THM compliant water production at the minimum costs (£0.07  $m^{-3}$ ). However, reliable pilot data confirming the oxidants doses suggested on the  $O_3/H_2O_2$  WLCA (10  $mg\ L^{-1}$  and 7  $mg\ L^{-1}$ , respectively) would validate this advanced technology as benchmark. The sensitive analysis showed greater influence of operational cost on the UV-based AOP than on the peroxone treatment. UV/ $H_2O_2$  would even be £86,000 more expensive than  $O_3/H_2O_2$  in a £0  $kWh^{-1}$  hypothetical scenario. The UV/ $H_2O_2$  remained an equivalent economic process comparable with catchment management and biological treatments for removing metaldehyde to trace levels. Do nothing should not be considered in any case. The WLCA undertaken in this study can be improved by using industrial prices from local manufacturers, thus avoiding updating prices from available research and empirical equations. LED-based breakthrough technology might incline water utilities to use technically reliable UV/ $H_2O_2$  over  $O_3/H_2O_2$  as evidenced metaldehyde efficiency for peaks of 2.0  $\mu g\ L^{-1}$  were tackled

## REFERENCES

- Autin O., Hart J., Jarvis P., MacAdam J., Parsons S.A and Jefferson B. (2012) "Comparison of UV/H<sub>2</sub>O<sub>2</sub> and UV/TiO<sub>2</sub> for the degradation of metaldehyde: Kinetics and the impact of background organics". *Water Research*, 46 p. 5655-5662
- Castle G.D., Mills G.A., Gravell A., Jones L., Townsend I., Cameron D.G. and Fones G.R. (2017) "Review of the molluscicide metaldehyde in the environment". *Environmental Science: Water Research & Technology*, 3(3) p. 415-428
- Collins J. and Bolton J.R. (2016) *Advanced Oxidation Handbook* Denver: American water Works Association
- Comninellis C., Kapalka A., Malato S., Parsons S. A., Poullos I. and Mantzavinos, D. (2008) "Advanced oxidation processes for water treatment: advances and trends for R&D". *Journal of Chemical Technology and Biotechnology*, 83 p. 769–776
- Cooper B. (2011) "Working with farmers to reduce pesticide movement to water". *Aspects of Applied Biology*, 106 p. 289-294
- European Parliament. Council of the European Union (1998) *Directive 98/83/EC of 3 November 1998 on the quality of water intended for human consumption*
- Despotović V.N., Abramović B.F., Šojić D.V. Kler S.J., Dalmacija M.B., Bjelica L.J. and Orčić D.Z. (2012) "Photocatalytic degradation of herbicide quinmerac in various types of natural water". *Water, Air, & Soil Pollution*, 223(6) p. 3009-3020
- Dolan T. (2013) *Water Framework Directive Article 7, The Drinking Water Directive and European Pesticide Regulation: Impacts on the diffuse pesticide pollution, potable water decision making and catchment management strategy*. EngD thesis. Cranfield University
- Dolan T., Parsons D.J., Howsam P., Whelan M.J. and Varga, L. (2014) "Identifying adaptation options and constraints: the role of agronomist knowledge in catchment management strategy". *Water Resources Management*, 28(2) p. 511-526

- Drinking Water Inspectorate (DWI) (2000) *The Water Supply (Water Quality) Regulations 2000, Statutory Instruments. No. 3184. Water, England and Wales*. Drinking Water Inspectorate
- Drinking Water Inspectorate (DWI) (2014) *Public water supplies - regional reports*. Available at: <http://dwi.defra.gov.uk/about/annual-report/2014/index.html> [Accessed: 23/11/2016]
- Drinking Water Inspectorate (DWI) (2016) *Annual Report of 2015*. Available at: [www.dwi.gov.uk/about/annual-report/2015/index.html](http://www.dwi.gov.uk/about/annual-report/2015/index.html) [Accessed: 23/11/2016]
- International Programme on Chemical Safety (IPCS) (1999) *Metaldehyde: International Programme on Chemical Safety Poisons Information Monograph 332*. Available at: <http://www.inchem.org/documents/pims/chemical/pim332.htm> [Accessed: 18/10/2016]
- James C.P., Germain E. and Judd S. (2014) "Micropollutant removal by advanced oxidation of microfiltered secondary effluent for water reuse". *Separation and Purification Technology*, 127 p. 77-83
- Jefferson B., Jarvis P., Bhagianathan G.K., Smith H., Autin O., Goslan E.H., MacAdam J. and Carra, I. (2016) "Effect of elevated UV dose and alkalinity on metaldehyde removal and THM formation with UV/TiO<sub>2</sub> and UV/H<sub>2</sub>O<sub>2</sub>". *Chemical Engineering Journal*, 288 p. 359-367
- Kay P. and Grayson R. (2014) "Using water industry data to assess the metaldehyde pollution problem". *Water and Environment Journal*, 28(3) p. 410–417
- Kim M.-K. and Zoh, K.-D. (2016) "Occurrence and removals of micropollutants in water environment". *Environmental Engineering Research*, 21(4) p. 319-332
- Martinez S., Delgado M. and Jarvis P (2016) "Removal of Herbicide Mecoprop from Surface Water Using Advanced Oxidation Processes (AOPS)". *International Journal of Environmental Research*, 10(2) p. 291-296

- Özcan A., Oturan N., Şahin Y. and Oturan M.A. (2010) "Electro-Fenton treatment of aqueous Clopyralid solutions". *International Journal of Environmental and Analytical Chemistry*, 90(3-6) p. 478-486
- Pesticides Forum (2015) *Pesticides in the UK: The 2014 report on the impacts and sustainable use of pesticides*. York: Health and Safety Executive
- Pesticide Management Education Program (PMEP) (1993) Metaldehyde. Available at: <http://pmez.cce.cornell.edu/profiles/extoxnet/haloxfop-methylparathion/metaldehyde-ext.html> [Accessed: 15/12/2016]
- Reichenberger S., Bach M., Skitschak A. and Frede H. G. (2007) "Mitigation strategies to reduce pesticide inputs into ground-and surface water and their effectiveness; A review". *Science of the Total Environment*, 384(1) p. 1-35
- Roche P. and Prados M. (1995) "Removal of pesticides by use of ozone or hydrogen peroxide/ozone". *Ozone: Science & Engineering*, 17(6) p. 657-672
- Semitsoglou-Tsiapou S., Templeton M.R., Graham N.J., Leal L.H., Martijn B.J., Royce A. and Kruithof, J.C. (2016) "Low pressure UV/H<sub>2</sub>O<sub>2</sub> treatment for the degradation of the pesticides metaldehyde, clopyralid and mecoprop– Kinetics and reaction product formation". *Water Research*, 91 p. 285-294
- Tang L.L., DeNardo M.A., Gayathri C., Gil R.R., Kanda R. and Collins T.J. (2016) "TAML/H<sub>2</sub>O<sub>2</sub> Oxidative Degradation of Metaldehyde: Pursuing Better Water Treatment for the Most Persistent Pollutants". *Environmental Science & Technology*, 50(10) p. 5261-5268
- Tao B. and Fletcher A. (2016) "Development of a novel dual-stage method for metaldehyde removal from water". *Chemical Engineering Journal*, 284 p. 741-749
- Tizaoui C., Mezughi K. and Bickley, R. (2011) "Heterogeneous photocatalytic removal of the herbicide clopyralid and its comparison with UV/H<sub>2</sub>O<sub>2</sub> and ozone oxidation techniques". *Desalination*, 273(1) p. 197-204
- UK Water Industry Research (UKWIR) (2011) *Treatment for new and emerging pesticides (11/DW/14/4)*. London: UKWIR

Westerhoff P., Yoon Y., Snyder S. and Wert E. (2005) "Fate of endocrine-disruptor, pharmaceutical, and personal care product chemicals during simulated drinking water treatment processes". *Environmental Science & Technology*, 39(17) p. 6649-6663

## **APPENDICES**

### **Appendix A Operating conditions evaluated**

This Appendix gathers all the operating conditions under which the AOP pilot experiments were carried out.

**Table A-1** UV/H<sub>2</sub>O<sub>2</sub> process conditions, flow rate, metaldehyde inlet concentration (MIC) and metaldehyde removal after treatment

| Flow rate<br>(m <sup>3</sup> h <sup>-1</sup> ) | UV<br>(%) | Electrical<br>power<br>(kW) | UV fluence<br>(KWh m <sup>-3</sup> ) | H <sub>2</sub> O <sub>2</sub><br>(mg L <sup>-1</sup> ) | MIC<br>(µg L <sup>-1</sup> ) | Metaldehyde residual post<br>UV/H <sub>2</sub> O <sub>2</sub><br>(µg L <sup>-1</sup> ) |
|------------------------------------------------|-----------|-----------------------------|--------------------------------------|--------------------------------------------------------|------------------------------|----------------------------------------------------------------------------------------|
| 2.44                                           | 60        | 1.26                        | 0.52                                 | 20                                                     | 0.14                         | 0.06                                                                                   |
| 2.49                                           | 60        | 1.26                        | 0.51                                 | 33                                                     | 0.14                         | 0.04                                                                                   |
| 2.49                                           | 60        | 1.26                        | 0.51                                 | 42                                                     | 0.14                         | 0.03                                                                                   |
| 3.49                                           | 60        | 1.26                        | 0.36                                 | 14                                                     | 0.14                         | 0.07                                                                                   |
| 3.48                                           | 60        | 1.26                        | 0.36                                 | 28                                                     | 0.14                         | 0.05                                                                                   |
| 3.53                                           | 60        | 1.26                        | 0.36                                 | 35                                                     | 0.14                         | 0.05                                                                                   |
| 2.5                                            | 60        | 1.26                        | 0.50                                 | 17                                                     | 0.53                         | 0.27                                                                                   |
| 2.52                                           | 60        | 1.26                        | 0.50                                 | 28                                                     | 0.53                         | 0.16                                                                                   |
| 2.5                                            | 60        | 1.26                        | 0.50                                 | 38                                                     | 0.53                         | 0.17                                                                                   |
| 3.02                                           | 60        | 1.26                        | 0.42                                 | 13                                                     | 0.53                         | 0.33                                                                                   |
| 3.11                                           | 60        | 1.26                        | 0.40                                 | 29                                                     | 0.53                         | 0.24                                                                                   |
| 3.08                                           | 60        | 1.26                        | 0.41                                 | 42                                                     | 0.53                         | 0.20                                                                                   |
| 2.53                                           | 60        | 1.26                        | 0.50                                 | 15                                                     | 0.80                         | 0.27                                                                                   |
| 2.53                                           | 60        | 1.26                        | 0.50                                 | 30                                                     | 0.80                         | 0.18                                                                                   |
| 2.49                                           | 60        | 1.26                        | 0.51                                 | 40                                                     | 0.80                         | 0.18                                                                                   |
| 2.54                                           | 60        | 1.26                        | 0.50                                 | 8                                                      | 2.11                         | 0.76                                                                                   |
| 2.54                                           | 60        | 1.26                        | 0.50                                 | 29                                                     | 2.11                         | 0.56                                                                                   |
| 2.47                                           | 60        | 1.26                        | 0.51                                 | 15                                                     | 2.11                         | 0.54                                                                                   |
| 2.51                                           | 60        | 1.26                        | 0.50                                 | 15                                                     | 2.14                         | 0.85                                                                                   |
| 2.53                                           | 60        | 1.26                        | 0.50                                 | 30                                                     | 2.14                         | 0.56                                                                                   |
| 2.55                                           | 60        | 1.26                        | 0.49                                 | 40                                                     | 2.14                         | 0.47                                                                                   |
| 2.51                                           | 60        | 1.26                        | 0.50                                 | 14                                                     | 2.30                         | 0.93                                                                                   |
| 2.56                                           | 60        | 1.26                        | 0.49                                 | 26                                                     | 2.30                         | 0.65                                                                                   |

| Flow rate<br>(m <sup>3</sup> h <sup>-1</sup> ) | UV<br>(%) | Electrical<br>power<br>(kW) | UV fluence<br>(KWh m <sup>-3</sup> ) | H <sub>2</sub> O <sub>2</sub><br>(mg L <sup>-1</sup> ) | MIC<br>(µg L <sup>-1</sup> ) | Metaldehyde residual post<br>UV/H <sub>2</sub> O <sub>2</sub><br>(µg L <sup>-1</sup> ) |
|------------------------------------------------|-----------|-----------------------------|--------------------------------------|--------------------------------------------------------|------------------------------|----------------------------------------------------------------------------------------|
| 2.52                                           | 60        | 1.26                        | 0.50                                 | 35                                                     | 2.30                         | 0.52                                                                                   |
| 2.5                                            | 90        | 1.89                        | 0.76                                 | 19                                                     | 0.14                         | 0.02                                                                                   |
| 2.43                                           | 90        | 1.89                        | 0.78                                 | 32                                                     | 0.14                         | 0.01                                                                                   |
| 2.48                                           | 90        | 1.89                        | 0.76                                 | 40                                                     | 0.14                         | 0.01                                                                                   |
| 2.55                                           | 90        | 1.89                        | 0.74                                 | 15                                                     | 0.53                         | 0.12                                                                                   |
| 2.53                                           | 90        | 1.89                        | 0.75                                 | 28                                                     | 0.53                         | 0.05                                                                                   |
| 2.52                                           | 90        | 1.89                        | 0.75                                 | 36                                                     | 0.53                         | 0.04                                                                                   |
| 3.01                                           | 96        | 2.01                        | 0.67                                 | 13                                                     | 0.53                         | 0.16                                                                                   |
| 3.07                                           | 96        | 2.01                        | 0.66                                 | 28                                                     | 0.53                         | 0.06                                                                                   |
| 3.07                                           | 96        | 2.01                        | 0.66                                 | 36                                                     | 0.53                         | 0.06                                                                                   |
| 2.59                                           | 90        | 1.89                        | 0.73                                 | 15                                                     | 0.80                         | 0.14                                                                                   |
| 2.55                                           | 90        | 1.89                        | 0.74                                 | 30                                                     | 0.80                         | 0.04                                                                                   |
| 2.48                                           | 90        | 1.89                        | 0.76                                 | 40                                                     | 0.80                         | 0.16                                                                                   |
| 2.46                                           | 90        | 1.89                        | 0.77                                 | 15                                                     | 2.11                         | 0.41                                                                                   |
| 2.51                                           | 90        | 1.89                        | 0.75                                 | 27                                                     | 2.11                         | 0.13                                                                                   |
| 2.51                                           | 90        | 1.89                        | 0.75                                 | 42                                                     | 2.11                         | 0.09                                                                                   |
| 2.52                                           | 90        | 1.89                        | 0.75                                 | 15                                                     | 2.14                         | 0.30                                                                                   |
| 2.55                                           | 90        | 1.89                        | 0.74                                 | 30                                                     | 2.14                         | 0.17                                                                                   |
| 2.5                                            | 90        | 1.89                        | 0.76                                 | 40                                                     | 2.14                         | 0.21                                                                                   |
| 3.48                                           | 96        | 2.01                        | 0.58                                 | 17                                                     | 0.14                         | 0.03                                                                                   |
| 3.46                                           | 96        | 2.01                        | 0.58                                 | 27                                                     | 0.14                         | 0.02                                                                                   |
| 3.51                                           | 96        | 2.01                        | 0.57                                 | 38                                                     | 0.14                         | 0.01                                                                                   |
| 2.52                                           | 96        | 2.01                        | 0.80                                 | 12                                                     | 2.30                         | 0.29                                                                                   |
| 2.53                                           | 96        | 2.01                        | 0.80                                 | 26                                                     | 2.30                         | 0.12                                                                                   |
| 2.52                                           | 96        | 2.01                        | 0.80                                 | 36                                                     | 2.30                         | 0.13                                                                                   |
| 2.57                                           | 70        | 1.47                        | 0.57                                 | 17                                                     | 0.53                         | 0.21                                                                                   |
| 2.56                                           | 80        | 1.68                        | 0.66                                 | 15                                                     | 0.53                         | 0.16                                                                                   |
| 2.52                                           | 80        | 1.68                        | 0.67                                 | 31                                                     | 0.53                         | 0.07                                                                                   |

| Flow rate<br>(m <sup>3</sup> h <sup>-1</sup> ) | UV<br>(%) | Electrical<br>power<br>(kW) | UV fluence<br>(KWh m <sup>-3</sup> ) | H <sub>2</sub> O <sub>2</sub><br>(mg L <sup>-1</sup> ) | MIC<br>(µg L <sup>-1</sup> ) | Metaldehyde residual post<br>UV/H <sub>2</sub> O <sub>2</sub><br>(µg L <sup>-1</sup> ) |
|------------------------------------------------|-----------|-----------------------------|--------------------------------------|--------------------------------------------------------|------------------------------|----------------------------------------------------------------------------------------|
| 2.50                                           | 70        | 1.47                        | 0.59                                 | 31                                                     | 0.53                         | 0.12                                                                                   |
| 2.50                                           | 70        | 1.47                        | 0.59                                 | 37                                                     | 0.53                         | 0.09                                                                                   |
| 2.52                                           | 80        | 1.68                        | 0.67                                 | 31                                                     | 0.53                         | 0.07                                                                                   |
| 1.94                                           | 90        | 1.89                        | 0.97                                 | 40                                                     | 0.53                         | 0.02                                                                                   |
| 1.97                                           | 80        | 1.68                        | 0.85                                 | 39                                                     | 0.53                         | 0.03                                                                                   |
| 1.96                                           | 60        | 1.26                        | 0.64                                 | 39                                                     | 0.53                         | 0.11                                                                                   |
| 1.92                                           | 60        | 1.26                        | 0.66                                 | 30                                                     | 0.53                         | 0.15                                                                                   |
| 1.92                                           | 80        | 1.68                        | 0.87                                 | 30                                                     | 0.53                         | 0.05                                                                                   |
| 1.96                                           | 80        | 1.68                        | 0.86                                 | 16                                                     | 0.53                         | 0.11                                                                                   |
| 1.98                                           | 60        | 1.26                        | 0.64                                 | 17                                                     | 0.53                         | 0.22                                                                                   |
| 1.96                                           | 90        | 1.89                        | 0.96                                 | 20                                                     | 0.53                         | 0.06                                                                                   |
| 1.90                                           | 80        | 1.68                        | 0.88                                 | 14                                                     | 2.11                         | 0.35                                                                                   |
| 2.10                                           | 60        | 1.26                        | 0.60                                 | 17                                                     | 2.11                         | 0.70                                                                                   |
| 2.09                                           | 90        | 1.89                        | 0.90                                 | 13                                                     | 2.11                         | 0.28                                                                                   |
| 2.08                                           | 60        | 1.26                        | 0.61                                 | 26                                                     | 2.11                         | 0.42                                                                                   |
| 2.07                                           | 80        | 1.68                        | 0.81                                 | 28                                                     | 2.11                         | 0.13                                                                                   |
| 2.08                                           | 80        | 1.68                        | 0.81                                 | 36                                                     | 2.11                         | 0.09                                                                                   |
| 2.03                                           | 60        | 1.26                        | 0.62                                 | 40                                                     | 2.11                         | 0.40                                                                                   |
| 2.01                                           | 90        | 1.89                        | 0.94                                 | 45                                                     | 2.11                         | 0.04                                                                                   |
| 2.56                                           | 80        | 1.68                        | 0.66                                 | 35                                                     | 2.11                         | 0.19                                                                                   |
| 2.54                                           | 70        | 1.47                        | 0.58                                 | 36                                                     | 2.11                         | 0.29                                                                                   |
| 2.51                                           | 70        | 1.47                        | 0.59                                 | 29                                                     | 2.11                         | 0.33                                                                                   |
| 2.51                                           | 80        | 1.68                        | 0.67                                 | 27                                                     | 2.11                         | 0.31                                                                                   |
| 2.49                                           | 80        | 1.68                        | 0.67                                 | 15                                                     | 2.11                         | 0.44                                                                                   |
| 2.46                                           | 70        | 1.47                        | 0.60                                 | 15                                                     | 2.11                         | 0.56                                                                                   |
| 2.54                                           | 70        | 1.47                        | 0.58                                 | 15                                                     | 0.80                         | 0.21                                                                                   |
| 2.55                                           | 80        | 1.68                        | 0.66                                 | 15                                                     | 0.80                         | 0.15                                                                                   |
| 2.49                                           | 80        | 1.68                        | 0.67                                 | 30                                                     | 0.80                         | 0.07                                                                                   |

| Flow rate<br>(m <sup>3</sup> h <sup>-1</sup> ) | UV<br>(%) | Electrical<br>power<br>(kW) | UV fluence<br>(KWh m <sup>-3</sup> ) | H <sub>2</sub> O <sub>2</sub><br>(mg L <sup>-1</sup> ) | MIC<br>(µg L <sup>-1</sup> ) | Metaldehyde residual post<br>UV/H <sub>2</sub> O <sub>2</sub><br>(µg L <sup>-1</sup> ) |
|------------------------------------------------|-----------|-----------------------------|--------------------------------------|--------------------------------------------------------|------------------------------|----------------------------------------------------------------------------------------|
| 2.50                                           | 70        | 1.47                        | 0.59                                 | 30                                                     | 0.80                         | 0.13                                                                                   |
| 2.52                                           | 70        | 1.47                        | 0.58                                 | 40                                                     | 0.80                         | 0.09                                                                                   |
| 2.46                                           | 80        | 1.68                        | 0.68                                 | 40                                                     | 0.80                         | 0.05                                                                                   |
| 1.97                                           | 90        | 1.89                        | 0.96                                 | 40                                                     | 0.80                         | 0.11                                                                                   |
| 1.95                                           | 80        | 1.68                        | 0.86                                 | 40                                                     | 0.80                         | 0.03                                                                                   |
| 1.98                                           | 60        | 1.26                        | 0.64                                 | 40                                                     | 0.80                         | 0.03                                                                                   |
| 1.97                                           | 60        | 1.26                        | 0.64                                 | 30                                                     | 0.80                         | 0.12                                                                                   |
| 1.95                                           | 80        | 1.68                        | 0.86                                 | 30                                                     | 0.80                         | 0.20                                                                                   |
| 1.98                                           | 80        | 1.68                        | 0.85                                 | 15                                                     | 0.80                         | 0.31                                                                                   |
| 1.98                                           | 90        | 1.89                        | 0.95                                 | 15                                                     | 0.80                         | 0.25                                                                                   |
| 1.98                                           | 60        | 1.26                        | 0.64                                 | 15                                                     | 0.80                         | 0.03                                                                                   |
| 2.48                                           | 70        | 1.47                        | 0.59                                 | 15                                                     | 2.14                         | 0.62                                                                                   |
| 2.51                                           | 80        | 1.68                        | 0.67                                 | 15                                                     | 2.14                         | 0.49                                                                                   |
| 2.49                                           | 80        | 1.68                        | 0.67                                 | 30                                                     | 2.14                         | 0.20                                                                                   |
| 2.51                                           | 70        | 1.47                        | 0.59                                 | 30                                                     | 2.14                         | 0.35                                                                                   |
| 2.57                                           | 70        | 1.47                        | 0.57                                 | 40                                                     | 2.14                         | 0.29                                                                                   |
| 2.61                                           | 80        | 1.68                        | 0.64                                 | 40                                                     | 2.14                         | 0.17                                                                                   |
| 1.96                                           | 90        | 1.89                        | 0.96                                 | 40                                                     | 2.14                         | 0.04                                                                                   |
| 1.99                                           | 80        | 1.68                        | 0.84                                 | 40                                                     | 2.14                         | 0.06                                                                                   |
| 1.96                                           | 60        | 1.26                        | 0.64                                 | 40                                                     | 2.14                         | 0.35                                                                                   |
| 1.99                                           | 60        | 1.26                        | 0.63                                 | 30                                                     | 2.14                         | 0.43                                                                                   |
| 2.01                                           | 80        | 1.68                        | 0.84                                 | 30                                                     | 2.14                         | 0.12                                                                                   |
| 1.96                                           | 80        | 1.68                        | 0.86                                 | 15                                                     | 2.14                         | 0.35                                                                                   |
| 1.97                                           | 90        | 1.89                        | 0.96                                 | 15                                                     | 2.14                         | 0.19                                                                                   |
| 1.95                                           | 60        | 1.26                        | 0.65                                 | 15                                                     | 2.14                         | 0.67                                                                                   |
| 2.99                                           | 80        | 1.68                        | 0.56                                 | 13                                                     | 0.53                         | 0.18                                                                                   |
| 3.06                                           | 80        | 1.68                        | 0.55                                 | 26                                                     | 0.53                         | 0.10                                                                                   |
| 3.05                                           | 80        | 1.68                        | 0.55                                 | 37                                                     | 0.53                         | 0.09                                                                                   |

| Flow rate<br>(m <sup>3</sup> h <sup>-1</sup> ) | UV<br>(%) | Electrical<br>power<br>(kW) | UV fluence<br>(KWh m <sup>-3</sup> ) | H <sub>2</sub> O <sub>2</sub><br>(mg L <sup>-1</sup> ) | MIC<br>(µg L <sup>-1</sup> ) | Metaldehyde residual post<br>UV/H <sub>2</sub> O <sub>2</sub><br>(µg L <sup>-1</sup> ) |
|------------------------------------------------|-----------|-----------------------------|--------------------------------------|--------------------------------------------------------|------------------------------|----------------------------------------------------------------------------------------|
| 2.52                                           | 80        | 1.68                        | 0.67                                 | 14                                                     | 2.30                         | 0.53                                                                                   |
| 2.55                                           | 80        | 1.68                        | 0.66                                 | 25                                                     | 2.30                         | 0.25                                                                                   |
| 2.52                                           | 80        | 1.68                        | 0.67                                 | 34                                                     | 2.30                         | 0.18                                                                                   |
| 3.49                                           | 80        | 1.68                        | 0.48                                 | 15                                                     | 0.14                         | 0.05                                                                                   |
| 3.46                                           | 80        | 1.68                        | 0.49                                 | 27                                                     | 0.14                         | 0.03                                                                                   |
| 3.58                                           | 80        | 1.68                        | 0.47                                 | 35                                                     | 0.14                         | 0.02                                                                                   |
| 2.44                                           | 70        | 1.47                        | 0.60                                 | 14                                                     | 0.14                         | 0.05                                                                                   |
| 2.49                                           | 80        | 1.68                        | 0.67                                 | 14                                                     | 0.14                         | 0.03                                                                                   |
| 2.46                                           | 80        | 1.68                        | 0.68                                 | 35                                                     | 0.14                         | 0.01                                                                                   |
| 2.46                                           | 70        | 1.47                        | 0.60                                 | 29                                                     | 0.14                         | 0.02                                                                                   |
| 2.48                                           | 70        | 1.47                        | 0.59                                 | 42                                                     | 0.14                         | 0.02                                                                                   |
| 2.48                                           | 80        | 1.68                        | 0.68                                 | 40                                                     | 0.14                         | 0.02                                                                                   |
| 1.89                                           | 90        | 1.89                        | 1.00                                 | 40                                                     | 0.14                         | 0.01                                                                                   |
| 1.88                                           | 80        | 1.68                        | 0.89                                 | 47                                                     | 0.14                         | 0.02                                                                                   |
| 1.90                                           | 60        | 1.26                        | 0.66                                 | 40                                                     | 0.14                         | 0.02                                                                                   |
| 1.91                                           | 60        | 1.26                        | 0.66                                 | 37                                                     | 0.14                         | 0.02                                                                                   |
| 1.86                                           | 80        | 1.68                        | 0.90                                 | 30                                                     | 0.14                         | 0.01                                                                                   |
| 1.89                                           | 80        | 1.68                        | 0.89                                 | 20                                                     | 0.14                         | 0.01                                                                                   |
| 1.89                                           | 90        | 1.89                        | 1.00                                 | 15                                                     | 0.14                         | 0.01                                                                                   |
| 1.90                                           | 60        | 1.26                        | 0.66                                 | 17                                                     | 0.14                         | 0.05                                                                                   |

**Table A-2** O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> process conditions, flow rate, metaldehyde inlet concentration (MIC) and metaldehyde removal after treatment

| Flow rate<br>(m <sup>3</sup> h <sup>-1</sup> ) | O <sub>3</sub><br>(mg L <sup>-1</sup> ) | H <sub>2</sub> O <sub>2</sub><br>(mg L <sup>-1</sup> ) | MIC<br>(µg L <sup>-1</sup> ) | Metaldehyde residual post O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub><br>(µg L <sup>-1</sup> ) |
|------------------------------------------------|-----------------------------------------|--------------------------------------------------------|------------------------------|--------------------------------------------------------------------------------------------------|
| 1.92                                           | 3.39                                    | 8                                                      | 0.53                         | 0.28                                                                                             |
| 1.84                                           | 3.45                                    | 13                                                     | 0.53                         | 0.28                                                                                             |
| 1.65                                           | 5.97                                    | 18                                                     | 0.53                         | 0.23                                                                                             |
| 1.85                                           | 7.19                                    | 24                                                     | 0.53                         | 0.17                                                                                             |
| 1.84                                           | 3.46                                    | 10                                                     | 2.04                         | 0.82                                                                                             |
| 1.88                                           | 3.59                                    | 10                                                     | 2.04                         | 0.73                                                                                             |
| 1.95                                           | 5.06                                    | 16                                                     | 2.04                         | 0.60                                                                                             |
| 1.86                                           | 7.16                                    | 22                                                     | 2.11                         | 0.39                                                                                             |
| 2.50                                           | 2.58                                    | 7                                                      | 0.53                         | 0.31                                                                                             |
| 2.51                                           | 2.47                                    | 10                                                     | 0.53                         | 0.19                                                                                             |
| 2.62                                           | 3.69                                    | 10                                                     | 0.53                         | 0.19                                                                                             |
| 2.55                                           | 3.84                                    | 16                                                     | 0.53                         | 0.31                                                                                             |
| 2.55                                           | 5.15                                    | 15                                                     | 0.53                         | 0.19                                                                                             |
| 2.53                                           | 5.08                                    | 23                                                     | 0.53                         | 0.19                                                                                             |
| 1.45                                           | 2.98                                    | 10                                                     | 0.80                         | 0.01                                                                                             |
| 1.43                                           | 2.99                                    | 13                                                     | 0.80                         | 0.35                                                                                             |
| 1.29                                           | 5.14                                    | 15                                                     | 0.80                         | 0.29                                                                                             |
| 1.40                                           | 6.19                                    | 24                                                     | 0.80                         | 0.24                                                                                             |
| 1.08                                           | 2.29                                    | 10                                                     | 2.14                         | 0.19                                                                                             |
| 1.81                                           | 2.20                                    | 8                                                      | 2.14                         | 0.19                                                                                             |
| 1.90                                           | 3.16                                    | 14                                                     | 2.14                         | 0.19                                                                                             |
| 1.78                                           | 3.40                                    | 14                                                     | 2.14                         | 0.19                                                                                             |

| Flow rate<br>(m <sup>3</sup> h <sup>-1</sup> ) | O <sub>3</sub><br>(mg L <sup>-1</sup> ) | H <sub>2</sub> O <sub>2</sub><br>(mg L <sup>-1</sup> ) | MIC<br>(µg L <sup>-1</sup> ) | Metaldehyde residual post O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub><br>(µg L <sup>-1</sup> ) |
|------------------------------------------------|-----------------------------------------|--------------------------------------------------------|------------------------------|--------------------------------------------------------------------------------------------------|
| 1.66                                           | 5.30                                    | 16                                                     | 2.14                         | 0.19                                                                                             |
| 1.66                                           | 5.12                                    | 24                                                     | 2.14                         | 0.19                                                                                             |
| 1.66                                           | 5.24                                    | 22                                                     | 2.14                         | 0.19                                                                                             |
| 1.66                                           | 5.33                                    | 24                                                     | 2.14                         | 0.31                                                                                             |
| 2.47                                           | 2.50                                    | 9                                                      | 2.30                         | 1.04                                                                                             |
| 2.51                                           | 3.87                                    | 15                                                     | 2.30                         | 0.65                                                                                             |
| 2.53                                           | 4.93                                    | 16                                                     | 2.30                         | 0.54                                                                                             |
| 1.88                                           | 3.38                                    | 11                                                     | 2.30                         | 1.09                                                                                             |
| 1.90                                           | 3.21                                    | 13                                                     | 2.30                         | 1.07                                                                                             |
| 1.86                                           | 5.07                                    | 12                                                     | 2.30                         | 0.84                                                                                             |
| 1.77                                           | 5.44                                    | 24                                                     | 2.30                         | 0.10                                                                                             |
| 1.96                                           | 6.84                                    | 14                                                     | 2.30                         | 0.42                                                                                             |
| 1.83                                           | 7.34                                    | 24                                                     | 2.30                         | 0.39                                                                                             |
| 1.83                                           | 2.10                                    | 8                                                      | 0.14                         | 0.08                                                                                             |
| 1.86                                           | 2.13                                    | 11                                                     | 0.14                         | 0.09                                                                                             |
| 1.89                                           | 3.17                                    | 11                                                     | 0.14                         | 0.07                                                                                             |
| 1.89                                           | 3.35                                    | 19                                                     | 0.14                         | 0.06                                                                                             |
| 1.89                                           | 4.52                                    | 18                                                     | 0.14                         | 0.05                                                                                             |
| 1.88                                           | 4.49                                    | 23                                                     | 0.14                         | 0.05                                                                                             |
| 1.85                                           | 5.29                                    | 14                                                     | 0.53                         | 0.22                                                                                             |
| 1.95                                           | 6.71                                    | 15                                                     | 0.53                         | 0.21                                                                                             |
| 1.69                                           | 5.94                                    | 11                                                     | 2.04                         | 0.60                                                                                             |
| 1.94                                           | 6.95                                    | 16                                                     | 2.04                         | 0.36                                                                                             |
| 1.39                                           | 4.64                                    | 13                                                     | 0.80                         | 0.31                                                                                             |
| 1.43                                           | 5.94                                    | 17                                                     | 0.80                         | 0.24                                                                                             |
| 1.78                                           | 3.56                                    | 13                                                     | 2.14                         | 0.31                                                                                             |

| Flow rate<br>(m <sup>3</sup> h <sup>-1</sup> ) | O <sub>3</sub><br>(mg L <sup>-1</sup> ) | H <sub>2</sub> O <sub>2</sub><br>(mg L <sup>-1</sup> ) | MIC<br>(µg L <sup>-1</sup> ) | Metaldehyde residual post O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub><br>(µg L <sup>-1</sup> ) |
|------------------------------------------------|-----------------------------------------|--------------------------------------------------------|------------------------------|--------------------------------------------------------------------------------------------------|
| 1.47                                           | 5.98                                    | 13                                                     | 2.14                         | 0.31                                                                                             |
| 2.05                                           | 4.33                                    | 16                                                     | 2.14                         | 0.19                                                                                             |

**Table A-3** H<sub>2</sub>O<sub>2</sub>/UV process conditions, metaldehyde inlet concentration (MIC), in this case the residual from the peroxone process, and metaldehyde removal after treatment

| UV fluence<br>(mJ cm <sup>-2</sup> ) | Flow rate UV<br>(m <sup>3</sup> h <sup>-1</sup> ) | Electrical<br>power<br>(kW) | UV fluence<br>(KWh m <sup>-3</sup> ) | H <sub>2</sub> O <sub>2</sub><br>(mg L <sup>-1</sup> ) | Metaldehyde<br>residual post<br>O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub><br>(µg L <sup>-1</sup> ) | Metaldehyde<br>residual post<br>H <sub>2</sub> O <sub>2</sub> /UV<br>(µg L <sup>-1</sup> ) |
|--------------------------------------|---------------------------------------------------|-----------------------------|--------------------------------------|--------------------------------------------------------|--------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------|
| 1400                                 | 0.47                                              | 0.34                        | 0.73                                 | 8                                                      | 0.28                                                                                                   | 0.14                                                                                       |
| 1400                                 | 0.44                                              | 0.34                        | 0.77                                 | 13                                                     | 0.28                                                                                                   | 0.12                                                                                       |
| 1800                                 | 0.31                                              | 0.34                        | 1.10                                 | 18                                                     | 0.23                                                                                                   | 0.05                                                                                       |
| 1000                                 | 0.63                                              | 0.34                        | 0.54                                 | 24                                                     | 0.17                                                                                                   | 0.06                                                                                       |
| 1400                                 | 0.44                                              | 0.34                        | 0.77                                 | 10                                                     | 0.82                                                                                                   | 0.38                                                                                       |
| 1400                                 | 0.44                                              | 0.34                        | 0.77                                 | 10                                                     | 0.73                                                                                                   | 0.37                                                                                       |
| 1800                                 | 0.31                                              | 0.34                        | 1.10                                 | 16                                                     | 0.60                                                                                                   | 0.13                                                                                       |
| 1000                                 | 0.61                                              | 0.34                        | 0.56                                 | 24                                                     | 0.39                                                                                                   | 0.13                                                                                       |
| 1400                                 | 0.41                                              | 0.34                        | 0.83                                 | 13                                                     | 0.35                                                                                                   | 0.14                                                                                       |
| 1800                                 | 0.33                                              | 0.34                        | 1.03                                 | 15                                                     | 0.29                                                                                                   | 0.08                                                                                       |
| 1000                                 | 0.62                                              | 0.34                        | 0.55                                 | 25                                                     | 0.24                                                                                                   | 0.09                                                                                       |
| 1400                                 | 0.42                                              | 0.34                        | 0.81                                 | 10                                                     | 0.19                                                                                                   | 0.60                                                                                       |
| 1400                                 | 0.42                                              | 0.34                        | 0.81                                 | 8                                                      | 0.19                                                                                                   | 0.54                                                                                       |

|      |      |      |      |    |      |      |
|------|------|------|------|----|------|------|
| 1800 | 0.33 | 0.34 | 1.03 | 14 | 0.19 | 0.30 |
| 1000 | 0.61 | 0.34 | 0.56 | 14 | 0.19 | 0.49 |
| 1400 | 0.42 | 0.34 | 0.81 | 16 | 0.19 | 0.27 |
| 1800 | 0.33 | 0.34 | 1.03 | 24 | 0.19 | 0.18 |
| 1000 | 0.60 | 0.34 | 0.57 | 22 | 0.19 | 0.32 |
| 1400 | 0.42 | 0.34 | 0.81 | 24 | 0.31 | 0.22 |
| 1000 | 0.58 | 0.34 | 0.59 | 11 | 1.09 | 0.54 |
| 1000 | 0.59 | 0.34 | 0.58 | 13 | 1.07 | 0.57 |
| 1000 | 0.57 | 0.34 | 0.60 | 12 | 0.84 | 0.41 |
| 1000 | 0.58 | 0.34 | 0.59 | 24 | 0.10 | 0.41 |
| 1000 | 0.56 | 0.34 | 0.61 | 14 | 0.42 | 0.19 |
| 1000 | 0.56 | 0.34 | 0.61 | 24 | 0.39 | 0.11 |
| 1000 | 0.61 | 0.34 | 0.56 | 8  | 0.08 | 0.05 |
| 1000 | 0.61 | 0.34 | 0.56 | 11 | 0.09 | 0.05 |
| 1000 | 0.60 | 0.34 | 0.57 | 11 | 0.07 | 0.04 |
| 1000 | 0.59 | 0.34 | 0.58 | 19 | 0.06 | 0.03 |
| 1000 | 0.59 | 0.34 | 0.58 | 18 | 0.05 | 0.02 |
| 1000 | 0.60 | 0.34 | 0.57 | 23 | 0.05 | 0.02 |

---

## Appendix B DistLM results on metaldehyde removal after AOPs

In this Appendix, the statistical tests undertaken in PRIMER v6 software are shown. This methodology was followed to evaluate the influence of the different predictors either process conditions tested (UV fluences, H<sub>2</sub>O<sub>2</sub> doses, O<sub>3</sub> doses and flow rates) or water quality parameters analysed (DOC, turbidity and UV254 nm) on metaldehyde degradation after a given AOP. In each table, the predictors significantly explaining variation ( $P < 0.05$ ) and in noteworthy proportion ('Prop.') on metaldehyde removal (effector) appear in bold. For each AOP process and sub processes, the marginal test is first displayed and then the sequential test. In the sequential test, 'res.df' indicates the residual degrees of freedom after adding a new predictor to the DistLM while the 'Cumul.' value explains the predictive power of the model.

- UV/ H<sub>2</sub>O<sub>2</sub>

**Table B-1** Individual influence of predictors on metaldehyde removal with  $n=125$  residual degrees of freedom according to the DistLM marginal test

| Variable                          | SS (trace) | Pseudo-F | P             | Prop.          |
|-----------------------------------|------------|----------|---------------|----------------|
| <b>Flow rate</b>                  | 16.101     | 18.313   | <b>0.0001</b> | <b>0.12779</b> |
| <b>H<sub>2</sub>O<sub>2</sub></b> | 16.43      | 18.744   | <b>0.0001</b> | <b>0.1304</b>  |
| <b>UV</b>                         | 39.827     | 57.771   | <b>0.0001</b> | <b>0.31608</b> |
| Turbidity inlet                   | 11.182     | 11.193   | 0.3022        | 0.0088746      |
| UV254 Abs inlet                   | 0.91015    | 0.90949  | 0.3471        | 0.0072234      |
| DOC inlet                         | 49.852     | 51.494   | 0.02          | 0.039565       |

**Table B-2** Sequential DistLM test of the predictors explaining metaldehyde removal

| Variable                          | SS (trace) | Pseudo-F | P             | Prop.          | Cumul.  | res.df |
|-----------------------------------|------------|----------|---------------|----------------|---------|--------|
| <b>UV</b>                         | 39.827     | 57.771   | <b>0.0001</b> | <b>0.31608</b> | 0.31608 | 125    |
| <b>H<sub>2</sub>O<sub>2</sub></b> | 13.975     | 24.002   | <b>0.0001</b> | <b>0.11091</b> | 0.427   | 124    |
| DOC inlet                         | 3.6263     | 6.5046   | 0.0097        | 0.02878        | 0.45578 | 123    |
| UV254 Abs inlet                   | 2.2132     | 4.069    | 0.0473        | 0.017565       | 0.47334 | 122    |
| Turbidity inlet                   | 2.2173     | 4.1829   | 0.0382        | 0.017598       | 0.49094 | 121    |
| Flow rate                         | 0.10541    | 0.19753  | 0.6618        | 0.000837       | 0.49178 | 120    |

- O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV

**Table B-3** Individual influence of predictors on metaldehyde removal with  $n=62$  residual degrees of freedom according to the DistLM marginal test

| Variable                                      | SS (trace) | Pseudo-F | P             | Prop.          |
|-----------------------------------------------|------------|----------|---------------|----------------|
| H <sub>2</sub> O <sub>2</sub> /O <sub>3</sub> | 1.969      | 2.0003   | 0.1561        | 0.031254       |
| <b>O<sub>3</sub></b>                          | 28.611     | 51.583   | <b>0.0001</b> | <b>0.45415</b> |
| <b>H<sub>2</sub>O<sub>2</sub></b>             | 21.155     | 31.345   | <b>0.0001</b> | <b>0.3358</b>  |
| <b>UV</b>                                     | 33.718     | 71.395   | <b>0.0001</b> | <b>0.53521</b> |
| Turbidity inlet                               | 0.057857   | 0.056991 | 0.8123        | 0.0009184      |
| UV254 inlet Abs                               | 0.35819    | 0.35452  | 0.5488        | 0.0056856      |
| DOC inlet                                     | 0.16609    | 0.16388  | 0.6848        | 0.0026363      |

**Table B-4** Sequential DistLM test of the predictors explaining metaldehyde removal

| Variable                                      | SS (trace) | Pseudo-F | P             | Prop.          | Cumul.  | res.df |
|-----------------------------------------------|------------|----------|---------------|----------------|---------|--------|
| <b>UV</b>                                     | 33.718     | 71.395   | <b>0.0001</b> | <b>0.53521</b> | 0.53521 | 62     |
| <b>O<sub>3</sub></b>                          | 15.681     | 70.333   | <b>0.0001</b> | <b>0.24891</b> | 0.78412 | 61     |
| H <sub>2</sub> O <sub>2</sub>                 | 1.7669     | 8.9589   | 0.0031        | 0.028046       | 0.81217 | 60     |
| DOC inlet                                     | 0.46052    | 2.3891   | 0.1289        | 0.00731        | 0.81948 | 59     |
| UV254 Abs inlet                               | 0.012533   | 0.063987 | 0.8056        | 0.000199       | 0.81968 | 58     |
| Turbidity inlet                               | 0.017697   | 0.088934 | 0.7708        | 0.000281       | 0.81996 | 57     |
| H <sub>2</sub> O <sub>2</sub> /O <sub>3</sub> | 0.000103   | 0.00051  | 0.9799        | 1.64E-06       | 0.81996 | 56     |

- O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> sub process

**Table B-5** Individual influence of predictors on metaldehyde removal with  $n=48$  residual degrees of freedom according to the DistLM marginal test

| Variable                                      | SS (trace) | Pseudo-F | P             | Prop.          |
|-----------------------------------------------|------------|----------|---------------|----------------|
| Flow rate                                     | 3.7589     | 3.9882   | 0.0528        | 0.076713       |
| H <sub>2</sub> O <sub>2</sub> /O <sub>3</sub> | 0.021648   | 0.021215 | 0.8806        | 0.0004418      |
| <b>O<sub>3</sub></b>                          | 5.0298     | 5.4907   | <b>0.0255</b> | <b>0.10265</b> |
| <b>H<sub>2</sub>O<sub>2</sub></b>             | 5.988      | 6.6825   | <b>0.0128</b> | <b>0.1222</b>  |
| <b>Turbidity inlet</b>                        | 7.2763     | 8.3709   | <b>0.0052</b> | <b>0.1485</b>  |
| <b>UV254 Abs inlet</b>                        | 12.609     | 16.632   | <b>0.0004</b> | <b>0.25733</b> |
| <b>DOC inlet</b>                              | 16.964     | 25.417   | <b>0.0001</b> | <b>0.3462</b>  |

**Table B-6** Sequential DistLM test of the predictors explaining metaldehyde removal

| Variable                                      | SS (trace) | Pseudo-F | P             | Prop.           | Cumul.  | res.df |
|-----------------------------------------------|------------|----------|---------------|-----------------|---------|--------|
| <b>DOC inlet</b>                              | 16.964     | 25.417   | <b>0.0001</b> | <b>0.3462</b>   | 0.3462  | 48     |
| <b>O<sub>3</sub></b>                          | 8.1653     | 16.077   | <b>0.0004</b> | <b>0.16664</b>  | 0.51284 | 47     |
| <b>Turbidity inlet</b>                        | 4.137      | 9.6433   | <b>0.0023</b> | <b>0.084428</b> | 0.59726 | 46     |
| UV254 Abs inlet                               | 1.3285     | 3.2481   | 0.0794        | 0.027113        | 0.62438 | 45     |
| Flow rate                                     | 2.4893     | 6.8816   | 0.0107        | 0.050802        | 0.67518 | 44     |
| H <sub>2</sub> O <sub>2</sub> /O <sub>3</sub> | 0.24518    | 0.67275  | 0.4169        | 0.005004        | 0.68018 | 43     |
| H <sub>2</sub> O <sub>2</sub>                 | 0.000224   | 0.000599 | 0.9822        | 4.56E-06        | 0.68019 | 42     |

- H<sub>2</sub>O<sub>2</sub>/UV sub process

**Table B-7** Individual influence of predictors on metaldehyde removal with  $n=29$  residual degrees of freedom according to the DistLM marginal test

| Variable                                                     | SS (trace) | Pseudo-F   | P      | Prop.      |
|--------------------------------------------------------------|------------|------------|--------|------------|
| O <sub>3</sub>                                               | 16.762     | 17.162     | 0.2032 | 0.055872   |
| H <sub>2</sub> O <sub>2</sub>                                | 0.0847     | 0.082109   | 0.786  | 0.0028233  |
| H <sub>2</sub> O <sub>2</sub> /O <sub>3</sub>                | 20.257     | 2.1        | 0.155  | 0.067524   |
| UV                                                           | 0.00098747 | 0.00095459 | 0.9766 | 0.32916    |
| Turbidity post O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> | 0.010373   | 0.010031   | 0.9243 | 0.00034576 |
| UV254 Abs post O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> | 0.021981   | 0.021264   | 0.8742 | 0.00073269 |
| DOC post O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub>       | 23.633     | 24.799     | 0.1227 | 0.078776   |

**Table B-8** Sequential DistLM test of the predictors explaining metaldehyde removal

| Variable                                                     | SS (trace) | Pseudo-F | P      | Prop.    | Cumul.  | res.df |
|--------------------------------------------------------------|------------|----------|--------|----------|---------|--------|
| DOC post O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub>       | 2.3633     | 2.4799   | 0.1228 | 0.078776 | 0.07877 | 29     |
| H <sub>2</sub> O <sub>2</sub> /O <sub>3</sub>                | 1.502      | 1.6092   | 0.2179 | 0.050066 | 0.12884 | 28     |
| UV254 Abs post O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> | 0.51378    | 0.54144  | 0.4732 | 0.017126 | 0.14597 | 27     |
| O <sub>3</sub>                                               | 1.5379     | 1.6603   | 0.2052 | 0.051263 | 0.19723 | 26     |
| H <sub>2</sub> O <sub>2</sub>                                | 0.53655    | 0.56968  | 0.4394 | 0.017885 | 0.21512 | 25     |
| Turbidity post O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> | 0.36311    | 0.3759   | 0.5468 | 0.012104 | 0.22722 | 24     |
| UV                                                           | 0.027798   | 0.027612 | 0.8656 | 0.000927 | 0.22815 | 23     |

## Appendix C DistLM results on DBPFP after AOPs

In this Appendix, the statistical tests undertaken in PRIMER v6 software are shown. This methodology was followed to evaluate the influence of the different predictors either process conditions tested (UV fluences, H<sub>2</sub>O<sub>2</sub> doses, O<sub>3</sub> doses and flow rates) or water quality parameters analysed (DOC, turbidity and UV254 nm) on the net DBPFP contribution after a given AOP. In each table, the predictors significantly explaining variation ( $P < 0.05$ ) and in noteworthy proportion ('Prop.') on DBPFP (THMFP/HAAFP) change (effector) appear in bold. For each AOP process and sub processes, the marginal test is first displayed and then the sequential test. In the sequential test, 'res.df' indicates the residual degrees of freedom after adding a new predictor to the DistLM while the 'Cumul.' value explains the predictive power of the model.

### C.1 Net THMFP contribution after AOP

- UV/ H<sub>2</sub>O<sub>2</sub>

**Table C-1** Individual influence of predictors on net THMFP contribution with  $n=25$  residual degrees of freedom according to the DistLM marginal test

| Variable                      | SS (trace) | Pseudo-F | P      | Prop.     |
|-------------------------------|------------|----------|--------|-----------|
| Flow rate                     | 0.1686     | 0.16317  | 0.6906 | 0.0064846 |
| H <sub>2</sub> O <sub>2</sub> | 28.397     | 30.653   | 0.0905 | 0.10922   |
| Metaldehyde inlet             | 0.067532   | 0.065104 | 0.8118 | 0.0025974 |
| UV                            | 0.088542   | 0.085428 | 0.7719 | 0.0034055 |
| Turbidity inlet               | 1.782      | 18.395   | 0.1882 | 0.068537  |
| UV254 Abs inlet               | 16.086     | 16.487   | 0.211  | 0.06187   |
| DOC inlet                     | 0.67867    | 0.67005  | 0.4195 | 0.026103  |
| UV254 Abs post AOP            | 0.70618    | 0.69798  | 0.4159 | 0.027161  |
| DOC post AOP                  | 22.785     | 24.013   | 0.1311 | 0.087635  |

**Table C-2** Sequential DistLM test of the predictors explaining net THMFP contribution

| Variable                      | SS (trace) | Pseudo-F | P      | Prop.    | Cumul.  | res.df |
|-------------------------------|------------|----------|--------|----------|---------|--------|
| H <sub>2</sub> O <sub>2</sub> | 2.8397     | 3.0653   | 0.0934 | 0.10922  | 0.10922 | 25     |
| UV254 Abs inlet               | 1.5354     | 1.7041   | 0.214  | 0.059055 | 0.16827 | 24     |
| Turbidity inlet               | 2.0217     | 2.372    | 0.1328 | 0.077759 | 0.24603 | 23     |
| Metaldehyde inlet             | 1.5822     | 1.9315   | 0.189  | 0.060853 | 0.30689 | 22     |
| DOC inlet                     | 2.4141     | 3.2483   | 0.081  | 0.09285  | 0.39974 | 21     |
| Flow rate                     | 0.90527    | 1.2315   | 0.2826 | 0.034818 | 0.43455 | 20     |
| UV254 Abs post AOP            | 0.31209    | 0.41209  | 0.536  | 0.012004 | 0.44656 | 19     |
| DOC post AOP                  | 0.5191     | 0.67365  | 0.4052 | 0.019965 | 0.46652 | 18     |
| UV                            | 0.003139   | 0.003848 | 0.9481 | 0.000121 | 0.46664 | 17     |

- O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV

**Table C-3** Individual influence of predictors on net THMFP contribution with  $n=37$  residual degrees of freedom according to the DistLM marginal test

| Variable                                      | SS (trace) | Pseudo-F | P             | Prop.          |
|-----------------------------------------------|------------|----------|---------------|----------------|
| H <sub>2</sub> O <sub>2</sub> /O <sub>3</sub> | 2.8109     | 2.9555   | 0.0928        | 0.073971       |
| O <sub>3</sub>                                | 0.61309    | 0.60675  | 0.4366        | 0.016134       |
| <b>H<sub>2</sub>O<sub>2</sub></b>             | 5.254      | 5.9366   | <b>0.018</b>  | <b>0.13826</b> |
| Metaldehyde inlet                             | 0.054779   | 0.053414 | 0.8195        | 0.001442       |
| UV                                            | 0.14927    | 0.14592  | 0.7157        | 0.003928       |
| Turbidity inlet                               | 0.43585    | 0.4293   | 0.5305        | 0.01147        |
| UV254 Abs inlet                               | 2.1783     | 2.2499   | 0.1409        | 0.057323       |
| <b>DOC inlet</b>                              | 5.2079     | 5.8762   | <b>0.0145</b> | <b>0.13705</b> |
| UV254 Abs post AOP                            | 0.75867    | 0.75375  | 0.3985        | 0.019965       |
| DOC post AOP                                  | 0.54838    | 0.54177  | 0.4732        | 0.014431       |

**Table C-4** Sequential DistLM test of the predictors explaining net THMFP contribution

| Variable                                      | SS (trace) | Pseudo-F | P            | Prop.          | Cumul. | res.df |
|-----------------------------------------------|------------|----------|--------------|----------------|--------|--------|
| <b>H<sub>2</sub>O<sub>2</sub></b>             | 5.254      | 5.9366   | <b>0.015</b> | <b>0.13826</b> | 0.1382 | 37     |
| <b>DOC inlet</b>                              | 4.9746     | 6.4486   | <b>0.011</b> | <b>0.13091</b> | 0.2691 | 36     |
| DOC post AOP                                  | 1.4233     | 1.8906   | 0.182        | 0.03745        | 0.3066 | 35     |
| UV254 Abs post AOP                            | 1.5678     | 2.1512   | 0.150        | 0.04125        | 0.3478 | 34     |
| UV254 Abs inlet                               | 0.8825     | 1.2186   | 0.291        | 0.02322        | 0.3711 | 33     |
| H <sub>2</sub> O <sub>2</sub> /O <sub>3</sub> | 0.39096    | 0.53222  | 0.454        | 0.01028        | 0.3814 | 32     |
| Turbidity inlet                               | 0.33613    | 0.44971  | 0.521        | 0.00884        | 0.3902 | 31     |
| Metaldehyde inlet                             | 0.82962    | 1.114    | 0.305        | 0.02183        | 0.4120 | 30     |
| O <sub>3</sub>                                | 0.17178    | 0.2247   | 0.626        | 0.00452        | 0.4166 | 29     |
| UV                                            | 0.032606   | 0.041242 | 0.835        | 0.00085        | 0.4174 | 28     |

- O<sub>3</sub>/H<sub>2</sub>O sub process

**Table C-5** Individual influence of predictors on net THMFP contribution with  $n=37$  residual degrees of freedom according to the DistLM marginal test

| Variable                                      | SS (trace) | Pseudo-F | P             | Prop.          |
|-----------------------------------------------|------------|----------|---------------|----------------|
| Flow rate                                     | 1.7337     | 1.7688   | 0.1905        | 0.045625       |
| H <sub>2</sub> O <sub>2</sub> /O <sub>3</sub> | 0.42498    | 0.41847  | 0.4987        | 0.011184       |
| O <sub>3</sub>                                | 1.9574     | 2.0094   | 0.1707        | 0.051511       |
| <b>H<sub>2</sub>O<sub>2</sub></b>             | 4.0561     | 4.4213   | <b>0.0375</b> | <b>0.10674</b> |
| Metaldehyde inlet                             | 0.39409    | 0.38774  | 0.5551        | 0.010371       |
| Turbidity inlet                               | 0.24599    | 0.24108  | 0.6243        | 0.006474       |
| UV254 Abs inlet                               | 1.6058     | 1.6325   | 0.2074        | 0.042258       |
| DOC inlet                                     | 3.2348     | 3.4428   | 0.0725        | 0.085127       |
| UV254 Abs post AOP                            | 0.000397   | 0.000387 | 0.9834        | 1.05E-05       |
| DOC post AOP                                  | 2.0101     | 2.0666   | 0.159         | 0.052899       |

**Table C-6** Sequential DistLM test of the predictors explaining net THMFP contribution

| Variable                                      | SS (trace) | Pseudo-F | P      | Prop.    | Cumul.  | res.df |
|-----------------------------------------------|------------|----------|--------|----------|---------|--------|
| H <sub>2</sub> O <sub>2</sub>                 | 4.0561     | 4.4213   | 0.0396 | 0.10674  | 0.10674 | 37     |
| DOC inlet                                     | 3.3022     | 3.8796   | 0.0532 | 0.0869   | 0.19364 | 36     |
| UV254 Abs post AOP                            | 2.8949     | 3.6516   | 0.061  | 0.076181 | 0.26982 | 35     |
| O <sub>3</sub>                                | 3.4747     | 4.8673   | 0.0428 | 0.091439 | 0.36126 | 34     |
| DOC post AOP                                  | 2.0314     | 3.0141   | 0.0886 | 0.053457 | 0.41472 | 33     |
| Turbidity inlet                               | 1.0844     | 1.6403   | 0.2086 | 0.028538 | 0.44326 | 32     |
| H <sub>2</sub> O <sub>2</sub> /O <sub>3</sub> | 0.20694    | 0.30622  | 0.5716 | 0.005446 | 0.4487  | 31     |
| UV254 Abs inlet                               | 0.1559     | 0.22493  | 0.6406 | 0.004103 | 0.4528  | 30     |
| Metaldehyde inlet                             | 2.5829     | 4.1133   | 0.0542 | 0.067972 | 0.52078 | 29     |
| Flow rate                                     | 2.1179     | 3.6849   | 0.061  | 0.055734 | 0.57651 | 28     |

- H<sub>2</sub>O<sub>2</sub>/UV sub process

**Table C-7** Individual influence of predictors on net THMFP contribution with  $n=18$  residual degrees of freedom according to the DistLM marginal test

| Variable                                                       | SS (trace) | Pseudo-F | P             | Prop.          |
|----------------------------------------------------------------|------------|----------|---------------|----------------|
| O <sub>3</sub>                                                 | 0.23358    | 0.22404  | 0.6554        | 0.012294       |
| H <sub>2</sub> O <sub>2</sub>                                  | 0.0030564  | 0.002896 | 0.9598        | 0.00016086     |
| H <sub>2</sub> O <sub>2</sub> /O <sub>3</sub>                  | 0.45059    | 0.43724  | 0.5323        | 0.023715       |
| <b>Metaldehyde inlet</b>                                       | 38.762     | 46.134   | <b>0.0362</b> | <b>0.20401</b> |
| UV                                                             | 0.25148    | 0.24144  | 0.64          | 0.013236       |
| <b>Turbidity post O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub></b> | 44.093     | 54.396   | <b>0.0368</b> | <b>0.23207</b> |
| UV254 Abs post O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub>   | 0.42277    | 0.40963  | 0.5293        | 0.022251       |
| DOC post O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub>         | 0.27709    | 0.26639  | 0.624         | 0.014584       |

**Table C-8** Sequential DistLM test of the predictors explaining net THMFP contribution

| Variable                                                       | SS (trace) | Pseudo-F | P             | Prop.         | Cumul.  | res.df |
|----------------------------------------------------------------|------------|----------|---------------|---------------|---------|--------|
| <b>Turbidity post O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub></b> | 4.4093     | 5.4396   | <b>0.0353</b> | <b>0.2320</b> | 0.23207 | 18     |
| Metaldehyde inlet                                              | 1.3105     | 1.6775   | 0.2197        | 0.0689        | 0.30104 | 17     |
| DOC post O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub>         | 2.162      | 3.1113   | 0.1009        | 0.1137        | 0.41483 | 16     |
| O <sub>3</sub>                                                 | 1.5435     | 2.4181   | 0.138         | 0.0812        | 0.49607 | 15     |
| UV                                                             | 0.64499    | 1.0112   | 0.3297        | 0.0339        | 0.53001 | 14     |
| H <sub>2</sub> O <sub>2</sub> /O <sub>3</sub>                  | 0.25793    | 0.38667  | 0.5515        | 0.0135        | 0.54359 | 13     |
| UV254 Abs post O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub>   | 0.002396   | 0.003317 | 0.955         | 0.0001        | 0.54372 | 12     |
| H <sub>2</sub> O <sub>2</sub>                                  | 0.001114   | 0.001413 | 0.9694        | 5.9E-05       | 0.54377 | 11     |

## C.2 Net HAAFP contribution after AOP

- UV/ H<sub>2</sub>O<sub>2</sub>

**Table C-9** Individual influence of predictors on net HAAFP contribution with  $n=21$  residual degrees of freedom according to the DistLM marginal test

| Variable                      | SS (trace) | Pseudo-F | P      | Prop.      |
|-------------------------------|------------|----------|--------|------------|
| Flow rate                     | 0.018638   | 0.017806 | 0.8973 | 0.00084718 |
| H <sub>2</sub> O <sub>2</sub> | 0.83323    | 0.82666  | 0.3683 | 0.037874   |
| Metaldehyde inlet             | 0.27858    | 0.26933  | 0.6147 | 0.012663   |
| UV                            | 0.54305    | 0.53149  | 0.4892 | 0.024684   |
| Turbidity inlet               | 2.004      | 21.046   | 0.1723 | 0.091089   |
| UV254 Abs inlet               | 15.266     | 15.658   | 0.2253 | 0.06939    |
| DOC inlet                     | 0.074921   | 0.07176  | 0.788  | 0.0034055  |
| UV254 Abs post AOP            | 0.091652   | 0.087852 | 0.7665 | 0.004166   |
| DOC post AOP                  | 0.27176    | 0.26265  | 0.6079 | 0.012353   |

**Table C-10** Sequential DistLM test of the predictors explaining net HAAFP contribution

| Variable                      | SS (trace) | Pseudo-F | P      | Prop.    | Cumul.   | res.df |
|-------------------------------|------------|----------|--------|----------|----------|--------|
| Turbidity inlet               | 2.004      | 2.1046   | 0.1626 | 0.091089 | 0.091089 | 21     |
| UV254 Abs inlet               | 2.938      | 3.4447   | 0.082  | 0.13355  | 0.22463  | 20     |
| DOC post AOP                  | 0.70629    | 0.82068  | 0.3809 | 0.032104 | 0.25674  | 19     |
| H <sub>2</sub> O <sub>2</sub> | 0.93103    | 1.0868   | 0.3152 | 0.042319 | 0.29906  | 18     |
| UV254 Abs post AOP            | 0.25484    | 0.28567  | 0.6097 | 0.011584 | 0.31064  | 17     |
| DOC inlet                     | 0.16193    | 0.17268  | 0.6907 | 0.007361 | 0.318    | 16     |
| Flow rate                     | 0.041116   | 0.041218 | 0.848  | 0.001869 | 0.31987  | 15     |
| UV                            | 0.04036    | 0.037865 | 0.8313 | 0.001835 | 0.32171  | 14     |

- O<sub>3</sub>/H<sub>2</sub>O<sub>2</sub> + H<sub>2</sub>O<sub>2</sub>/UV

**Table C-11** Individual influence of predictors on net HAAFP contribution with  $n=23$  residual degrees of freedom according to the DistLM marginal test

| Variable                                        | SS (trace) | Pseudo-F | P             | Prop.          |
|-------------------------------------------------|------------|----------|---------------|----------------|
| <b>H<sub>2</sub>O<sub>2</sub>/O<sub>3</sub></b> | 8.9524     | 13.684   | <b>0.0018</b> | <b>0.37302</b> |
| O <sub>3</sub>                                  | 1.8137     | 1.8802   | 0.1827        | 0.075572       |
| H <sub>2</sub> O <sub>2</sub>                   | 1.4117     | 1.4375   | 0.2399        | 0.058822       |
| <b>Metaldehyde inlet</b>                        | 9.531      | 15.15    | <b>0.0016</b> | <b>0.39712</b> |
| UV                                              | 0.43903    | 0.42858  | 0.5206        | 0.018293       |
| <b>Turbidity inlet</b>                          | 11.905     | 22.638   | <b>0.0002</b> | <b>0.49603</b> |
| <b>UV254 Abs inlet</b>                          | 4.2818     | 4.9945   | <b>0.0357</b> | <b>0.17841</b> |
| <b>DOC inlet</b>                                | 9.0261     | 13.864   | <b>0.001</b>  | <b>0.37609</b> |
| <b>UV254 Abs post AOP</b>                       | 4.4615     | 5.2518   | <b>0.0307</b> | <b>0.18589</b> |
| DOC post AOP                                    | 1.0626     | 1.0655   | 0.3067        | 0.044274       |

**Table C-12** Sequential DistLM test of the predictors explaining net HAAFP contribution

| Variable                                        | SS (trace) | Pseudo-F | P             | Prop.          | Cumul.  | res.df |
|-------------------------------------------------|------------|----------|---------------|----------------|---------|--------|
| <b>Turbidity inlet</b>                          | 11.905     | 22.638   | <b>0.0001</b> | <b>0.49603</b> | 0.49603 | 23     |
| <b>H<sub>2</sub>O<sub>2</sub>/O<sub>3</sub></b> | 2.8207     | 6.6909   | <b>0.0159</b> | <b>0.11753</b> | 0.61356 | 22     |
| UV254 Abs post AOP                              | 1.9552     | 5.6096   | 0.0299        | 0.081465       | 0.69503 | 21     |
| UV                                              | 1.1713     | 3.8105   | 0.0711        | 0.048806       | 0.74383 | 20     |
| O <sub>3</sub>                                  | 0.56108    | 1.9081   | 0.1748        | 0.023379       | 0.76721 | 19     |
| H <sub>2</sub> O <sub>2</sub>                   | 0.38814    | 1.3439   | 0.2601        | 0.016172       | 0.78338 | 18     |
| Metaldehyde inlet                               | 0.3418     | 1.1963   | 0.2878        | 0.014242       | 0.79763 | 17     |
| UV254 Abs inlet                                 | 0.3517     | 1.249    | 0.2789        | 0.014654       | 0.81228 | 16     |
| DOC post AOP                                    | 0.99573    | 4.2558   | 0.0555        | 0.041489       | 0.85377 | 15     |

- O<sub>3</sub>/H<sub>2</sub>O sub process

**Table C-13** Individual influence of predictors on net HAAFP contribution with  $n=21$  residual degrees of freedom according to the DistLM marginal test

| Variable                                      | SS (trace) | Pseudo-F | P             | Prop.          |
|-----------------------------------------------|------------|----------|---------------|----------------|
| Flow rate                                     | 0.097202   | 0.093196 | 0.7674        | 0.004418       |
| H <sub>2</sub> O <sub>2</sub> /O <sub>3</sub> | 2.7875     | 3.0468   | 0.0974        | 0.1267         |
| O <sub>3</sub>                                | 0.56366    | 0.55218  | 0.4633        | 0.025621       |
| H <sub>2</sub> O <sub>2</sub>                 | 0.69771    | 0.68781  | 0.4169        | 0.031714       |
| <b>Metaldehyde inlet</b>                      | 6.5287     | 8.8617   | <b>0.0086</b> | <b>0.29676</b> |
| <b>Turbidity inlet</b>                        | 4.5019     | 5.4029   | <b>0.0307</b> | <b>0.20463</b> |
| <b>UV254 Abs inlet</b>                        | 6.5901     | 8.9807   | <b>0.0075</b> | <b>0.29955</b> |
| <b>DOC inlet</b>                              | 8.3656     | 12.885   | <b>0.0025</b> | <b>0.38026</b> |
| UV254 Abs post AOP                            | 0.10197    | 0.097787 | 0.754         | 0.004635       |
| <b>DOC post AOP</b>                           | 7.3889     | 10.62    | <b>0.0046</b> | <b>0.33586</b> |

**Table C-14** Sequential DistLM test of the predictors explaining net HAAFP contribution

| Variable                                      | SS (trace) | Pseudo-F | P             | Prop.          | Cumul.  | res.df |
|-----------------------------------------------|------------|----------|---------------|----------------|---------|--------|
| <b>DOC inlet</b>                              | 8.3656     | 12.885   | <b>0.0026</b> | <b>0.38026</b> | 0.38026 | 21     |
| <b>DOC post AOP</b>                           | 2.4477     | 4.3761   | <b>0.0488</b> | <b>0.11126</b> | 0.49152 | 20     |
| Turbidity inlet                               | 2.0844     | 4.3511   | 0.0508        | 0.094747       | 0.58626 | 19     |
| H <sub>2</sub> O <sub>2</sub>                 | 1.2109     | 2.762    | 0.1104        | 0.05504        | 0.6413  | 18     |
| UV254 Abs post AOP                            | 1.5548     | 4.1713   | 0.0567        | 0.070672       | 0.71197 | 17     |
| H <sub>2</sub> O <sub>2</sub> /O <sub>3</sub> | 1.4075     | 4.5688   | 0.0485        | 0.063977       | 0.77595 | 16     |
| O <sub>3</sub>                                | 0.90754    | 3.3851   | 0.0805        | 0.041252       | 0.8172  | 15     |
| UV254 Abs inlet                               | 0.15024    | 0.54331  | 0.4753        | 0.006829       | 0.82403 | 14     |
| Flow rate                                     | 0.036709   | 0.12445  | 0.7341        | 0.001669       | 0.8257  | 13     |

- H<sub>2</sub>O<sub>2</sub>/UV sub process

**Table C-15** Individual influence of predictors on net HAAFP contribution with  $n=11$  residual degrees of freedom according to the DistLM marginal test

| Variable                                                     | SS (trace) | Pseudo-F | P             | Prop.          |
|--------------------------------------------------------------|------------|----------|---------------|----------------|
| O <sub>3</sub>                                               | 0.32409    | 0.30533  | 0.5922        | 0.027008       |
| H <sub>2</sub> O <sub>2</sub>                                | 0.61259    | 0.59175  | 0.4493        | 0.051049       |
| H <sub>2</sub> O <sub>2</sub> /O <sub>3</sub>                | 0.1324     | 0.12272  | 0.7327        | 0.011033       |
| <b>Metaldehyde inlet</b>                                     | 58.377     | 10.421   | <b>0.0087</b> | <b>0.48648</b> |
| <b>UV</b>                                                    | 46.241     | 68.962   | <b>0.0223</b> | <b>0.38534</b> |
| Turbidity post O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> | 0.50499    | 0.48324  | 0.4979        | 0.042082       |
| UV254 Abs post O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> | 32.975     | 4.168    | 0.0649        | 0.27479        |
| DOC post O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub>       | 10.057     | 10.062   | 0.3316        | 0.083806       |

**Table C-16** Sequential DistLM test of the predictors explaining net HAAFP contribution

| Variable                                                     | SS (trace) | Pseudo-F | P             | Prop.          | Cumul. | res.df |
|--------------------------------------------------------------|------------|----------|---------------|----------------|--------|--------|
| <b>Metaldehyde inlet</b>                                     | 5.8377     | 10.421   | <b>0.0082</b> | <b>0.48648</b> | 0.4864 | 11     |
| <b>UV</b>                                                    | 3.3978     | 12.291   | <b>0.0068</b> | <b>0.28315</b> | 0.7696 | 10     |
| O <sub>3</sub>                                               | 0.30226    | 1.1048   | 0.3183        | 0.025188       | 0.7948 | 9      |
| Turbidity post O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> | 0.19083    | 0.67212  | 0.4291        | 0.015902       | 0.8107 | 8      |
| DOC post O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub>       | 0.22802    | 0.78114  | 0.4091        | 0.019002       | 0.8297 | 7      |
| UV254 Abs post O <sub>3</sub> /H <sub>2</sub> O <sub>2</sub> | 0.16898    | 0.54091  | 0.4917        | 0.014082       | 0.8438 | 6      |
| H <sub>2</sub> O <sub>2</sub> /O <sub>3</sub>                | 0.61739    | 2.4559   | 0.1755        | 0.051449       | 0.8952 | 5      |
| H <sub>2</sub> O <sub>2</sub>                                | 0.34482    | 1.5121   | 0.2897        | 0.028735       | 0.9239 | 4      |